

Stormwater Management Report

# Brock Street and Nelkydd Lane, Township of Uxbridge, ON

---



Prepared for Westlane Development Group Ltd.  
by IBI Group  
September 15, 2021

# Document Control Page

---

<b>CLIENT:</b>	Westlane Development Group Ltd.
<b>PROJECT NAME:</b>	
<b>REPORT TITLE:</b>	Brock Street and Nelkydd Lane, Township of Uxbridge, ON
<b>IBI REFERENCE:</b>	
<b>VERSION:</b>	
<b>DIGITAL MASTER:</b>	\\caneast.ibigroup.com\J\TO\2018-0302\400_Tchncl\70_Rprts\FSR SWM August 2021
<b>ORIGINATOR:</b>	Roy Jonson, B.Eng., P.Eng., MA.Sc.
<b>REVIEWER:</b>	Benny Hon, P.Eng.
<b>AUTHORIZATION:</b>	Neil Short, B.Eng.
<b>CIRCULATION LIST:</b>	
<b>HISTORY:</b>	1.0 Final Report Issued for Zoning Approval
	2.0 Final Report Issued for Zoning Approval
	3.0 Final Report Issued for Zoning Approval

# Table of Contents

---

<b>1</b>	<b>Introduction</b> .....	<b>1</b>
1.1	Background.....	1
1.2	Site Description.....	1
<b>2</b>	<b>Site Proposal</b> .....	<b>2</b>
<b>3</b>	<b>Stormwater Management and Drainage</b> .....	<b>3</b>
3.1	Design Criteria.....	3
3.2	Existing Conditions.....	3
3.3	Proposed Storm Drainage System.....	4
3.4	Stormwater Management Controls.....	5
3.4.1	Quantity Controls.....	5
3.4.2	Stormwater Quality Control.....	6
3.4.3	Water Balance.....	6
3.4.4	Volume Control.....	7
3.4.5	Erosion Control.....	7
3.4.6	Phosphorous Loading.....	7
3.4.7	Low Impact Development.....	7
3.4.8	100 Year Emergency Overland Flow Route.....	8
3.4.9	100 Year Capture Analysis.....	8
3.4.10	Channel Capacity Assessment.....	8
<b>4</b>	<b>Site Grading</b> .....	<b>9</b>
4.1	Existing Grades.....	9
4.2	Proposed Grades.....	9
<b>5</b>	<b>Design Details of Erosion and Sediment Control Measures</b> .....	<b>10</b>
5.1	Sediment Control Fence/Construction Fence.....	10
5.2	Construction Mud Mat.....	10
5.3	Inlet Protection Devices.....	10
5.4	Rock Check Dams, Sediment Traps and Swales.....	10
<b>6</b>	<b>Record Keeping and Maintenance Procedures</b> .....	<b>11</b>
6.1	General Inspection and Maintenance.....	11

## Table of Contents (continued)

---

6.2	Silt Fence Inspection and Maintenance .....	11
6.3	Inlet Protection Devices Inspection and Maintenance .....	12
6.4	Mud Matt Inspection and Maintenance .....	12
<b>7</b>	<b>Construction Management .....</b>	<b>13</b>
7.1	Construction Vehicle Access .....	13
7.2	Street Cleaning .....	13
7.3	Health and Safety .....	13
<b>8</b>	<b>Construction and Long Term Dewatering .....</b>	<b>13</b>
<b>9</b>	<b>Conclusions and Recommendations .....</b>	<b>14</b>
	Stormwater Management .....	14
	Site Grading .....	14

### LIST OF TABLES

<b>Table 3.1</b>	<b>Pre-Development Drainage Parameters .....</b>	<b>3</b>
<b>Table 3.2</b>	<b>Pre-Development Peak Flows .....</b>	<b>4</b>
<b>Table 3.3</b>	<b>Post-Development Drainage Parameters .....</b>	<b>5</b>
<b>Table 3.4</b>	<b>Post Development Peak Flows .....</b>	<b>5</b>
<b>Table 3.5</b>	<b>Additional Onsite Treatment Units .....</b>	<b>6</b>

### LIST OF FIGURES

Figure FIG 1	Location Plan .....	Following Report
Figure FIG 2	Aerial Map .....	Following Report
Figure DAP-1	Pre-Development Drainage Area Plan .....	Appendix B
Figure DAP-2	Post-Development Drainage Area Plan .....	Appendix B
Figure DAP-3	100 Year Emergency Overland Flow Plan .....	Appendix B
Figure DAP-4	100 Year Capture Area Plan .....	Appendix B

# Table of Contents (continued)

---

## LIST OF DRAWINGS

SG-01	Site Grading Plan.....	Appendix C
SS-01	Site Servicing Plan.....	Appendix C
XS-01	Cross Sections.....	Appendix C
XS-02	Cross Sections.....	Appendix C
EC-01	Erosion Control Plan Stage 1 .....	Appendix C
EC-02	Erosion Control Plan Stage 2 .....	Appendix C
EC-03	Erosion Control Plan Stage 3 .....	Appendix C
EC-04	Erosion Control Details .....	Appendix C
DD-01	Detail Design .....	Appendix C
DD-02	Details .....	Appendix C

## APPENDICES

Appendix A	Background Information
Appendix B	Stormwater Management Calculations
Appendix C	Engineering Plans

# 1 Introduction

## 1.1 Background

IBI Group Professional Services (Canada) Inc. (IBI) was retained by Westlane Development Group Ltd. to prepare a Stormwater Management Report in support of Site Plan Application for a proposed residential development located on the south side of Brock Street East, east of Nelkydd Lane within the Township of Uxbridge (the “Town”), in the Region of Durham (the “Region”). The proposed development is comprised of 60 townhouses. The purpose of this report is to provide site-specific information for the Town and the Region to review with respect to the infrastructure required to support the proposed development regarding storm drainage, water supply, and sanitary discharge. More specifically, the report will present the following:

- Evaluate on a preliminary basis the Stormwater Management (SWM) opportunities and constraints, including:
  - Calculation of allowable and proposed runoff rates for the development;
  - Evaluate suitable methods for attenuation and treatment of stormwater runoff;
  - Develop and propose on-site control measures and examine theoretical performance; and,
  - Demonstrate compliance of the proposed stormwater control measures with the Town, the conservation authorities, Ministry of Environment, Conservation and Parks (MECP) and LSRCA’s Technical Guidelines.

The following documents were reviewed during the preparation of this report:

- Stormwater Management Pond, Prepared by Vincent and Associates Ltd., Drawing Number S SW-1 and SW-2, dated July 2000;
- Geo Morphix Technical Design Brief: Tributary of Uxbridge Creek and Design Drawing GEO-1, XS-1, and DET-1, dated October 2020;
- Hydrogeological Assessment and Water Balance Study by WSP dated March, 2021;
- Summary of Infiltration Tests- Westlane Development Group Ltd. by WSP dated July 26, 2018; and,
- LSRCA Technical Guidelines for SWM Submissions, dated 2016.
- Road Stormwater Conveyance Report Brock Street and Herrema Boulevard, Township of Uxbridge, Prepared by Cole Engineering, dated September 2019 [Stormwater Conveyance Report]

## 1.2 Site Description

The subject site is located south of Brock Street East and east of Nelkydd Lane in the Town, within the Region. The existing site is approximately 2.61ha in size and is comprised of two (2) different properties, each occupied by a residential dwelling. The legal description is as follows: Part of Lot 30, Concession 7, and Part of Lots 55, 56, 57, 58, 59, 60 and Centre Street, Plan H50061, Township of Uxbridge.

A drainage ditch runs through each of the existing properties, carrying flows from the existing storm water management detention facility to the west, to a 1000 mm ø culvert on Brock Street East.

The site is bound by an open space area to the east, Brock Street East to the north, a wetland to the west, and a residential subdivision to the south. Refer to **Figures FIG 1** and **Figure FIG 2** following the report for location plan and aerial map of the site location.

## 2 Site Proposal

The proposed development consists of a townhouse and semi-detached development with a 10.0m wide and 15.0m wide headwater drainage feature. The development is approximately 2.33 ha in size. The access to the townhouses will be through a private entrance from Brock Street East. The headwater drainage feature is approximately 0.41ha in size and is comprised of a 10.0m wide headwater drainage feature along the south property line and a 15.0m headwater drainage feature along east property boundary. The proposed headwater drainage feature will carry flows from the existing storm water management detention facility to the west of the property, to a proposed 1200 mm ø culvert on Brock Street East. Refer to Site Plan in **Appendix A** for details.

## 3 Stormwater Management and Drainage

### 3.1 Design Criteria

As previously mentioned, the proposed SWM scheme is proposed to meet the MOECP SWMPD Manual (2003), LSRCA's Technical Guidelines and the Town standards. The following design criteria will be applied:

- Quality Control: Level 1 Enhanced Level protection, i.e., annually 80% TSS removal, as defined in the MOECP SWMPD Manual (2003);
- Quantity Control: Post-development peak flows for all storm events up to and including the 100-year event should be controlled to pre-development rates. The Town's IDF data to be used for analysis;
- Water Balance: Post-development to Pre-development water balance; stormwater runoff volumes will be controlled and the post-construction runoff volume shall be captured and retained / treated on site from a 25 mm rainfall event from the total impervious area.
- Volume Control: Best efforts to achieve 25 mm and 5 mm minimum requirement for sites with restrictions;
- Erosion Control: LSRCA will require that the runoff from a 25 mm design storm (4 hour, Chicago distribution) be detained and released over a period of at least 24 hours; and,
- Phosphorus Removal: Minimum 80% Post-development phosphorus removal Lake Simcoe Phosphorus Offsetting Policy (LSPOP) and 90% or cash-in-lieu (Uxbridge Urban Area Stormwater Management Plan) for post-development. Best efforts to achieve 80% removal are encouraged and cash in lieu is required for any remaining phosphorus loading to Lake Simcoe. Any phosphorus load above zero phosphorus the developer or proponent shall be require to provide phosphorus offsetting to the LSRCA. Phosphorus offsetting will include the following:
  - Offset Ratio = 2.5:1;
  - Offset Value – \$35,000/kg/year; and,
  - Offset Calculation = (ratio (2.5) x P deficit in kg x \$ 35,000)

### 3.2 Existing Conditions

Under existing conditions, the subject site (2.61ha) is currently occupied by two (2) residential dwelling, 216 and 226 Brock Street East, in the Town. Major flows from the site are conveyed overland into a naturalized drainage ditch that runs the length of the site. The existing ditch currently conveys uncontrolled discharge from the subject site (A1 Pre) and external drainage area (EXT1) located to the south of the site. In addition, controlled discharge is conveyed within the drainage ditch from the existing Coral Creek Homes stormwater management pond located adjacent to the site (POND). Flow conveyed within the existing drainage ditch is outlet into the roadside ditch located parallel to Brock Street East before being conveyed downstream. The existing drainage area plan is illustrated in **Figure DAP-1** provided in **Appendix B.2**.

Composite runoff coefficients were calculated for each pre-development drainage area using runoff coefficients values of 0.25 for pervious and 0.95 for impervious land use types. A time of concentration of 13 minutes was calculated using the Uplands Method. Input parameters used to model the ore-development conditions are summarized in **Table 3.1**.

**Table 3.1 Pre-Development Drainage Parameters**



Catchment ID	Drainage Area (ha)	Runoff Coefficient ('C')	Tc (Min)
A1 Pre	2.61	0.30	13
EXT1	0.60	0.45	10

Rational Method calculations were performed using the Town's Intensity-Duration-Frequency (IDF) data in order to determine the peak runoff rates resulting from the pre-development site conditions. Controlled release rates from the existing stormwater pond were provided on Drawing SW-1 by Vincent & Associates (July 2000). The peak runoff rates for Drainage Area A1 Pre provided in **Table 3.2** below will be used as the target release rates from the subject site during each storm event. Detailed pre-development flow calculations are included in **Appendix B.2**.

**Table 3.2 Pre-Development Peak Flows**

Catchment Id	Catchment Description	Discharge Location	Peak Flows (L/S)		
			2-Year Storm Event	5-Year Storm Event	100-Year Storm Event
A1 Pre	Proposed Site Development	Discharge into ditch along Brock Street East	140.9	196.4	458.3
EXT 1	Uncontrolled area from Coral Subdivision	Discharge into naturalized drainage feature	57.4	80	187.4
Pond	Controlled Flows from Coral Creek Homes Pond		70	160	860
<b>Total Flow</b>			<b>268.3</b>	<b>436.3</b>	<b>1505.7</b>

### 3.3 Proposed Storm Drainage System

Based on the proposed grading scheme of the site, the new development will comprise of a total of three (3) internal drainage areas. Drainage Area A1 Post will discharge uncontrolled into the proposed naturalized headwater drainage feature located along the eastern boundary of the site. Drainage Area A2 Post will also discharge at uncontrolled rate onto Brock Street East along the northern boundary of the development. The majority of the subject site, Drainage Area A3 Post, will be discharged at a controlled rate to a storm sewer under Brock Street East that drains to a naturalized channel to the north. The external drainage EXT1 and POND are not accounted for in the post-development storm drainage plans and calculations as peak flow contributions conveyed in the drainage feature to Brock Street East remain unchanged from these drainage areas in pre- and post-development conditions.

Composite runoff coefficients were calculated for each drainage area using a runoff coefficient of 0.95 for impervious areas and 0.25 for pervious areas. Post-development drainage areas and runoff coefficients are illustrated in **Figure DAP-2** found in **Appendix B.3**. The relevant drainage parameter of the post-development drainage areas are provided in **Table 3.3** on the following page.

**Table 3.3 Post-Development Drainage Parameters**

Catchment	Drainage Area (Ha)	Discharge Location	Runoff Coefficient ('C')	Tc (Min)
A1 Post	0.40	Uncontrolled to naturalized drainage feature along south and east boundary	0.25	10
A2 Post	0.11	Uncontrolled to Brock Street	0.50	10
A3 Post	2.10	Controlled discharge to the storm sewer crossing Brock Street	0.69	10
EXT 1	0.60	Uncontrolled to naturalized drainage feature along south boundary of Site	0.45	10
Pond	-	Controlled Flows from Coral Creek Homes Pond drains to naturalized drainage feature along south boundary of Site	-	-

### 3.4 Stormwater Management Controls

#### 3.4.1 Quantity Controls

The post-development release rates to Brock Street East will be controlled to pre-development conditions as outlined in **Section 3.4.2**. On-site SWM controls will be required to ensure that quantity, quality, water balance, and minimum phosphorous removal criteria are met. Using the Town's intensity-duration-frequency (IDF) data, Modified Rational Method calculations were undertaken to determine the maximum storage and subsequent post-development release rates from the subject site. Results for the 2-, 5- and 100-year storm are provided in **Table 3.4** below. The detailed post-development quantity control calculations are provided in **Appendix B.3**.

**Table 3.4 Post Development Peak Flows**

Storm Event	Target Release Rate (L/S)	Uncontrolled Release Rate (L/S)	Controlled Release Rate (L/S)	Total Required Storage Volume (M <sup>3</sup> )	Provided Storage Volume (M <sup>3</sup> )	Total Site Release Rate (L/S)
2-Year	141	37	102	132	497	139
5-Year	196	52	113	214		164
100-Year	367	97	140	488		237

A 75mm  $\varnothing$  orifice plate and 250mm  $\varnothing$  orifice plate is proposed to be installed on the downstream invert of MH9 in order to control post development peak flows to the target pre-development rates prior to discharge to Brock Street S. Detailed orifice sizing calculations are provided in **Appendix B**. Onsite storage will be provided through the use of oversized box culverts, and pipe storage which will provide a at a minimum a total available storage volume of 497 m<sup>3</sup>. The above stormwater management strategy has been designed to over-control the captured areas of the

site to compensate for the uncontrolled runoff from Drainage Area A2 Post to Brock Street South.

The proposed stormwater management system in conjunction with the proposed grading and servicing design retains enough runoff volume on site to reduce the post-development peak flows from the entire site to the pre-development peak flow targets. All detailed calculations related to quantity control can be found in **Appendix B.3**.

### 3.4.2 Stormwater Quality Control

Stormwater treatment must meet Enhanced (Level 1) Protection as defined by the Ministry of Environment, Conservation and Parks (MOECP) 2003 Stormwater Management Planning and Design (SWMPD) manual. Quality control is to be provided by a combination of rooftop and landscaped areas, in addition to a Jellyfish unit to treat flows from the asphalt areas prior to discharging into the culvert across Brock Street East. Runoff from rooftop and landscaped areas is considered inherently 'clean' as these do not contain oil and grit.

A Jellyfish Unit, JF8-8-2 (or approved equivalent) will be used to provide the required TSS removal to meet MOECP standards. Treatment unit sizing parameters are summarized in **Table 3.5** below and sizing results are provided in **Appendix B.4**.

**Table 3.5 Additional Onsite Treatment Units**

Drainage Area (Ha)	Percent Impervious	Model	Effective TSS Removal
2.1	62.8	JF8-8-2	80%

The combination of clean rooftop and landscaped areas and the proposed Jellyfish Unit will provide an overall TSS removal of 80% for the subject site.

### 3.4.3 Water Balance

The LSRCA's Stormwater Management Guidelines require post-development infiltration volumes to best match pre-development levels on an annual basis.

A water balance analysis has been completed by WSP in March 2021 and it was found the annual pre-development infiltration volume is 6,994m<sup>3</sup>. The total on-site infiltration is reduced by approximately 20% or 1,385 m<sup>3</sup>/year when compared to the pre-development scenario. Refer to the WSP report for detailed information found within **Appendix A**. Due to high groundwater levels the options for locations of infiltration are limited. To meet this requirement, a 7.5 m wide infiltration trench is proposed just to the south of Street B along the full length of the rear yards which will provide an annual infiltrated volume of 2200m<sup>3</sup>/year. An infiltration test was completed by WSP in the area of the proposed trench resulting in a rate of 34.5mm/hr that has been used in designing the trench. This has a draw down of 8.7 hours (0.3 m/ 34.5 mm/hr = 8.7 hrs). The proposed infiltration trench will strictly receive runoff from inherently clean roof and landscaped areas therefore only clean water will be infiltrated. Groundwater elevations in this area are approximately at existing grade level. Thus, the site was filled and the trench was made very shallow, 0.3m of clear stone beneath the underdrain.

The online wet meadows have conservatively not been accounted for in the water balance but do provide some surface storage that can be infiltrated. Water balance assessment calculations are provided in **Appendix B.5**. In addition to the above top soil on all landscape areas will be increased as a best efforts approach.

Cash in lieu will be explored as a method to compensate for the infiltration deficit.

### 3.4.4 Volume Control

As per LSRCA SWM Guidelines, stormwater runoff volumes will be controlled and the post-construction runoff volume shall be captured and retained / treated on site from a 25 mm rainfall event from the total impervious area.

As noted in Section 3.4.3 above, best efforts have been pursued to implement volume control on site. Due to high groundwater levels LID locations are limited to the already proposed locations. Consequently, providing retention of the 25 mm or 12.5 mm events are infeasible.

As per LSRCA requirements for sites with restrictions, 5 mm retention is required per impervious area on site. The volume required for volume control is 68 m<sup>3</sup>. The infiltration trench volume of 72 m<sup>3</sup>. Therefore, minimum volume control requirements have been met. In addition to the above topsoil on all landscape areas will be increased to as a best efforts approach.

### 3.4.5 Erosion Control

LSRCA will require that the runoff from a 25 mm design storm (4 hour, Chicago distribution) be detained and released over a period of at least 24 hours. As the outlet structure configuration from a residential site is highly constrained compared with that of a SWM pond, providing extended detention of the 25 mm event is not feasible.

### 3.4.6 Phosphorous Loading

Refer to **Appendix B. 6**. As required in the 2009 Lake Simcoe Protection Plan (LSPP) implemented by the LSRCA, new developments within the Lake Simcoe Watershed must adopt Best Management Practices (BMPs) and LID techniques in order to achieve sustainable development practices that will provide 80% phosphorus removal. The Uxbridge Urban Area Stormwater Management Plan requires 90% Phosphorous removal from the development or cash-in-lieu for any deficiency.

A phosphorous loading analysis was completed for the subject site using the MOECP Lake Simcoe Phosphorous Loading Development Tool. Pre-development conditions were simulated by applying a land use type of 'Hay-Pasture' for the large undeveloped field which makes up the majority of the site and 'Low-intensity Development' for the single residential lot located in the northeast corner.

The post-development conditions were simulated by applying a land use type of 'High Intensity Development' for the residential component of the site and 'Open Water' for the proposed headwater drainage feature located along the west boundary of the site. The post-development annual phosphorus loading was estimated to be 3.02 kg/year. In applying the proposed LIDs for the subject site, which includes an enhanced headwater drainage feature and a treatment train approached including infiltration galleries, underground storage and a Jellyfish treatment unit, the mitigated annual phosphorous loading was significantly reduced by 66% to 1.03 kg/year in post-development conditions.

Maximum efforts have been made and due to stormwater management constraints on-site, a 100% removal cannot be achieved. As such, the owner will provide cash-in-lieu for the phosphorous removal deficiency. Based on the deficit, the contribution totals **\$122,138.63**.

### 3.4.7 Low Impact Development

To meet requirements for LSCRA, best management practices have been proposed. These design considerations include infiltration trenches and enhanced grassed swales.

### **3.4.8 100 Year Emergency Overland Flow Route**

Critical Overland Flow route locations are shown on **Figure DAP3**. The locations have been evaluated to make sure that 100 year unattenuated overland flows can be conveyed through them. Calculations are provided in **Appendix B.7**.

### **3.4.9 100 Year Capture Analysis**

A 100-year capture analysis was performed to ensure that 100 year flows are captured within the controlled drainage area A1 Post. Calculations are provided in **Appendix B.7** and **Figure DAP3** shows the 100-year capture areas.

### **3.4.10 Channel Capacity Assessment**

A hydraulic analysis of the channel adjacent to the Site shows that it has sufficient capacity (~30 m<sup>3</sup>/s ) to convey flows from the Coral Creek Pond. Refer to **Appendix B.8**.

## 4 Site Grading

### 4.1 Existing Grades

The existing site topography generally slopes towards Brook Street East.

The eastern and western drainage patterns slope towards a water drainage feature running through the centre of the site. The drainage feature runs from the south to north, conveying flows from the existing stormwater management facility to the west, towards an existing 1000 mm diameter culvert on Brock Street East. Flows are then conveyed to the existing stormwater management facility to the north.

### 4.2 Proposed Grades

The proposed grading of the site will match existing grades where possible and will provide an emergency overland flow route to Brook Street East located at the north end of the site, similar to the pre-development conditions. The site has been graded in accordance with Town Standards and adheres to road grades of 0.5% -5.0% and lot grades of 2.0% to 5.0% and has been designed such that as much drainage as possible from the townhouse blocks is controlled and conveyed to the proposed 1200 mm  $\varnothing$  pipe on Brook Street East. Grading along the south limit of the site, will be governed by the proposed 10.0m wide headwater drainage feature which will match the grades of the existing residential development. The west property boundary will require grading to integrate the existing berm and match grades of the proposed development. To the west, proposed grades will match grades from the proposed 15.0 m wide headwater drainage feature designed by Geo Morphix. The headwater drainage feature will match existing grades along the east property boundary. To the extent practical, overland flows for events up to and including the 100-year storm design event, will be captured within the site. Overland flows for events exceeding the 100-year design event, will be directed to Brock Street East via the proposed laneways.

## 5 Design Details of Erosion and Sediment Control Measures

The erosion and sediment control measures will be implemented using several BMP measures. The erosion and sediment control measures are outlined below.

### 5.1 Sediment Control Fence/Construction Fence

The temporary sediment control silt fence will be erected around the entire proposed development perimeter as part of the overall ESC Plan as per **Drawing EC-02** and **EC-03**.

### 5.2 Construction Mud Mat

Temporary construction access will be permitted only through Brock Street. Refer to **Drawing EC-02** and **EC-03** for the location of the access route and Mud Mat.

### 5.3 Inlet Protection Devices

Nearby existing catch basins located along Brock Street will be fitted with inlet protection devices to reduce sediment load entering the existing storm system. Refer to **Drawing EC-02** and **EC-03** for the location of the Inlet Protection Devices.

### 5.4 Rock Check Dams, Sediment Traps and Swales

Rock Check dams will be spaced every 0.5 m grade change along interceptor swales. Sediment traps will collect drainage less than 2 ha prior to out letting.

## 6 Record Keeping and Maintenance Procedures

Maintenance of record keeping for all the erosion and sediment control requirements will be conducted by IBI's field representative throughout the duration of the work program.

### 6.1 General Inspection and Maintenance

The minimum general inspection frequency during all construction stages is to be as follows:

- On a weekly basis during active construction;
- Before and after significant\* rainfall events;
- After significant snowmelt events;
- After any extreme weather (e.g. wind storms) which could result in damage to ESC measures;
- Daily during extended rain or snowmelt periods;
- Monthly during inactive periods (> 30 days);
- During or immediately following any spill event;
- Before construction is shut down for the winter to ensure the site is ready for freezing conditions and thaws; and,
- At the end of construction \*A rainfall event should be considered significant when either of the following criteria are met:
  - An event during which  $\geq 15$  mm have been received within 24 hours; or,
  - An event with an intensity of  $\geq 5$ mm/hr and during which at least 10 mm have been received.

All damaged erosion and sediment control measures should be repaired and/or replaced within 48 hours of the inspection or immediately as required.

### 6.2 Silt Fence Inspection and Maintenance

- Inspect the entire length of sediment fence weekly and before and after significant rainfall (see definition in **Section 10.1.2**) or snowmelt events, and keep a record of the inspection;
- Inspect the fence to look for any signs of damage to the geotextile or compromising of the structural integrity of the fence. Ensure the fence has been properly installed as defined under "Design and Installation" section above;
- Remove and properly dispose of sediment before it reaches approximately 30% of the height of the fence, or sooner if not functioning as intended;
- A supply of sediment control fence materials should be kept on-site to allow for quick repairs or the installation of additional fencing as needed;
- Where fence continues to fail on an ongoing basis, consider reinforcing problem areas or replacing with an alternative sediment retention device. If failure is a result of concentrated flows being directed to the fence, consider re-designing surface water flow paths to reduce volumes being directed to the problem area; and,
- Any repair or maintenance needs identified should be repaired within 48 hours or sooner.



### 6.3 Inlet Protection Devices Inspection and Maintenance

- Inspect weekly and before and after significant rainfall or snowmelt events, and keep a record of the inspection;
- Look for any signs that runoff is undermining or otherwise by passing the sediment control measure and repair as needed;
- Remove any sediment accumulation that has reached approximately 30% of the height of the sediment retention barrier and ensure proper disposal;
- For below grade installations, like filter fabric sacks / bags, make sure that it is cleaned out at the frequency specified by the manufacturer / supplier and at a minimum when it reaches 50% accumulation. If there are signs of clogging causing impeded flow through and flooding, clean out immediately;
- Clean and/or replace the device if there is any evidence of clogging significantly impeding flow through and leading to flooding;
- Look for any signs of structural damage to the device. If it is being damaged due to vehicle traffic, consider substituting with a below grade device;
- Any repair or maintenance needs identified should be repaired within 48 hours or sooner; and,
- Ensure the inlet grate is not being unintentionally blocked by the protection device.

### 6.4 Mud Matt Inspection and Maintenance

- Inspect vehicle tracking controls weekly, and before and after significant rainfall or snowmelt events, and keep a record of the inspection;
- Inspect mud mats for excessive sediment accumulation. For rock pads look for signs that the voids have been filled with sediment and replace granular material as needed;
- Clean up any sediment tracked onto public roads at the end of each day;
- Ensure the installation of storm drain inlet protection for inlets in roads that will be subject to street sweeping, since this can sometimes cause additional sediment to be swept into storm drain inlets; and,
- Any repair or maintenance needs identified should be repaired within 48 hours or sooner.

An erosion and sediment control monitoring checklist has been included in **Appendix B.9**.

## 7 Construction Management

**Drawing EC-02** and **EC-03** identifies the access location for construction vehicles, parking and haulage routes in order to ensure minimal disturbance to the existing area.

### 7.1 Construction Vehicle Access

During the excavation and shoring works, the civil contractor's construction vehicles are permitted to enter and leave the development area using only the access to the proposed development via the Mud Matt's.

### 7.2 Street Cleaning

Municipal roads adjacent to the site and those roads that form the haulage route to and from the site shall be left in a broom swept condition at the end of each working day.

### 7.3 Health and Safety

The contractor will provide a comprehensive health and safety plan prior to construction. Everyone working on site shall abide by those health and safety regulations and applicable OHSA regulations.

## 8 Construction and Long Term Dewatering

Construction and long term dewatering is noted in the Hydrogeological Report. Excerpts are included in **Appendix A**.

## 9 Conclusions and Recommendations

Based on our investigation, we conclude and recommend the following:

### Stormwater Management

Based on the above analysis, storage provided within the proposed oversized box culverts and manholes in conjunction with a dual 75mm and 250 mm  $\varnothing$  orifice plate is sufficient to control post-development peak flows to the corresponding pre-development target flows.

Quality control will be provided via inherently 'clean' rooftop and landscaped areas in combination with a Jellyfish treatment unit (or approved equivalent) to achieve the minimum TSS removal of 80%.

Water balance mitigation is to be achieved through the proposed infiltration gallery which will receive clean runoff from the surrounding roof and landscaped areas in addition to small soak away pits located within the meanders of the naturalized headwater drainage feature. As best efforts extra topsoil will also be provided for all landscape areas.

The required phosphorus removal requirements, as outlined in the LSRCA guidelines, will be achieved by an enhanced headwater drainage feature and treatment train approach including underground storage, infiltration and treatment unit.

Results of the analysis provided in this report indicate that the proposed measures will effectively meet the SWM criteria set forth by the City, LSRCA and MOECP.

### Site Grading

The proposed grading of the site will match the existing grades where possible and maintain the existing overland flow routes. To the extent practical, overland flows for events up to and including the 100-year storm design event, will be captured within the site. Overland flows for events exceeding the 100-year design event, will be directed to Brook Street East via the proposed laneways.

Respectfully,



Roy Johnson, P. Eng.  
Senior Water Resources Engineer  
Roy.Johnson@IBIGroup.com



## **APPENDIX A**

### **Background Information**

<b>Appendix A1</b>	<b>Conveyance Report Excerpts</b>
<b>Appendix A2</b>	<b>Conveyance Report Figure Excerpts</b>
<b>Appendix A3</b>	<b>WSP Hydrogeological Report Excerpts</b>
<b>Appendix A4</b>	<b>Geomorphix Report and Drawings</b>
<b>Appendix A5</b>	<b>Coral Creek Pond Drawing</b>

**APPENDIX A1**  
**Conveyance Report Excerpts**

# EVENDALE DEVELOPMENTS LTD.

## ROAD STORMWATER CONVEYANCE REPORT

Brock Street and Herrema Boulevard,  
Township of Uxbridge

Project No.: 2017-0569



# COLE

**COLE ENGINEERING GROUP LTD.**

SEPT 2019

HEAD OFFICE

70 Valleywood Drive Markham, ON L3R 4T5

**T.** 905 940 6161 | 416 987 6161 **F.** 905 940 2064

[www.coleengineering.ca](http://www.coleengineering.ca)

PREPARED BY:

COLE ENGINEERING GROUP LTD.





---

Timothy Louis Ng, P.Eng.  
 Water Resources Engineer  
 Infrastructure Planning

CHECKED BY:

COLE ENGINEERING GROUP LTD.




---

Chaodong Sheng, M.Sc., P.Eng.  
 Senior Water Resources Engineer  
 Infrastructure Planning

AUTHORIZED FOR ISSUE BY:

COLE ENGINEERING GROUP LTD.

A handwritten signature in blue ink, appearing to read "Joe Lasitz".

---

Joe Lasitz  
 Team Leader  
 Urban Development (ICI&T)

**Issues and Revisions Registry**

Identification	Date	Description of issued and/or revision
Final Report	January 2019	1 <sup>st</sup> submission
Final Report	March 2019	2 <sup>nd</sup> submission
Final Report	June 2019	3 <sup>rd</sup> submission
Final Report	Sept 2019	4 <sup>th</sup> submission

**Statement of Conditions**

This Report / Study (the “Work”) has been prepared at the request of, and for the exclusive use of, the Owner / Client, Township of Uxbridge and its affiliates (the “Intended User”). No one other than the Intended User has the right to use and rely on the Work without first obtaining the written authorization of Cole Engineering Group Ltd. and its Owner. Cole Engineering Group Ltd. expressly excludes liability to any party except the Intended User for any use of, and/or reliance upon, the work.

Neither possession of the Work, nor a copy of it, carries the right of publication. All copyright in the Work is reserved to Cole Engineering Group Ltd. The Work shall not be disclosed, produced or reproduced, quoted from, or referred to, in whole or in part, or published in any manner, without the express written consent of Cole Engineering Group Ltd., Township of Uxbridge, or the Owner.



## Table of Contents

<b>1</b>	<b>Introduction</b> .....	<b>1</b>
1.1	Background .....	1
1.2	Subdivision Description and General Assumptions .....	2
<b>2</b>	<b>Stormwater Conveyance Design Criteria</b> .....	<b>2</b>
<b>3</b>	<b>Brock Street Urbanization Changes to Stormwater Conditions</b> .....	<b>2</b>
3.1	Quantity Control to Barton Pond .....	2
3.2	Quantity Control to the Natural Channel.....	4
3.3	Quality and Erosion Control .....	5
<b>4</b>	<b>Stormsewer Conveyance</b> .....	<b>5</b>
<b>5</b>	<b>100 Year HGL</b> .....	<b>7</b>
<b>6</b>	<b>Critical Overland Flow Conveyance Routes</b> .....	<b>7</b>
<b>7</b>	<b>Development Area Target Flows</b> .....	<b>8</b>
<b>8</b>	<b>Conclusions</b> .....	<b>9</b>

### LIST OF TABLES

Table 3-1	Comparison of Increased Flows to Barton Pond from Brock Street Urbanization .....	3
Table 3-2	Estimated Uncontrolled Flow from Evendale Developments to Barton Farm .....	3
Table 3-3	Target Flows and Estimated Design Flows from Evendale Developments .....	3
Table 3-4	Estimated Design Flows Impact on Barton Pond Flows.....	4
Table 3-5	Comparison of Flows to the Natural Channel from Brock Street Urbanization .....	4

### APPENDICES

Appendix A	Background Information
Appendix B	Stormwater Management Calculations
Appendix C	LSRCA Comment Response Matrix

### Figures Located in Appendix B

Figure 1	Existing Drainage Plan
Figure 2	Proposed Drainage Plan
Figure 3	Estimated Uncontrolled Areas to Barton Pond from Evendale
Figure 4	Critical Overland Flow Sections to Barton Pond

# 1 Introduction

## 1.1 Background

Cole Engineering Group Ltd. (COLE) was retained by Evendale Developments Ltd. to prepare a Road Conveyance Report in support of the Plan of Subdivision Application: S-U-2017-03, in the Township of Uxbridge (the “Town”), within the Regional Municipality of Durham (the “Region”). The purpose of this report is to provide information for the Town to review with respect to stormsewer and overland flow conveyance. More specifically, the report will present the evaluation on the following:

- Overland Flow conveyance through Block 8
- Stormsewer and Overland Flow conveyance for Herrema Boulevard, and;
- Stormsewer conveyance along Brock Street.

The following documents were reviewed to complete this analysis and relevant excerpts are included in **Appendix A**:

- Stormwater Management Report for Barton Farm Plan of Subdivision 18T-87061, Prepared by G.M Sernas Associated Ltd. (December 1992) (**Barton Pond SWM Report**);
- Drainage Area Plan Barton Farm Subdivision Figure 1, by G.M. Sernas & Associates Ltd. (1992) (**Barton Farm Subdivision Drainage Plan**);
- Stormwater Management Report for Goldmanco Uxbridge Part of Lots 102 to 105 (Both Inclusive), Part of Park Street , Registered Plan H50061 and Part of Lot 31 Concession 7;
- Township of Uxbridge, Prepared by G.M Sernas (July 2008) (**Goldmanco SWM Report**);
- Goldmanco Subdivision, Drawing OTT-1 dated August 2007 prepared by G.M Sernas Associates Ltd (**Goldmanco Drainage Plan**);
- Coral Creek Homes, Storm Drainage Plan Drawing ST-1, Prepared by Vincent & Associates. (June 12 2001) (**Coral Creek Drainage Plan**);
- Evendale Developments Ltd, Functional Servicing and Stormwater Management Report for Brock Street East Development, Township of Uxbridge, Prepared by Cole Engineering Ltd., Dated May 2018 (**Evendale FSR**);
- Westlane Development Ltd, Functional Servicing and Stormwater Management Report for Brock Street and Nelkydd Lane, Township of Uxbridge, Prepared by Cole Engineering Ltd., Dated March 2019 (**Westlane FSR**); and,
- Plan and Profile drawings provided by the Region.

## 1.2 Subdivision Description and General Assumptions

The study area as part of this analysis is shown on **Drawing STM-01** and **STM-02**. The Barton Pond SWM report set the overall drainage intent for stormwater draining towards the Barton SWM Pond located north along Herrema Boulevard at Barton Trail. The drainage plan from the Barton Pond SWM report has been included in **Appendix A**. Several developments have taken place or are planning to be developed since the Barton Pond SWM report and information from them has been compiled to perform the stormwater conveyance analysis. The proposed urbanization along Brock Street was included to set drainage areas in conjunction with assumptions from various reports listed below:

- The Evendale FSR includes information on future developments located north of Brock Street, refer to Evendale FSR drainage plan excerpts in **Appendix A**. This report was used to assume the original target controlled flows to the stormsewer network along Herrema Boulevard. It was also used to aid in assuming uncontrolled flows to Brock Street;
- The Westlane FSR includes information on future developments located south of Brock Street, refer to Westlane drainage plan excerpts in **Appendix A**. This report was used to assume controlled flows to MH20 and then to a naturalized channel;
- The Coral Creek Drainage Plan includes areas to the west of the Westlane developments and a portion of the road from the drainage plan was used in the stormwater conveyance analysis, refer to Coral Creek Drainage Plan excerpts in **Appendix A**; and,
- The Goldmanco Drainage Plan includes areas to the west of Evendale FSR development that were assumed to drain to Herrema Boulevard, refer to Goldmanco Drainage Plan excerpts in **Appendix A**. It should be noted that it cannot be verified where or how information for these drainage areas was determined, therefore it is uncertain on whether they are correct.

## 2 Stormwater Conveyance Design Criteria

- The storm sewers within the subdivision should be designed such that they can convey the minor flow, i.e., runoff based on the 5-year design storm.
- The overland Flow Route along Herrema Boulevard should be analyzed for conveyance of major flow, i.e., 100-year runoff minus 5-year runoff based design storms.

## 3 Brock Street Urbanization Changes to Stormwater Conditions

The urbanization of Brock Street ditches to storm sewers and removal of Donald Ln re-alignment of Herrema Boulevard, results in an increase in paved surfaces and changes to drainage areas. Prior to discussion about stormsewer and overland flow capacity in this report, Quantity Control, Quality Control and Erosion Control have been analyzed for impacts and required mitigation measures. This analysis was done for both discharge points – flows to Barton Pond and flows towards the Natural Channel. It should be noted that both these discharge points ultimately drain to the same creek.

### 3.1 Quantity Control to Barton Pond

**Figure 1** and **2** illustrates the existing and proposed minor and major storm drainage system not including the Evendale and Westlane development areas. A comparison of the existing and proposed 5 year and 100 year flows draining to the Pond are summarized in **Table 3-1** below using Visual OTTHYMO modeling. The 5.41 ha area A1 Pre minor and major is the drainage to Barton Pond under existing conditions, which

includes some areas north and south of Brock Street and a portion of Brock Street as shown on **Figure 1**. The areas north of Brock Street within A1pre do not include Block 6, 7 and 8. Similarly A1 Post minor and A1 Post major are drainage areas towards the pond from some areas north and south of Brock Street and a portion of Brock Street and do not include Block 6, 7 and 8. The reason Block 6, 7 and 8 are not included on **Figures 1 and 2** is because this analysis shown in **Table 3-1** is to determine the change in flows as a result of the urbanization of Brock Street.

**Table 3-1 Comparison of Increased Flows to Barton Pond from Brock Street Urbanization**

Catchment ID/Description	Storm Event (yr)	Catchment Area (ha)	V05 Flow (L/s)	Increase in Flow (L/s)
A1 Pre Existing Minor System to Pond	5	5.41	680	-
A1 Pre Existing Major System to Pond	100	5.41	1,749	-
A1 Post Proposed Minor System to Pond	5	5.80	727	47
A1 Post Proposed Major System to Pond	100	5.43	1,789	40

Based on **Table 3-1** the urbanization of Brock Street will increase flows to Barton Pond. As a result, the Site Plan components of Evendale development (Blocks 6, 7 and 8, which are areas A5 Post and A15 post on **DWG STM-01**) will have their targets reduced. To determine the max pipe flow and overland flow from the Evendale Site Plans, the uncontrolled areas from Evendale development had to be approximated first. The approximate uncontrolled drainage area for Evandale developments to Barton Pond B1 Post is shown on **Figure 3** and a summary of the flows are shown on **Table 3-2** below.

**Table 3-2 Estimated Uncontrolled Flow from Evendale Developments to Barton Farm**

Catchment ID/Description	Storm Event (yr)	Catchment Area (ha)	V05 Flow (L/s)
B1 Post	5	0.92	119
B1 Post	100	0.92	306

The new Evendale development target flows to the storm sewer and overland are shown below in **Table 3-3** below.

**Table 3-3 Target Flows and Estimated Design Flows from Evendale Developments**

Storm Event	Original Total Target Flow (L/s)	Min Flow Decrease Required to Offset Increase in Flow (L/s)	New Total Target Flow Overl and and Pipe (L/s)	Uncontrolled Flow 119 L/s in Pipe the rest Overland (L/s)	New Control Target Flow Overland from Evendale Developments (L/s)	New Control Target Flow to Storm Sewer from Evendale Developments A5 + A15 (L/s)*	Total Estimated Design Flow (L/s)	Total Estimated Design Flow - Target Flow (L/s)
5	171	47	124	119	0	11	130	6
100	451	40	411	306	94	11	411	0

\*Areas A5 and A15 are shown on Drawing STM-01

Based on **Table 3-3**, the 5 year total estimated design flow is higher than the target flow. This is unavoidable due to grading and servicing constraints that limit how much flow can be controlled on the

Evendale site plans. Low flow control structures have been assumed to potentially be placed within the Evendale Site plans that connect to the storm sewer under Herrema Blvd. Low flow control structures typically can only control flows up to a minimum of 3.5 L/s. As there are 3 outlets to Herrema from the Evendale Site Plan areas it has been assumed that the target flow for them can only be as low as 10.5 L/s. During detailed design of the Evendale development Site Plans, an ICD is recommended to be installed on one of the catch basins on Herrema BLVD to lower the flow to the stormsewer by 6 L/s during the 5 year storm event. This is recommended to not exceed the assumed target flows to the storm sewer.

**Table 3-4** below shows the 5 year % increase in flow compared to the original design of drainage area to Barton Pond. The % increase in flow to the pond is less than 0.5% and is anticipated to have a negligible impact on the downstream environment. It should also be noted that it is unlikely that the 6 L/s increase in flow will coincide with the same peak time as the peak flow towards the pond. Furthermore, **Section 3.2** below shows that flow to the natural channel are being reduced, which creates an overall net decrease in flow to the downstream creek. Refer to quantity control calculations in **Appendix B** and excerpts of the Original Pond Design in **Appendix A**. It should be noted that if uncontrolled flow areas from Evendale development are changed then the targets would have to change accordingly such that post to pre flows are maintained.

**Table 3-4 Estimated Design Flows Impact on Barton Pond Flows**

Storm Event	Total Drainage to Pond from Sernas Report	%Increase in Flow Towards the Pond Compared to Total Design Drainage to Pond from Sernas Report (Total Design Flow - Target Flow)/Total Drainage to Pond	Barton Farm Target Flows from Sernas Report (L/s)	Total Outflow from Pond from Sernas Report (L/s)	Outflow from Pond - Target Flow for Pond (L/s)	Max Outflow from Pond - Target Flow for Pond after Urbanization of Brock Street and Evendale Developments (L/s)
5	5,930	0.10%	2,000	980	-1,020	-1,014
100	16,200	0.00%	5,570	4,800	-770	-770

### 3.2 Quantity Control to the Natural Channel

**Figure 1** and **2** illustrates the existing and proposed minor and major storm drainage system not including the Evendale and Westlane Site Plan development areas. A comparison of the existing and proposed 5 year and 100 year flows draining to the Pond are summarized in **Table 3-5** below using the rational method. Based on **Table 3-5** the flows towards the natural channel have decreased. Refer to quantity control calculations in **Appendix B**.

**Table 3-5 Comparison of Flows to the Natural Channel from Brock Street Urbanization**

Catchment ID/Description	Storm Event (yr)	Catchment Area (ha)	Rainfall Intensity (mm/hr)	Rational Method Flow (L/s)	Increase in Flow (L/s)
--------------------------	------------------	---------------------	----------------------------	----------------------------	------------------------

A2 Pre Existing Minor System to Channel	5	1.09	107.0	170	0
A2 Pre Existing Major System to Channel	100	1.09	200.6	398	0
A2 Post Proposed Minor System to Channel	5	0.7	107.0	116	-54
A2 Post Proposed Major System to Channel	100	1.07	200.6	395	-3

### 3.3 Quality and Erosion Control

As the developments and future developments indicated in the Evendale FSR utilize 80% TSS removal the TSS loading from these areas will mimic grass areas which is lower than the 35% imperviousness that was allotted for these areas draining to the Barton SWM Pond (refer to Table 2.1 of the Barton Pond SWM Report). This will offset the small ditch area on Brock Street draining towards the Barton Pond that is being filled and paved. Also, the ditch areas are being filled with sidewalks which are generally clean as they are for pedestrian traffic. As the total flow towards the pond will remain generally the same, it is anticipated that there will not be any significant impacts to erosion control.

Due to the Brock Street Urbanization the passive ditch treatment of stormwater for the road has been reduced to the natural channel. As discussed with the LSRCA and the Region, an OGS unit that is ETV certified has been agreed to be used to satisfy quality control as a result of the loss of the ditches. A Stormceptor OGS unit has been proposed. Refer to the **Servicing Drawing** for the location of the Stormceptor OGS unit and model type. Refer to ETV Certification and OGS to sizing calculations provided in **Appendix B**. As the total flow towards the channel are less than existing conditions as shown in **Section 3.2**, it is anticipated that there will not be any significant impacts to erosion control towards the natural channel.

## 4 Stormsewer Conveyance

To evaluate the storm sewer conveyance system performance, controlled and uncontrolled flows to various sections of the storm sewer network were analyzed.

The following drainage areas were analyzed as 5-year controlled flows draining into the storm sewer network with the following assumptions:

- A5 Post and A15 Post with flows of 3.5 L/s and 7 L/s respectively as per the Evendale FSR were modified to a total pipe target flow from both areas of 11 L/s. **Section 3.1** and calculations in **Appendix B** provide further information on how that target flow was calculated;
- A12 Post with 1505L/s 100-year flow as per the Westlane FSR;
- Due to limited information, A13 Post shown on **Drawing STM-01** was assumed to be controlled such that the effective runoff coefficient would be 0.37. The runoff coefficient of 0.75 from the ST-1 drawing for Coral Creek drainage plan was not used because it is unknown as to how much flow that area was required to control to and flows are required to be estimated for the storm sewer design sheet analysis. The runoff coefficient of 0.37 was determined by reviewing the Barton Pond SWM Report **Catchment Area 105**. According to the report approximately 4.2 ha from **Catchment Area 105** at an imperviousness of 35% (converted to a runoff coefficient of 0.48) was allowed to drain towards the pond from areas that include Brock Street and some areas to

the south of it (excerpts from Barton Pond SWM Report are included in **Appendix A**). Therefore a CxA value of 2.02 was allowed. To maintain this same total CxA value A13 Post C value must be 0.37 (refer to calculations provided in **Appendix B and Existing Drainage Plan Figure 1 in Appendix B**). The drainage area delineation for A13 post was estimated based upon plan and profiles provided by the Region, Barton Farm Subdivision Drainage Plan, Goldmanco Drainage Plan and Coral Creek Drainage Plan included in **Appendix A**. Please note that it is anticipated that this was a conservative approach applied under the conditions that limited information was available for review;

- The drainage area from Maunder Court lots near the outlet of the stormsewer to Herrema Boulevard, was assumed as per discussions with the Town (refer to correspondence in **Appendix A**); and,
- 100 year flows from Area A18 will drain towards catchment area A5 and be captured and A5 and A18 together will be controlled to the target release rate for A5.

A 5-year storm sewer design sheet is provided on **Drawing STM-03**, which demonstrates that the sewers along Herrema Boulevard as well as Brock Street are of sufficient size to convey the minor system (5-year storm event). The design sheet has assumed that all drainage from the minor system is captured within the stormsewer network. It should be noted that the 5-year stormsewer design sheet and **Figures 1-4** and **Drawing STM-01, Drawing STM-02** and **Drawing STM-03** should be read in conjunction with this SWM Report as it provides context for several assumptions. It should be noted that due to limited information, the storm sewer design sheets only include drainage that extends as far as A19 Post to the headwall that drains to the natural channel going north of Brock Street.

Regarding the future developments along Herrema Boulevard, north of Brock Street, the target release rates for stormwater management controls, both minor flows discharged into the existing storm sewer system and the overland flows conveyed via the road network, shall be governed by this Conveyance Report and detailed in a Stormwater Management Report to support those submissions.

## 5 100 Year HGL

The 100 year HGL was calculated using the following assumptions:

- A5 Post 100 year controlled flows are 3.5 L/s as modified to account for Brock Street Urbanization (see **Section 3.1**);
- A15 Post 100 year controlled flows is 7 L/s modified to account for Brock Street Urbanization (see **Section 3.1**);
- A12 Post with 100-year flow of 1505L/s as per the Westlane FSR;
- All other flows captured in the storm sewer system are assumed to be up to the 10 year event; and,
- The downstream starting HGL at Maunder Court is 266.10 as per Drawing P-101.

A 100 Year HGL design sheet is included in **Appendix B**. The 100 Year HGL is shown on the Profile Drawings. As Brock Street was originally a ditch conveyance system it has been assumed that houses abutting Brock Street were using sump pumps to grade. The HGL is not contained on DICB2, however this is an interim DICB T/G condition as that area will be developed in the future and filled. Development along Low Boulevard will be sump pumped to grade. As can be seen on the Plan and Profile Drawings, overall the HGL levels are contained within the storm sewer system.

## 6 Critical Overland Flow Conveyance Routes

Several critical overland flow conveyance areas were assessed for this report. **Figure 4** illustrates drainage areas and critical overland flow sections.

Section A-A and Section B-B shown on **Figure 4** illustrates overland flow from drainage area C1 towards an easement located within Block 8. The overland flow route easement will be maintained by Block 8. Calculations shown in **Appendix B** show that these sections have sufficient capacity to convey flows from drainage areas C1 and C2. In the interim condition Block 8 will have a large swale and open area that will sheet flow towards the north east and spill towards Low Blvd. Refer to **Drawing GR-01, GR-02** for grading information. When development occurs for Block 8 this overland flow route will need to be reanalyzed and maintained by Block 8 to still convey the same drainage.

Section C-C shown on **Figure 4** illustrates overland flow towards Low Blvd from drainage areas C2 and C3. Calculations shown in **Appendix B** show that these sections have sufficient capacity to convey flows from drainage areas C2 and C3.

The roadway at the end of Herrema Boulevard **Section D-D** shown on **Figure 4** in **Appendix B**, was analyzed for overland flow conveyance. Due to limited information several assumptions were made. Key assumptions are listed below:

- Based on the **Goldmanco Drainage Plan**, an overland flow area of 1.05 ha at an imperviousness of 36% (runoff coefficient of 0.48) will drain through Low Boulevard and ultimately towards Barton SWM pond. It should be noted that this area is indicated as overland only on this drawing and has therefore been assumed not to be required to be conveyed through the storm sewer network draining east towards Herrema Boulevard;



- Conservatively, the total 100 year target flow for Evendale Developments (411 L/s) was assumed flowing overland only for the overland conveyance analysis
- Conservatively it has been assumed that Area A13 Post has no controls active
- The rational method was used and a scaling coefficient of 1.25 has been used for the 100 year storm event

The drainage area to Section D-D used was based upon A1 Post and B1 shown on **Figure 2** and **Figure 3**. Total 100-year flows and 5-year flows to Herrema Boulevard are provided in **Appendix B**. Flow master calculations provided in **Appendix B** verify that the 100 year flows minus the minor system flows (2,214L/s) are able to be conveyed within the ROW 3 m into the boulevards that have a capacity of 3,110 L/s. Refer to **Drawing GR-01, GR-02** for grading information and **Drawing GP-01, GP-02** for servicing information.

## 7 Development Area Target Flows

Based on the above, in order to avoid causing an impact to downstream conditions, the target flows to the Brock Street and Herrema Blvd Storm Sewers from the Westlane and Evendale developments shown on **Drawing STM-01** and **Drawing STM-02** are as follows:

### Evendale Developments 5 year Storm Sewer Target Flows:

- A5 Post 3.5 L/s; and,
- A15 Post 7 L/s.

### Evendale Developments 100 year Storm Sewer Target Flows:

- A5 Post 3.5 L/s; and,
- A15 Post 7 L/s.

### Westlane Development FSR 5 year Storm Sewer Target Flows:

- A12 Post 436 L/s


### Westlane Development FSR 100 year Storm Sewer Target Flows:

- A12 Post 1505 L/s (includes external areas draining through Westlane Development)

At detailed design these developments within catchment areas A5, A15 and A12 Post, will be required to control their flows to the storm sewer to the above mentioned targets.

## 8 Conclusions

Based on the above, the proposed stormsewer network has adequate capacity to convey the minor system North towards Herrema Boulevard and East along Brock Street up to the limits shown on the storm drainage plan **Drawing STM-01** and **STM-02**. The overland flow route along the roadway at the end of Herrema Boulevard has adequate capacity to convey the 100 year minus the minor system flows.




**DRAINAGE AREA PLAN  
BARTON FARM SUBDIVISION**

**G.M. Sernas & Associates Ltd.**  
 Consulting Engineers & Planners  
 110 SCOTIA COURT UNIT 41  
 WATFORD, ONTARIO L1M 8Y7  
 TEL (416) 432-7878  
 FAX (416) 432-7877

DATE: DECEMBER 1992	DRAWN BY: A.H.	PROJECT No. 92061
SCALE: 1 : 10,000	DESIGNED BY: R.P.S.	DRAWING No. FIG. 1
	CHECKED BY: R.P.S.	

**APPENDIX A2**  
**Conveyance Report Figure Excerpts**

P:\m\2017\2017-009 Evandale\_BroadStreet\_Uxbridge\300-Design-Engineering\312-Datavectors\Project\2019\_Sep\_Compense\_Analytic\Figure\Site-03\_SDI-04.dwg (FIG 1)



Proposed Site Area  
(0.491 ha - 1.21 ac.)



70 VALLEYWOOD DRIVE, MARKHAM, ON L3R 4T5  
T:416.987.6161 / 905.940.6161 F:905.940.2064

**LEGEND**

- EXISTING MAJOR/MINOR DRAINAGE AREA
- AREA 105


A1 PRE  
0.12ha  
0.60

STORM DRAINAGE AREA ID  
DRAINAGE AREA (ha)  
RUNOFF COEFFICIENT

EXISTING STORM DRAINAGE AREA PLAN  
EVANDALE DEVELOPMENTS LTD.  
BROCK STREET DEVELOPMENT  
TOWN OF UXBRIDGE  
REGIONAL MUNICIPALITY OF DURHAM

DATE:	SEPT 2019	PROJECT No.:	2017-0569
SCALE:	NTS	FIGURE No.:	FIG 1

P:\mkt\2017-0569 - Evandale\_BrockStDev\_Engineering\312-Deliverables\Project\2019\_Sep\_Compense\_Analysis\Figures\STP-03\_STM-04.dwg (FIG 2)



Proposed Site Area  
(0.491 ha - 1.21 ac.)



70 VALLEYWOOD DRIVE, MARKHAM, ON L3R 4T5  
T:416.987.6161 / 905.940.6161 F:905.940.2064

**LEGEND**

- MINOR SYSTEM DRAINAGE AREA
- MAJOR SYSTEM DRAINAGE AREA


A1POST 0.12ha	STORM DRAINAGE ID
0.60	DRAINAGE AREA (ha)
	RUNOFF COEFFICIENT

A1POST 0.12ha	STORM DRAINAGE ID
0.60	DRAINAGE AREA (ha)
	RUNOFF COEFFICIENT

**POST-STORM DRAINAGE AREA PLAN**  
EVANDALE DEVELOPMENTS LTD.  
BROCK STREET DEVELOPMENT  
TOWN OF UXBRIDGE  
REGIONAL MUNICIPALITY OF DURHAM

DATE:	SEPT 2019	PROJECT No.:	2017-0569
SCALE:	NTS	FIGURE No.:	FIG 2

S:\2017 Projects\17-0569 Evendale\_BrockStDev\_Lab\1705-Design-Engineering\312-Deliverables\Project Deliverables\2019 September\Compendium Analysis\Figures\312-03\_SIT-04.dwg (P15)



Proposed Site Area  
(0.491 ha - 1.21 ac.)




70 VALLEYWOOD DRIVE, MARKHAM, ON L3R 4T5  
T:416.987.6161 / 905.940.6161 F:905.940.2064

**LEGEND**

- OVERLAND FLOW AREA
- B1POST  
0.92ha  
0.60
- STORM DRAINAGE ID
- DRAINAGE AREA (ha)
- RUNOFF COEFFICIENT

ESTIMATED UNCONTROLLED AREAS TO BARTON POND FROM EVENDALE	
EVENDALE DEVELOPMENTS LTD. BROCK STREET DEVELOPMENT TOWN OF UXBRIDGE REGIONAL MUNICIPALITY OF DURHAM	
DATE:	SEPT 2019
PROJECT No.:	2017-0569
SCALE:	NTS
FIGURE No.:	FIG 3

S:\2017 Projects\2017-0668 Euvale\_BrockStreet\_Library\300-Design-Engineering\312-Deliverables\Project Deliverables\2019 September\Commissioe Analysis\Plan\STM-03\_07M-04.dwg (1/9)



Proposed Site Area  
(0.491 ha - 1.21 ac.)



70 VALLEYWOOD DRIVE, MARKHAM, ON L3R 4T5  
T:416.987.6161 / 905.940.6161 F:905.940.2064

**LEGEND**



OVERLAND FLOW AREA

C1POST  
0.12ha  
0.60  
STORM DRAINAGE ID  
DRAINAGE AREA (ha)  
RUNOFF COEFFICIENT

CRITICAL OVERLAND FLOW SECTIONS TO BARTON POND  
EVANDALE DEVELOPMENTS LTD.  
BROCK STREET DEVELOPMENT  
TOWN OF UXBRIDGE  
REGIONAL MUNICIPALITY OF DURHAM

DATE: SEPT 2019	PROJECT No.: 2017-0569
SCALE: NTS	FIGURE No.: FIG 4





**LEGEND**

- PROPERTY LINE
- STORM DRAINAGE AREA
- STORM DRAINAGE ID
- STORM DRAINAGE AREA (ha) EXTERNAL
- STORM FLOW L/S
- MAJOR FLOW
- EXISTING MAJOR FLOW
- MINOR FLOW
- PROPOSED STORM MANHOLE
- PROPOSED STORM CATCH BASIN MANHOLE
- PROPOSED CATCH BASIN
- PROPOSED DOUBLE CATCH BASIN
- EXISTING MANHOLE
- EXISTING CATCH BASIN
- PROPOSED STORM SEWER
- EXISTING STORM SEWER


**SURVEYOR INFORMATION**

JD BARNES LIMITED  
110 SCOTIA COURT #40  
WHITBY, ON L1N 8Y7  
PHONE: (905) 723-2212  
FAX: (905) 723-4234

H.F. GRANDER Co. LIMITED  
ONTARIO LAND SURVEYOR  
1575 HIGHWAY 7A WEST UNIT 2A  
PORT PERRY, ON L3L 1A6  
PHONE: (905) 965-8900  
FAX: (905) 965-2347

**BENCHMARK INFORMATION:**  
MINISTRY OF TRANSPORTATION OF ONTARIO PRECISE  
BENCHMARK N° 0819778487 (AKA 778487), TWO STOREY RED  
BRICK HOUSE ON SOUTH SIDE OF HIGHWAY 47 (BROCK STREET)  
IN THE TOWN OF UXBRIDGE, 118.9m EAST OF MARIETTA STREET,  
18.4m WEST OF FRANKLIN STREET AND 15.9m SOUTH OF THE  
CENTRELINE OF HIGHWAY 47. TABLET IS SET HORIZONTALLY IN  
THE EAST FACE OF CONCRETE FOUNDATION, 3.9m SOUTH OF  
NORTHEAST CORNER, 30cm ABOVE GROUND LEVEL AND 34cm  
BELOW BRICKWORK. ELEVATION = 274.359m (GEODETIK)

**6 REGION AND TOWNSHIP SUBMISSION** OCT 28, 2019 PS  
**5 LSRCA SUBMISSION** SEPT 13, 2019 PS  
**4 100% SUBMISSION** JUNE 28, 2019 PS  
**3 ISSUED FOR LSRCA APPROVAL** JUNE 20, 2019 PS  
**2 90% SUBMISSION** MAR 25, 2019 PS  
**1 60% SUBMISSION** JAN 11, 2019 PS



THE REGIONAL  
MUNICIPALITY OF DURHAM

TOWN OF UXBRIDGE

COLE ENGINEERING  
GROUP LTD.  
70 Valleywood Drive,  
Markham, ON L3R 4T5  
T. 416 987 8161 905 940 8161  
www.coleengineering.ca

EVENDALE DEVELOPMENTS LTD.  
BROCK STREET DEVELOPMENT  
UXBRIDGE, ONTARIO

**STORM DRAINAGE AREA PLAN**

DESIGNED BY: PS DATE: JANUARY 2019 CHECKED BY: NG  
 DRAWN BY: PS PROJECT No. 2017-0569 DRAWING No. STM-01  
 SCALE: 1:500

ACCEPTED TO BE IN GENERAL CONFORMANCE WITH THE TOWNSHIP OF UXBRIDGE STANDARDS THIS ACCEPTANCE IS NOT TO BE CONSTRUED AS VERIFICATION OF ENGINEERING CONTENT

APPROVED

AECOM CANADA LTD. DEPARTMENT OF WORKS REGION OF DURHAM


DATE: DATE:

**POST DRAINAGE AREAS**

DRAINAGE ID NUMBER	AREAS (ha)	COEFFICIENTS
A1	0.14	0.45
A2	0.21	0.80
A3	0.33	0.45
A4	0.08	0.48
A6	0.31	0.80
A7	0.97	0.70
A8	0.20	0.72
A9	0.10	0.62
A10	0.27	0.56
A11	0.20	0.60
A13	2.70	0.36
A14	0.29	0.70

**POST DRAINAGE AREAS**

DRAINAGE ID NUMBER	AREAS (ha)	COEFFICIENTS
A16	0.25	0.59
A17	0.41	0.53
A18	0.07	0.48
A19	0.02	0.63
A20	0.06	0.64
A21	0.29	0.54
A22	0.11	0.60
A23	0.11	0.64
A24	0.18	0.64
A25	0.05	0.64
A26	0.06	0.59



## **APPENDIX A3**

### **WSP Hydrogeological Report Excerpts**

# 5 WATER BUDGET ANALYSIS

The Water Budget Analysis is presented in the following sections. Section 5.1 describes the analysis of historical climate data to estimate annual average precipitation and potential evapotranspiration. Section 5.2 describes the Pre-Development Water Budget. Section 5.3 Describes the Post-Development Water Budget. Section 5.4 revisits the Post-Development Water Budget to consider the potential benefits of identified mitigation opportunities.

---

## 5.1 CLIMATE-BASED WATER BUDGET

The climate-based water budget calculations are included in Tables **D-1** to **D-4** (**Appendix D**) and are summarized in **Table 3**. The average annual precipitation for the thirty year normal data between 1981 and 2010 is about 886.2 mm/m<sup>2</sup>/year (mm/year). The annual potential evapotranspiration is calculated in Table D-1 at 579.3 mm/year. This equates to a potential water surplus of 393.1 mm/year and a soil moisture deficit of 86.2 mm/year. Thus the net annual water surplus based on potential evapotranspiration is 306.9 mm/year.

The calculations were expanded to include the water holding capacity of the soil as presented in Tables D-2 to D-4. This will produce a total moisture surplus based on the calculated actual evapotranspiration. Three (3) combinations of soil type and vegetation type were identified on the Site for the Pre-Development and Post-Development scenarios. The majority of the surficial soil at the site is considered to be fine sandy loam. The land use classifications and the corresponding water holding capacities are:

- Fine Sandy Loam, Urban Lawn (75 mm/year);
- Fine Sandy Loam, Cultivated (150 mm/year);
- Fine Sandy Loam, Uncultivated (150 mm/year); and

Consideration of these factors produces a range of net annual moisture surplus between 283.8 and 341.1 mm/year as summarized in **Table 3**. The soils with higher water holding capacity effectively increase the water removed as evapotranspiration.

The calculated moisture surplus occurs during the winter, spring and fall months, and a water deficit occurs during the summer months. Much of the water surplus in the winter accumulates as snow. Snowmelt during the spring results in the runoff or infiltration of precipitation that is effectively equivalent to the winter and spring water surplus.

---

## 5.2 PRE-DEVELOPMENT WATER BUDGET

The Pre-Development Water Budget was developed based on topographic information provided by Ontario Base Mapping and the preliminary Site Grading Plan provided by *IBI*.

---

### 5.2.1 PRE-DEVELOPMENT CATCHMENTS

**Figure 11** illustrates the delineation of drainage catchments and sub-catchments for the Site. The Site is represented by one (1) (on site) catchment area that is not considered to receive run-on from adjacent properties. The Pre-Development Drainage Plan prepared by *IBI* includes an external catchment to the south of the Site. *IBI* confirmed that the external catchment was included in their analysis to estimate the quantity of runoff from off-site to be conveyed through the headwater drainage feature. The water generated in the off-site catchment is considered to be conveyed through the site and does not contribute to on-Site infiltration. WSP did not include this off-site catchment in the pre-development water balance calculations.

The on-Site catchment areas have been further subdivided. The drainage sub-catchments are based on similar slopes, soils, and vegetation/land use. The drainage sub-catchments also include consideration of post-development

drainage boundaries so that changes to drainage areas can be evaluated for the post-development conditions. The outlets for drainage of the identified Pre-Development catchments are as follows:

**On-Site Catchments:**

- **Pre-Development On-Site Catchment A:** Drains off-site through the north-eastern property boundary via overland flow (to the ditch along Brock Street East).

Table E-1 (**Appendix E**) provides a summary of the data attributes used to estimate the infiltration factor for each pre-development catchment and sub-catchment. The infiltration factor determined the proportion of the annual water surplus that would infiltrate or runoff within each sub-catchment.

Additional infiltration was attributed to Catchment A due to observed saturated conditions during the site visits. The water in the central area of the site appeared primarily to be standing water with minimum flow observed and is considered to provide an opportunity for enhanced infiltration in this area. An additional 25% of the runoff was allocated for infiltration in the pre-development scenario. This step is reflected in the water budget summary on **Table 4**, but not within the detailed water budget calculations (**Appendix E**).

---

### 5.2.2 PRE-DEVELOPMENT ANALYSIS

Properties associated with area, slope, soil type, and land cover were analyzed and assigned to each Pre-Development sub-catchment. The values assigned to each Pre-Development sub-catchment are provided in Table E-1. These values were used to estimate an Infiltration Factor. The Infiltration Factors were reviewed to confirm that they are appropriate and adjusted if necessary. Existing paved areas were assumed to be impervious and to generate runoff equivalent to the precipitation volume minus a 10% evaporative loss. Gravel areas were assumed to have a surplus equivalent to that of urban lawn areas.

Table E-1 includes the overall analysis of the total Study Area's infiltration and runoff. Table H-1 also documents the calculation of volumes associated with input and output parameters for the Pre-Development conditions. These volumes are also expressed in terms of the number of mm of water within each sub-catchment area.

A summary of the Pre-Development water budget calculations is provided in **Table 4**. These values will be used to assess the changes that proposed development will create relative to the pre-development conditions.

---

### 5.2.3 PRE-DEVELOPMENT INFILTRATION

The estimated total infiltration for the Site is 6,994 m<sup>3</sup>/yr or an equivalent of 267.8 mm/year (mm/m<sup>2</sup>/yr). The calculated infiltration represents approximately 30% of the annual precipitation (886.2 mm/yr) and 79% of the estimated annual water surplus (340.1 mm/yr).

---

### 5.2.4 PRE-DEVELOPMENT RUNOFF

The total runoff for the Site is 1,889 m<sup>3</sup>/yr or an equivalent of 72.3 mm/year. The calculated runoff represents approximately 8% of the annual precipitation (886.2 mm/yr) and 21% of the estimated annual water surplus (340.1 mm/yr).

---

## 5.3 WATER BUDGET– POST-DEVELOPMENT CONDITIONS

The Post-Development Water Budget was based on the proposed concept plan presented in **Figure 3**. The Post-Development scenario introduces 60 townhomes, and new driveway and roadway areas. WSP understands that a naturalized drainage feature is to be constructed along the south and east side of this development area to convey water currently drained by the headwater drainage feature.

The Post-Development scenario presented by *IBI* in the Functional Servicing and Stormwater Management Report (*IBI*, 2021) includes the off-site catchment to the south as was included in Pre-Development. *IBI* has confirmed that

the volume of water previously conveyed through the Site via the headwater drainage feature would now be directed to the proposed natural drainage feature along the south and east side of the property. The natural drainage features include a series of swales/soak away pits that have been designed to promote infiltration. *IBI* confirmed that the perimeter drainage feature is capable of promoting infiltration. WSP has accounted for this by increasing the soil infiltration factor within the drainage feature in detailed water budget calculations (**Appendix F**).

*IBI* also allowed for an infiltration trench to capture and infiltrate runoff from rooftops within the central area of the development. WSP also accounted for this infiltration in the detailed water budget calculations (**Appendix F**).

---

### 5.3.1 POST-DEVELOPMENT CATCHMENTS

**Figure 12** illustrates the delineation of drainage catchments and sub-catchments for the Site under post-development conditions. The Site has been subdivided into six (6) on-site catchments. Sub-catchment delineations in Pre-Development conditions were maintained for the Post-Development analysis. The post-development catchments were prepared based on a preliminary grading plan and drainage area plan provided by *IBI*.

Under Post-Development conditions, a new naturalized drainage feature that drains off-site to the northwest is introduced in Catchment PF. Runoff from within the developed areas of the Site drains northwest via the on-site storm sewer system and rear lot catch basins, or directly to the offsite northwest via overland flow. WSP has assumed that the runoff from the upgradient properties (to the south and west) will be conveyed through the natural drainage feature. The outlets for each Catchment are summarized below:

#### **On-Site Catchments:**

- **Post-Development On-Site Catchment PA1:** Drains off-site to the northwest via overland flow.
- **Post-Development On-Site Catchment PA2:** Drains off-site to the northwest via overland flow.
- **Post-Development On-Site Catchment PB:** Drains off-site to the northwest via the on-site storm sewer system.
- **Post-Development On-Site Catchment PC:** Drains to the rear lot infiltration trench, which connects to the on-site storm system and subsequently flows off-site to the north.
- **Post-Development On-Site Catchment PD:** Drains to the rear lot catch basins which connect to the on-site storm sewer system and subsequently flows off-site to the north.
- **Post-Development On-Site Catchment PE:** Drains to the rear lot catch basins which connect to the on-site storm sewer system and subsequently flows off-site to the north.
- **Post-Development On-Site Catchment PF:** Drains to the proposed drainage swale which subsequently flows off-site to the north west via overland flow

Table F-1 (**Appendix F**) provides a summary of the data attributes used to estimate the infiltration factor for each post-development catchment and sub-catchment. The infiltration factor determined the proportion of the annual water surplus that would infiltrate or runoff within each sub-catchment. Runoff from the developed areas in on-site catchment areas will be affected by the creation of buildings and driveway areas.

WSP prepared the post-development catchments with input from *IBI* on split drainage from rooftops to rear lot catch basins. This results in some differences in catchment delineations between the *IBI* Post Development Drainage Area Plan (*IBI, 2021*) and the post-development site catchment areas in **Figure 12**. Catchment A1 in Post Development Drainage Area Plan (PDDAP) includes Catchment PF in **Figure 12**. Catchment A2 in the PDDAP includes Catchment PA1 and PA2 in **Figure 12**. Catchment A3 in the PDDAP includes Catchment PB, PC, PD and PE in **Figure 12**. The difference in catchment delineations is primarily due to the manner in which runoff is accounted for in stormwater management as opposed to the water balances.

---

### 5.3.2 POST-DEVELOPMENT ANALYSIS

Properties associated with area, slope, soil type, and land cover were analyzed and assigned to each Post-Development sub-catchment. The values assigned to each Post-Development sub-catchment are provided in

Table F-1 (**Appendix F**). These values were used to estimate an Infiltration Factor. The Infiltration Factors were reviewed to confirm that they are appropriate and adjusted if necessary.

Table F-1 includes the overall analysis of the total Study Area's infiltration and runoff. Table F-1 also documents the calculation of volumes associated with input and output parameters for the Post-Development condition. These volumes are also expressed in terms of the number of mm of water within each sub-catchment area. The volumes are summed by catchment and for the total property area.

Assumptions incorporated into the water budget for the Post-Development scenario included:

- 1) Impervious surfaces (roads, driveways and buildings) are assumed to have a 10% evaporative loss.
- 2) Runoff is assumed to be conveyed directly to the outlets and not infiltrated.
- 3) Runoff from external sub-catchments is conveyed through the Site and not infiltrated.
- 4) Infiltration through the naturalized drainage feature is included in the Water Budget Summary in **Table 4**.
- 5) Rooftop runoff from the entire roof area in Catchment PC will be redirected to the rear lawns, and 50% of the volumes are assumed to infiltrate.
- 6) Rooftop runoff from rear roof areas in Catchment PA1, PD and PE will be redirected to the rear lawns and 50% of the volumes are assumed to infiltrate.
- 7) The remaining rooftop runoff in Catchment PC and the runoff from rear lawn areas will be captured by the infiltration trench in Catchment PC, with 80% of the volume received by the infiltration trench assumed to infiltrate.

A summary of the Post-Development water budget calculations is provided in **Table 4**.

---

### 5.3.3 POST-DEVELOPMENT INFILTRATION

In the post-development condition, the Site will contain approximately 13,574 m<sup>2</sup> of impervious surfaces. This would result in a net infiltration of 3,053 m<sup>3</sup>/year or 117 mm/yr through natural pervious areas, including infiltration in the naturalized drainage area. A further 1,685 m<sup>3</sup>/yr will infiltrate through the rear lawns by rooftop disconnect and 872 m<sup>3</sup>/yr will infiltrate through the rear yard infiltration trench. This results in a net infiltration of 5,610 m<sup>3</sup>/yr. The net infiltration would reflect approximately 24% of the precipitation (886.2 mm/yr).

---

### 5.3.4 POST-DEVELOPMENT RUNOFF

The introduction of impervious surfaces will increase the total runoff from the developed area. The total runoff generated by the proposed development area is 11,939 m<sup>3</sup>/yr or 457 mm/year. As mentioned above, 1,685 m<sup>3</sup>/yr of this runoff will infiltrate through the rear lawns by rooftop disconnect and 872 m<sup>3</sup>/yr will infiltrate through the central rear-lot infiltration trench. The net runoff generated in the post-development scenario is 9,382 m<sup>3</sup>/yr. The total calculated net Post-Development runoff represents approximately 40.5% of the annual precipitation (886.2 mm/yr).

---

### 5.3.5 COMPARISON WITH PRE-DEVELOPMENT

**Table 4** provides a comparison of the water budget estimates for the Pre-Development and Post-Development cases. The Post-Development scenario includes measures designed to enhance infiltration at the site. The total on-site infiltration is reduced by approximately 20% or 1,385 m<sup>3</sup>/yr when compared to the Pre-Development Scenario. The introduction of additional impervious surfaces increases the total runoff by 7,493 m<sup>3</sup>/yr. This increased runoff is managed by the stormwater management system.

Measures are proposed to re-direct front and rear roof-top runoff from the townhouse to the back lawns assumes that 50% of the redirected roof-top runoff will infiltrate into the lawns. The infiltration trench proposed in the rear lots of Catchment PC will have the ability to infiltrate runoff from the lawns. It is assumed that 80% of the volumes received are able to infiltrate back in the groundwater beneath the development site. The net infiltration is enhanced

by 2,557 m<sup>3</sup>/year through these actions. The primary goal of the water balance mitigation analysis is to determine whether the annual infiltration to groundwater beneath the development area can be maintained.

If other options for mitigation are preferred due to site area availability, it would also be possible to enhance infiltration by redirecting some of the runoff from driveways and other impervious surfaces. This can be accomplished by changing the infiltration characteristics of the pervious surfaces to allow for more infiltration.

---

## 5.4 WATER QUALITY

The water budget analysis must also consider potential changes to water quality that could be experienced in relation to the proposed development. The following sections describe the typical contaminants associated with the current and future land uses.

---

### 5.4.1 EXISTING CONDITIONS

The Site is currently vacant. As such, there are no activities present that could potentially impact groundwater quality at this time.

---

### 5.4.2 FUTURE CONDITIONS

The proposed Post-Development condition includes new driveway and roadway areas. These areas may be a future source of contamination to groundwater infiltration or surface water runoff by winter road de-icing agents. The most effective method of reducing potential impacts from salt or other winter road de-icing agents is to minimize the mass/volume of material applied through the use of Best Management Practices (BMPs). Any pervious areas used for winter snow storage may also become potential sources of contamination from winter road de-icing agents. BMPs recommend storing snow on impervious surfaces.

The driveway and roadway areas may also be a potential sources of petroleum hydrocarbons. These are typically contained in vehicles. The release of these substances will typically be the result of accidents. These potential releases could result in impairment of water quality by infiltrating into the groundwater. The risk of an accident occurring at the Site is low considering the only traffic will be the residents who occupy the building.

In pervious areas, soil-enrichment agents (i.e. fertilizers) and/or herbicides may also be a source of contamination. Application of these products should be minimized in order to reduce potential contamination.

# 7 DEWATERING ASSESSMENT

The potential requirements for dewatering in association with construction of the proposed residences, for long-term drainage from foundation drains and associated buried utilities (storm and sanitary sewers) is assessed below. The potential requirements for permitting associated with dewatering activities are as follows:

- Takings of less than 50,000 L/day at any one time do not require a permit;
- Takings of greater than 50,000 L/day but less than 400,000 L/day at any one time requires registration with the Environmental Activity and Sector Registry (EASR); or
- Takings of greater than 400,000 L/day at any one time for the project will require a Category 3 Permit to Take Water (PTTW).

WSP has prepared a preliminary assessment of the dewatering requirements and the associated impacts associated with construction and long-term drainage.

---

## 7.1 DEWATERING EQUATIONS AND ASSUMPTIONS

Given the subsurface conditions encountered in the study area, equations are used to account for excavations under unconfined groundwater conditions. For the purposes of these calculations, long narrow trench equations are assumed to be more appropriate to estimate flows for the foundation excavation, since the length to width ratio of the excavation is greater than 1.5.

### LONG NARROW TRENCH EQUATION – UNCONFINED CONDITIONS

Dewatering volumes were estimated using the following equation from Powers (1992) for drainage trench of finite length with a length to width ratio of greater than 1.5 for an unconfined system:

$$Q = \frac{xK(H^2 - h^2)}{\ln \frac{R_0}{r_s}} + 2 \left[ \frac{xK(H^2 - h^2)}{2L} \right]$$

where Q is discharge (m<sup>3</sup>/s), x is the trench sidewall length (m), K is hydraulic conductivity (m/s), H is initial water level (m), h is the required drawdown (m), R<sub>0</sub> is the equivalent radius of influence (m), and r<sub>s</sub> is the equivalent well radius (m). For more details, please refer to Powers (1992). Using the equation for a long, narrow system provides a more conservative estimate for dewatering rates when compared with using the equation for a drainage trench from a line source.

### DARCY'S LAW

Dewatering volumes for the calculation of seepage across the base of the excavation was estimated using the empirical Darcy's Law equation as described in Powers (1992):

$$Q = K_v A i$$

where Q is discharge (m<sup>3</sup>/s), K<sub>v</sub> is vertical hydraulic conductivity (m/s), A is cross-sectional area (m<sup>2</sup>), and i is the hydraulic gradient.

### EQUIVALENT RADIUS OF INFLUENCE (R<sub>0</sub>)

The equivalent radius of influence R<sub>0</sub> is assumed to be equivalent to the zone of influence (ZOI). R<sub>0</sub> was estimated using the empirical Sichart equation as described in Powers (1992):

$$R_0 = 3000(H - h)\sqrt{K}$$

where R<sub>0</sub> is the equivalent radius of influence or ZOI (meters), H is the initial water level (meters), h is the required drawdown (meters), and K is hydraulic conductivity (meters/second).



---

## 7.2 ASSUMPTIONS

A number of assumptions were incorporated based on the site-specific data collected in site investigations and information about the proposed development. The assumptions related to construction dewatering are as follows:

- No measures are to be put in place to restrict flows into the excavations (e.g., sheet piling, caissons) to provide more conservative (overestimate) dewatering rates;
- The aquifer is uniform, continuous and of infinite extent;
- The proposed elevations of the building footings and storm and sanitary sewer inverts were provided by *IBI* in the Site Servicing Plan dated March 2019.
- The dimensions for each building used to estimate potential dewatering requirements are outlined below:
  - Building 1 – 29.4 x 13.3 m
  - Building 2 – 36.5 x 13.3 m
  - Building 3 – 35.4 x 14.2 m
  - Buildings 4 through 9 – 42.5 x 14.2 m
  - Buildings 10 and 11 – 54.4 x 16.2 m
- The Site Servicing plan showing the depths of building footings and depths of structures, pipe lengths and slopes are presented in **Appendix G**.
- Assumed hydraulic conductivity is based on the field saturated hydraulic conductivity estimated from the infiltration testing conducted at the Site by WSP (WSP, 2018). The field saturated hydraulic conductivity was observed to be  $4.2 \times 10^{-5}$  m/sec. This value is considered to be conservative for the observed soils.
- For the purposes of estimating flux across the base of the excavation, vertical hydraulic conductivity was used in the calculation using the Darcy equation. The vertical hydraulic conductivity is assumed to be an order of magnitude lower than the horizontal hydraulic conductivity ( $4.2 \times 10^{-6}$  m/sec for the conservative dewatering rate)
- The vertical hydraulic gradient was assumed to be 0.1 m/m;
- Dewatering during construction is assumed to lower the water table by 0.5 m below the base of the building footing and 1.0 m below the base of the sewer inverts.
- Assumed seasonal high groundwater elevations for the Site is based on elevations measured in mid April and May of 2019 (**Table 1**).
- Groundwater elevation contours were used to prepare **Figure 17** to illustrate relative elevations of building foundations to the seasonally high groundwater elevations for use in the dewatering estimates.
- Groundwater elevation contours were used to prepare **Figure 18** to illustrate relative elevations of proposed utilities to the seasonally high groundwater elevations for use in the dewatering estimates. .
- Excavations for storm and sanitary sewers are assumed to not be any greater than 50 m trench segments.
- Precipitation entering the open excavations were estimated assuming a 10 mm rain storm event.
- A safety factor of 50% is applied to the dewatering estimates to account for fluctuations in groundwater elevations and variations in soil conditions.

The primary factors that will control the rate of seepage into the excavation or foundations are the hydraulic conductivity and the depth that the water table will be lowered.

This assessment does not represent an engineering design of a dewatering operation, but a preliminary hydrogeological analysis for assessment of dewatering volumes. The actual design of the dewatering operation will be the responsibility of the contractor.

---

## 7.3 DEWATERING CALCULATIONS

---

### 7.3.1 CONSTRUCTION DEWATERING FOR RESIDENTIAL FOUNDATIONS

The calculations of the estimated volumes of water that could enter the excavations during construction of each building lot are shown in **Table 5**. These calculations show the conservative dewatering rate that may be observed. Dewatering calculations are provided in **Appendix H1**.

Residential building foundations in the north-east portion of the Site (buildings 3, 4, 5, 8, 9 and 10) appear to be above the seasonally high groundwater elevations assumed at the Site. Residential building foundations in the south-west portion of the Site (buildings 1, 2, 6, 7 and 11) have potential to be below the seasonally high groundwater elevations assumed at the Site.

The total volume that would potentially need to be dewatered to maintain all foundations open at the same time would be up to 313,000 L/day. Typical approaches for construction of these types of projects result in only a few individual building foundations being constructed at any one time. It was estimated that precipitation may contribute between 3,910 and 8,813 L/day for a single excavation, in addition to the estimated volumes listed above. The zone of hydraulic influence from building excavations would be less than 24 m. There is potential that hydraulic influence would extend off-site if multiple lots near the Site boundaries were constructed at the same time. Review of the conservatism in the estimates, the likelihood that construction will be carried out in stages, and the effects of seasonality on potential impacts, it is prudent to register the proposed dewatering activity for the subdivision on the EASR and to manage activities such that daily dewatering volumes are maintained below 400,000 L/day.

The following is a summary of the dewatering estimates for each building foundation with footings depths below the water table:

- **Building 1 with proposed footing depths plus 0.5m construction drawdown between 1.0 and 1.5 m below the water table:** The dewatering volumes entering across the walls and the floor of a single excavation is estimated to be up to 58,494 L/day, with an estimated zone of influence (ZOI) of up to 24m. It was estimated that precipitation may contribute up to 3,910 L/day for a single excavation, in addition to the estimated volumes listed above. Dewatering for the construction of the building foundation would likely require registering on the EASR. Registration is recommended based on the potential that the total rate of dewatering at the Site could be between 50,000 L and 400,000 L/day.
- **Building 2 with proposed footing depths plus 0.5m construction drawdown between 0.5 and 1.0 m below the water table:** The dewatering volumes entering across the walls and the floor of a single excavation is estimated to be up to 47,092 L/day, with an estimated zone of influence (ZOI) of up to 15m. It was estimated that precipitation may contribute up to 4,855 L/day for a single excavation, in addition to the estimated volumes listed above. These building foundations could potentially be constructed without registration on the EASR, but registration is prudent to minimize potential for delays.
- **Building 3 with proposed footing depths plus 0.5m construction drawdown between 1.0 and 1.5 m above the water table:** A comparison of the average groundwater elevation and proposed building foundation footing elevations indicates that the footings will be above the water table. These building foundations could potentially be constructed without registration on the EASR, but registration is prudent to minimize potential for delays.
- **Building 4 with proposed footing depths plus 0.5m construction drawdown between 1.0 and 1.5 m above the water table:** A comparison of the average groundwater elevation and the proposed building foundation footing elevations indicates that the footings will be above the water table. These building foundations could potentially be constructed without registration on the EASR, but registration is prudent to minimize potential for delays.
- **Building 5 with proposed footing depths plus 0.5m construction drawdown between 0.5 and 1.0 m above the water table:** A comparison of the average groundwater elevation and the proposed building foundation footing elevations indicates that the footings will be above the water table. These building foundations could

potentially be constructed without registration on the EASR, but registration is prudent to minimize potential for delays..

- **Building 6 with proposed footing depths plus 0.5m construction drawdown between 1.0 and 1.5 m below the water table:** The dewatering volumes entering across the walls and the floor of a single excavation is estimated to be up to 78,173 L/day, with an estimated zone of influence (ZOI) of up to 24m. It was estimated that precipitation may contribute up to 6,035 L/day for a single excavation, in addition to the estimated volumes listed above. Dewatering for the construction of the building foundation would likely require registering on the EASR. Registration is recommended based on the potential that the total rate of dewatering at the Site could be between 50,000 L and 400,000 L/day.
- **Building 7 with proposed footing depths plus 0.5m construction drawdown between 1.0 and 1.5 m below the water table:** The dewatering volumes entering across the walls and the floor of a single excavation is estimated to be up to 55,381 L/day, with an estimated zone of influence (ZOI) of up to 15m. It was estimated that precipitation may contribute up to 6,035 L/day for a single excavation, in addition to the estimated volumes listed above. Dewatering for the construction of the building foundation would likely require registering on the EASR. Registration is recommended based on the potential that the total rate of dewatering at the Site could be between 50,000 L and 400,000 L/day.
- **Building 8 with proposed footing depths plus 0.5m construction drawdown between 0.5 and 1.0 m above the water table:** A comparison of the average groundwater elevation and the proposed building foundation footing elevations indicates that the footings will be above the water table. These building foundations could potentially be constructed without registration on the EASR, but registration is prudent to minimize potential for delays.
- **Building 9 with proposed footing depths plus 0.5m construction drawdown between 0.5 and 1.0 m above the water table:** A comparison of the average groundwater elevation and the proposed building foundation footing elevations indicates that the footings will be above the water table. These building foundations could potentially be constructed without registration on the EASR, but registration is prudent to minimize potential for delays..
- **Building 10 with proposed footing depths plus 0.5m construction drawdown between 0 and 0.5 m above the water table:** A comparison of the average groundwater elevation and the proposed building foundation footing elevations indicates that the footings will be above the water table. These building foundations could potentially be constructed without registration on the EASR, but registration is prudent to minimize potential for delays..
- **Building 11 with proposed footing depths plus 0.5m construction drawdown between 0.5 and 1.0 m below the water table:** The dewatering volumes entering across the walls and the floor of a single excavation is estimated to be up to 73,962 L/day, with an estimated zone of influence (ZOI) of up to 15m. It was estimated that precipitation may contribute up to 8,813 L/day for a single excavation, in addition to the estimated volumes listed above. Dewatering for the construction of the building foundation would likely require registering on the EASR. Registration is recommended based on the potential that the total rate of dewatering at the Site could be between 50,000 L and 400,000 L/day.

The dewatering estimates provided herein address dewatering associated with construction of the building foundations and is intended to be conservative to reflect the maximum volume that could be experienced. These calculations only reflect dewatering requirements for construction of the building foundations. Additional dewatering may also be required to construct underground utilities. Ideally, work can be coordinated on the Site so that the combined daily flows from all dewatering can be managed to be less than 400,000 L/day such that a Permit To Take Water is not required.

This assessment does not represent an engineering design of a dewatering operation, but provides a preliminary hydrogeological analysis for assessment of dewatering volumes. The actual design of the dewatering operation will be the responsibility of the contractors.

---

### 7.3.2 LONG-TERM DRAINAGE

Based on the observed water table elevations in April and May 2019, some of the proposed building footings will require drainage to maintain dry foundations in seasonally high conditions. WSP understands that the footings are intended to drain by gravity to the storm sewers.

The conservative calculations of the estimated volumes of water that could enter the foundation drains for each building lot are shown in **Table 6**. These calculations show a conservative seepage rate that may be experienced during peak drainage conditions. Foundation seepage calculations are provided in **Appendix H2**.

For long term drainage, the potential requirements for permitting are assessed based on the daily volume that will be removed from a single building block.

The following is a summary of the dewatering estimates for each building block:

- **Building 1 with proposed footing depths between 0.5 and 1.0m below the water table:** The potential rate of seepage into the foundation for this building may be up to 39,785 L/day, with precipitation potentially contributing up to 3,910 L/day during a rain event. This estimated volume is below the threshold requirement for a Category 3 PTTW of 50,000 L/day.
- **Building 2 with proposed footing depths between 0 and 0.5m below the water table:** The potential rate of seepage into the foundation for this building may be up to 31,099 L/day, with precipitation potentially contributing up to 4,855 L/day during a rain event. This estimated volume is below the threshold requirement for a Category 3 PTTW of 50,000 L/day.
- **Building 3 with proposed footing depths between 1.0 and 1.5 m above the water table:** Seepage into the foundation for this building is not anticipated.
- **Building 4 with proposed footing depths between 1.0 and 1.5 m above the water table:** Seepage into the foundation for this building is not anticipated.
- **Building 5 with proposed footing depths between 0.5 and 1.0 m above the water table:** Seepage into the foundation for this building is not anticipated.
- **Building 6 with proposed footing depths between 0.5 and 1.0m below the water table:** The potential rate of seepage into the foundation for this building may be up to 55,381 L/day, with precipitation potentially contributing up to 6,035 L/day during a rain event. This estimated volume is above the threshold requirement for a Category 3 PTTW of 50,000 L/day. Registration is recommended based on the potential that the total rate of long term drainage for this building could be between 50,000 L and 400,000 L/day.
- **Building 7 with proposed footing depths between 0 and 0.5m below the water table:** The potential rate of seepage into the foundation for this building may be up to 37,950 L/day, with precipitation potentially contributing up to 6,035 L/day during a rain event. This estimated volume is below the threshold requirement for a Category 3 PTTW of 50,000 L/day.
- **Building 8 with proposed footing depths between 0.5 and 1.0 m above the water table:** Seepage into the foundation for this building is not anticipated.
- **Building 9 with proposed footing depths between 0.5 and 1.0 m above the water table:** Seepage into the foundation for this building is not anticipated.
- **Building 10 with proposed footing depths between 0 and 0.5 m above the water table:** Seepage into the foundation for this building is not anticipated.
- **Building 11 with proposed footing depths between 0 and 0.5 below the water table:** The potential rate of seepage into the foundation for this building may be up to 53,877 L/day, with precipitation potentially contributing up to 8,813 L/day during a rain event. This estimated volume is above the threshold requirement for a Category 3 PTTW of 50,000 L/day.

---

### 7.3.3 CONSTRUCTION DEWATERING FOR INSTALLATION OF UTILITIES

The calculations of the estimated volumes of water that could enter the excavations during the installation of storm and sanitary sewers, watermain and lined filtration trenches are shown in **Table 7**. These calculations show the conservative estimate of the dewatering rate that may be observed per trench segment, ranging in lengths between 3 and 50 m. Dewatering calculations are provided in **Appendix H3**.

The following is a summary of the dewatering estimates for utility installations with similar maximum excavation depths below the water table:

- **Storm sewer (450 mm dia.) trench with proposed pipe invert depths plus 1.0m construction drawdown between 1.0 and 1.5 m below the water table:** The dewatering volumes entering across the walls a single 7 m trench excavation is estimated to be up to 13,206 L/day, with an estimated zone of influence (ZOI) of up to 29m. It was estimated that precipitation may contribute up to 112 L/day, in addition to the estimated volumes listed above. There is one trench segment in this category. Individual trench segments within this category of sewers could be excavated and dewatered without registering on the EASR.
- **Storm sewer (1800mm x 900mm) trench with proposed pipe invert depths plus 1.0m construction drawdown between 2.0 and 2.5 m below the water table:** The dewatering volumes entering across the walls a single trench excavation is estimated to range between 66,203 and 70,876 L/day, with an estimated zone of influence (ZOI) of up to 49m. It was estimated that precipitation may contribute up to 1,282 L/day, in addition to the estimated volumes listed above. There are two trench segments in this category, ranging in lengths between 41 and 46m. This estimated volume is above the threshold requirement for a Category 3 PTTW of 50,000 L/day. Registration is recommended based on the potential that the construction dewatering rate for these installations could be between 50,000 L and 400,000 L/day.
- **Storm sewer (250mm dia.) trench with proposed pipe invert depths plus 1.0m construction drawdown between 2.5 and 3.0m below the water table:** The dewatering volumes entering across the walls a single trench excavation is estimated to be up to 54,065 L/day, with an estimated zone of influence (ZOI) of up to 58m. It was estimated that precipitation may contribute up to 244 L/day, in addition to the estimated volumes listed above. There is one trench segment in this category, with a trench length of 20m. This estimated volume is above the threshold requirement for a Category 3 PTTW of 50,000 L/day. Registration is recommended based on the potential that the construction dewatering rate for these installations could be between 50,000 L and 400,000 L/day.
- **Storm sewer (1800mm x 900mm.) trench with proposed pipe invert depths plus 1.0m construction drawdown between 2.5 and 3.0m below the water table:** The dewatering volumes entering across the walls a single trench excavation is estimated to be up to 90,883 L/day, with an estimated zone of influence (ZOI) of up to 58m. It was estimated that precipitation may contribute up to 1,291 L/day, in addition to the estimated volumes listed above. There is one trench segment in this category, with a trench length of 46m. This estimated volume is above the threshold requirement for a Category 3 PTTW of 50,000 L/day. Registration is recommended based on the potential that the construction dewatering rate for these installations could be between 50,000 L and 400,000 L/day.
- **Storm sewer (200mm dia.) trench with proposed pipe invert depths plus 1.0m construction drawdown between 1.0 and 1.5m below the water table:** The dewatering volumes entering across the walls a single trench excavation is estimated to range between 12,875 and 22,683 L/day, with an estimated zone of influence (ZOI) of up to 29m. It was estimated that precipitation may contribute up to 281L/day, in addition to the estimated volumes listed above. There are two trench segments in this category, ranging in lengths between 8 and 23m. Individual trench segments within this category of sewers could be excavated and dewatered without registering on the EASR.
- **Sanitary sewer (200mm dia.) trench with proposed pipe invert depths plus 1.0m construction drawdown between 2.0 and 2.5 below the water table:** The dewatering volumes entering across the walls a single trench excavation is estimated to range between 57,651 and 66,614 L/day, with an estimated zone of influence (ZOI) of up to 49m. It was estimated that precipitation may contribute up to 539 L/day, in addition to the estimated volumes listed above. There are three trench segments in this category, ranging in lengths between 36 and 45m. This estimated volume is above the threshold requirement for a Category 3 PTTW of 50,000 L/day. Registration

is recommended based on the potential that the construction dewatering rate for these installations could be between 50,000 L and 400,000 L/day.

- **Sanitary sewer (200mm dia.) trench with proposed pipe invert depths plus 1.0m construction drawdown between 2.5 and 3.0m below the water table:** The dewatering volumes entering across the walls a single trench excavation is estimated to be up to 90,612 L/day, with an estimated zone of influence (ZOI) of up to 58m. It was estimated that precipitation may contribute up to 600 L/day, in addition to the estimated volumes listed above. There is two trench segments in this category, with trench lengths ranging from 20 to 50m. This estimated volume is above the threshold requirement for a Category 3 PTTW of 50,000 L/day. Registration is recommended based on the potential that the construction dewatering rate for these installations could be between 50,000 L and 400,000 L/day.
- **Sanitary sewer (200mm dia.) trench with proposed pipe invert depths plus 1.0m construction drawdown between 3.5 and 4.0 below the water table:** The dewatering volumes entering across the walls a single trench excavation is estimated to range between 108,527 and 118,337 L/day, with an estimated zone of influence (ZOI) of up to 78m. It was estimated that precipitation may contribute up to 491 L/day, in addition to the estimated volumes listed above. There are two trench segments in this category, ranging in lengths between 35 and 41 m. This estimated volume is above the threshold requirement for a Category 3 PTTW of 50,000 L/day. Registration is recommended based on the potential that the construction dewatering rate for these installations could be between 50,000 L and 400,000 L/day.
- **Sanitary sewer (200mm dia.) trench with proposed pipe invert depths plus 1.0m construction drawdown between 4.5 and 5.0 m below the water table:** The dewatering volumes entering across the walls a single trench excavation is estimated to range between 136,834 and 179,899 L/day, with an estimated zone of influence (ZOI) of up to 97m. It was estimated that precipitation may contribute up to 600 L/day, in addition to the estimated volumes listed above. There are four trench segments in this category, ranging in lengths between 16 and 50 m. This estimated volume is above the threshold requirement for a Category 3 PTTW of 50,000 L/day. Registration is recommended based on the potential that the construction dewatering rate for these installations could be between 50,000 L and 400,000 L/day.
- **Sanitary sewer (200mm dia.) trench with proposed pipe invert depths plus 1.0m construction drawdown between 5.0 and 5.5 m below the water table:** The dewatering volumes entering across the walls a single trench excavation is estimated to range between 131,903 and 157,233 L/day, with an estimated zone of influence (ZOI) of up to 107m. It was estimated that precipitation may contribute up to 213 L/day, in addition to the estimated volumes listed above. There are four trench segments in this category, ranging in lengths between 20 and 30 m. This estimated volume is above the threshold requirement for a Category 3 PTTW of 50,000 L/day. Registration is recommended based on the potential that the construction dewatering rate for these installations could be between 50,000 L and 400,000 L/day.

The dewatering estimates provided herein address dewatering associated with construction of the proposed utilities, and is intended to be conservative to reflect the maximum volume that could be experienced. These calculations only reflect dewatering requirements for construction of storm and sanitary sewers in up to 50m trench segments. Ideally, work can be coordinated on the Site so that the combined daily flows from all dewatering can be managed to be less than 400,000 L/day under a registered EASR, such that a Permit To Take Water is not required.

The utilities are to be constructed with low-permeability seals within the backfill below the seasonally high water table to minimize the potential for drainage of water or potential movement of contaminants within the excavated trenches.

This assessment does not represent an engineering design of a dewatering operation, but provides a preliminary hydrogeological analysis for assessment of dewatering volumes. The actual design of the dewatering operation will be the responsibility of the contractors.

---

## 7.4 DEWATERING SUMMARY

The conservative calculations of potential volumes of water that may require removal during construction or during long term use of the proposed residences are summarized in **Table 5, Table 6 and Table 7.**

There is potential that the volumes of water to be removed during construction dewatering may be greater than 50,000 L/day but will likely be less than 400,000 L/day. The proposed construction at the site is recommended to be registered as an activity on the EASR. Management may be required to coordinate construction activities such that daily dewatering volumes removed are maintained at less than 400,000 L/day. Records to demonstrate that daily volumes are less than 400,000 L/day for the Site will be a requirement of registration.

WSP notes that the water table is observed to vary by approximately 1.5 m in monitoring wells MW18-1 and MW18-2 during the course of the year, with higher values in the winter and spring and lower values in the summer and fall. Review of the water level data suggests that the foundation in buildings 1, 2, 6, 7 and 11 will be below the seasonally high water table. Water proofing of the foundations is recommended to reduce the potential that water is being removed and thereby complying with Policy DEMD-1 (see Section 6.1).


The potential capacity of the Region of Durham storm sewers to receive these flows has not been evaluated as part of this preliminary evaluation. The estimated rate of pumping to maintain dry foundations will likely exceed 50,000 L/day, and therefore the pumping activity will need to be registered on the EASR. An agreement with the Region of Durham will be required for discharge to be directed to the storm or sanitary sewers.

Review of the water level data suggests that the foundations for the proposed structures will be above the seasonally low water table and that foundation drainage would not occur year round, and may increase in response to precipitation events. Review of proposed foundation levels is recommended to confirm that they are above the seasonally low level.

## 8 CONCLUSIONS

- 1 WSP Canada Inc. (WSP) was retained by Westlane Development Group Ltd. to prepare a Hydrogeological Assessment and Water Balance Study for the proposed residential development located at 226 Brock Street East, Uxbridge, Ontario (Site).
- 2 The proposed development area lies within the Peterborough Drumlin Field physiographic region as defined by Chapman and Putnam (1984). The Peterborough Drumlin Field is typically characterized by rolling till plain. The area in and around the Site consist of clay plains.
- 3 The Site currently contains a headwater drainage feature that drains northerly across the site and discharges to a culvert beneath Brock Street. The development proposal includes a plan to incorporate the form and function of this headwater drainage feature in a naturalized drainage feature to be constructed along the east side of the property, pending approval of the LSRCA.
- 4 Based on the stratigraphy observed during the borehole drilling at the Site and well records from MECP Water Well Information System, the Site is predominantly underlain by alternating layers of sand and clay with isolated layers of silt, silty sand/sandy silt and silty clay observed in individual boreholes.
- 5 Groundwater elevations measured between May 2018 and May 2019 indicate that seasonally high groundwater levels are observed between February and May and also in the late fall, while groundwater levels are observed to be the lowest between July and October.
- 6 The apparent groundwater flow direction is to the north or northwest. The spacing of monitoring wells and the presence of the headwater drainage feature in the center of the site are factors to be considered in interpreting the groundwater flow direction from groundwater elevation data.
- 7 Representative groundwater samples were collected from the three (3) monitoring wells on June 21, 2018 and submitted for water quality analysis. The results of the test indicated that parameter concentrations are less than MECP Table 2: Full Depth Generic Site Condition Standards in a Potable Ground Water Condition for All Types of Property Use (Coarse Textured Soil).
- 8 The Climate-Based Water Budget indicates that average annual precipitation over the past 30 years is 886.2 mm/year. The available moisture surplus at the Site ranges between 327.1 mm/year to 341.1 mm/year year depending on the type of soil and vegetation cover. The moisture surplus will reflect the infiltration and runoff based on the soil properties, slopes, and vegetation within individual catchments.
- 9 Under existing conditions, the Site is considered to be one drainage catchment that drains to the ditch along the northern boundary of the site via overland flow.
- 10 The Pre-Development Water Budget reflects infiltration for the Site of approximately 6,994 m<sup>3</sup>/yr and runoff from the Site of approximately 1,889 m<sup>3</sup>/yr.
- 11 The Post-Development Water Budget reflects changes in land use to include increased areas of impervious surfaces (i.e. roads, buildings etc.) and re-grading. A naturalized drainage feature, with swales and soakaway pits is proposed to be constructed to replace the form and function of the headwater drainage feature. The proposed development conditions have been subdivided into six (6) on-site catchments. Runoff within the developed portion of the site is primarily captured by stormwater drainage systems.
- 12 The Stormwater Management Plan prepared by *IBI* incorporates Low Impact Development features in the form of an infiltration trench in the centre of the development to infiltrate runoff that is generated from rooftops and rear lots in the centre block of the development. The effect of these features is considered in the Post-Development Water Budget.
- 13 The Post-Development Water Budget predicts a net on-site infiltration of 5,610 m<sup>3</sup>/yr. Approximately 2,557 m<sup>3</sup>/yr of this infiltration is generated through the proposed LID measures. This reflects a net reduction of 1,385 m<sup>3</sup>/yr or 20% relative to Pre-Development. Additional opportunities to further mitigate the infiltration deficit have not been identified.
- 14 The Post-Development Water Budget predicts a net runoff of 9,382 m<sup>3</sup>/yr over the Site area. This is an increase of 7,493 m<sup>3</sup>/yr (397%) relative to Pre-Development.
- 15 The Site lies within WHPA-Q1 and WHPA-Q2 for the Uxbridge Water Supply system with assigned stress levels of moderate. Source Protection Plan (SPP) policies for WHPA-Q1 apply to areas where activities that take water without returning it to the same source may be a threat. SPP policies for WHPA-Q2 apply to areas where activities that reduce recharge might be a threat. Based on the estimated volumes of water that may require removal during construction and long-term drainage of the residential condominium, the Site will need






**LEGEND**

- APPROXIMATE SITE BOUNDARY
- + MONITORING WELL LOCATION

Data Source: Ministry of Natural Resources, Ontario Base Mapping, October 2016.

© 2021 Microsoft Corporation © 2021 Maxar © CNES 2021 Distribution Airbus DS



126 DON HILLOCK DRIVE, UNIT 2  
 AURORA, ONTARIO CANADA L4G 0G9  
 TEL.: 905-750-3080 | FAX: 905-727-0463 | WWW.WSP.COM

PROJECT:  
 HYDROGEOLOGICAL ASSESSMENT AND WATER BALANCE STUDY  
 226 BROCK STREET EAST, UXBRIDGE, ONTARIO

TITLE:  
 EXISTING CONDITIONS

CLIENT:  
 WESTLANE DEVELOPMENT GROUP LTD.

SCALE:

1:2,500

DRAWN BY:

TP

CHECKED BY:

LL

PROJECT NO:

181-06778-01

DATE:


MARCH 2021

FIGURE NO:

2


REV.:

-



Approximate groundwater elevations were determined based on the topographic survey completed by H.F. Grander Co. Ltd.

	APPROXIMATE SITE BOUNDARY		MONITORING WELL LOCATION		APPARENT GROUNDWATER FLOW DIRECTION
					GROUNDWATER ELEVATION




126 DON HILLOCK DRIVE, UNIT 2  
AURORA, ONTARIO CANADA L4G 0G9  
TEL.: 905-750-3080 | FAX: 905-727-0463 | WWW.WSP.COM

PROJECT:	HYDROGEOLOGICAL ASSESSMENT AND WATER BALANCE STUDY 226 BROCK STREET EAST, UXBRIDGE, ONTARIO	
TITLE:	SEASONAL HIGH WATER LEVELS	
CLIENT:	WESTLANE DEVELOPMENT GROUP LTD.	

SCALE:	1:1,250	
DRAWN BY:	TP	CHECKED BY: LL
PROJECT NO:	181-06778-01	
DATE:	MARCH 2021	
FIGURE NO:	10	REV.: -

Document Path: D:\a\Projects\181-06778-00\2020\MXD\181-06778-01 Figure 10 GW Flow V2.mxd

# TABLES



**TABLE 1  
GROUNDWATER ELEVATIONS  
HYDROGEOLOGICAL STUDY AND WATER BALANCE ASSESSMENT  
226 BROCK STREET  
UXBRIDGE, ON**

Monitor Designation	Elevation of T.O.P mASL	Elevation of Ground Surface mASL	PVC Casing Stick-up m	Measurement Date	Depth to Water		Groundwater Elevation (local benchmark) m ASL	Approximate Ground Elevation m ASL	Approximate Groundwater Elevation m ASL
					m bmp	m bgl			
MW18-1	100.21	99.28	0.93	28-May-18	2.45	1.52	97.76	271.68	270.16
				21-Jun-18	2.78	1.85	97.43		269.83
				18-Jul-18	3.20	2.27	97.01		269.41
				9-Aug-18	2.49	1.56	97.72		270.12
				12-Sep-18	2.92	1.99	97.29		269.69
				19-Oct-18	2.97	2.04	97.23		269.64
				21-Nov-18	2.51	1.58	97.70		270.10
				18-Dec-19	2.28	1.35	97.93		270.33
				29-Jan-19	2.71	1.78	97.50		269.90
				15-Feb-19	2.79	1.86	97.42		269.82
				19-Mar-19	2.93	2.00	97.28		269.68
				22-Apr-19	1.84	0.91	98.37		270.77
				15-May-19	1.67	0.74	98.54		270.94
				19-Aug-20	3.13	2.20	97.08		269.48
				MW18-2	100.09	99.08	1.02		28-May-18
21-Jun-18	2.24	1.22	97.86					270.77	
18-Jul-18	2.46	1.44	97.63					270.55	
9-Aug-18	1.79	0.77	98.30					271.22	
12-Sep-18	2.07	1.06	98.02					270.93	
19-Oct-18	1.93	0.91	98.17					271.08	
21-Nov-18	1.64	0.62	98.46					271.37	
18-Dec-19	1.57	0.55	98.53					271.44	
29-Jan-19	1.80	0.78	98.29					271.21	
15-Feb-19	1.81	0.79	98.28					271.20	
19-Mar-19	1.70	0.68	98.39					271.31	
22-Apr-19	1.11	0.09	98.98					271.90	
15-May-19	1.20	0.18	98.89					271.81	
19-Aug-20	2.80	1.78	97.29					270.21	
MW18-3	97.60	96.72	0.88					28-May-18	1.06
				21-Jun-18	1.09	0.20	96.52	269.77	
				18-Jul-18	1.07	0.19	96.53	269.78	
				9-Aug-18	1.00	0.12	96.60	269.85	
				12-Sep-18	1.07	0.19	96.53	269.78	
				19-Oct-18	1.14	0.25	96.47	269.72	
				21-Nov-18	1.04	0.15	96.57	269.82	
				18-Dec-19	-	-	-	-	
				29-Jan-19	frozen @ 0.97	0.09	96.63	269.88	
				15-Feb-19	frozen @ 0.97	0.09	96.63	269.88	
				19-Mar-19	frozen @ 0.97	0.09	96.63	269.88	
				22-Apr-19	0.99	0.10	96.62	269.87	
				5-May-19	1.00	0.12	96.60	269.85	
				19-Aug-20	1.18	0.30	96.42	269.67	

**Notes:**

- 1) "m" indicates metres.
- 2) "m bmp" indicates metres below measurement point, which is the top of pipe (referred to as T.O.P.)
- 3) "m bgl" indicates metres below ground level.
- 4) "m ASL" indicates metres above sea level.
- 5) Approximate ground and groundwater elevations were determined based on the topographic survey completed by H.F. Grandier Co. Ltd.
- 6) Approximate groundwater elevations highlight represent seasonally high levels observed at the monitoring well location

**Table 2**  
**WATER QUALITY RESULTS**  
**HYDROGEOLOGICAL STUDY AND WATER BALANCE ASSESSMENT**  
**226 BROCK STREET EAST**  
**UXBRIDGE, ONTARIO**

Parameters	UNIT	Table 2 SCS (1)	MW18-1	MW18-2	MW18-3	DUP (MW18-3)
			21-Jun-18	21-Jun-18	21-Jun-18	21-Jun-18
<b>Calculated Parameters</b>						
Anion Sum	me/L	-	3.56	8.3	12.0	11.8
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	-	202	293	377	372
Calculated TDS	mg/L	-	224	506	712	706
Carb. Alkalinity (calc. as CaCO3)	mg/L	-	<10	<10	<10	<10
Cation Sum	me/L	-	4.70	10.00	13.60	13.50
Hardness (CaCO3)	mg/L	-	215	324	480	478
Ion Balance (% Difference)	%	-	132.00	121.00	113.00	114.00
Langelier Index (@ 4C)	N/A	-	0.500	1.000	0.600	0.700
Saturation pH (@ 4C)	N/A	-	7.21	6.95	6.73	6.74
<b>Inorganics</b>						
Total Ammonia-N	mg/L	-	0.13	0.113	0.296	0.354
Conductivity	umho/cm	-	383	878	1240	1230
Dissolved Organic Carbon	mg/L	-	2.0	3.4	3.8	4.7
Orthophosphate (P)	mg/L	-	<0.0030	<0.0030	<0.0030	<0.0030
pH	pH	-	7.74	7.94	7.31	7.39
Dissolved Sulphate (SO4)	mg/L	-	8.4	11.7	33.3	34
Alkalinity (Total as CaCO3)	mg/L	-	202	293	377	372
Dissolved Chloride (Cl)	mg/L	790	1	112	181	178
Nitrite (N)	mg/L	-	<0.010	<0.010	<0.010	<0.010
Nitrate (N)	mg/L	-	0.147	0.06	<0.020	<0.020
Nitrate + Nitrite (N)	mg/L	-	0.147	0.06	<0.022	<0.022
<b>Metals</b>						
Dissolved Aluminum (Al)	mg/L	-	0.0323	0.0098	<0.0050	<0.0050
Dissolved Antimony (Sb)	mg/L	0.006	0.00027	0.00013	<0.00010	0.00014
Dissolved Arsenic (As)	mg/L	0.025	0.00052	0.0008	0.00178	0.00375
Dissolved Barium (Ba)	mg/L	1	0.03	0.127	0.195	0.237
Dissolved Beryllium (Be)	mg/L	0.004	<0.00010	<0.00010	<0.00010	<0.00010
Dissolved Boron (B)	mg/L	5	0.024	0.022	0.031	0.033
Dissolved Cadmium (Cd)	mg/L	0.0027	<0.000010	<0.000010	<0.000010	<0.000010
Dissolved Calcium (Ca)	mg/L	-	79	113	161	160
Dissolved Chromium (Cr)	mg/L	0.05	0.00079	<0.00050	<0.00050	<0.00050
Dissolved Cobalt (Co)	mg/L	0.0038	<0.00010	0.00013	0.00072	0.00074
Dissolved Copper (Cu)	mg/L	0.087	0.00067	0.00537	0.00027	<0.00020
Dissolved Iron (Fe)	mg/L	-	0.035	0.023	1.88	0.47
Dissolved Lead (Pb)	mg/L	0.01	0.000053	0.000162	0.000055	<0.000050
Dissolved Magnesium (Mg)	mg/L	-	4	10	19	19
Dissolved Manganese (Mn)	mg/L	-	0.01	0.0332	3.3700	2.9100
Dissolved Molybdenum (Mo)	mg/L	0.07	0.0034	0.00122	0.000547	0.000814
Dissolved Nickel (Ni)	mg/L	0.1	<0.00050	0.00074	0.002	0.00226
Dissolved Phosphorus (P)	mg/L	-	<0.050	<0.050	<0.050	<0.050
Dissolved Potassium (K)	mg/L	-	0.6	2.3	1.2	1.4
Dissolved Selenium (Se)	mg/L	0.01	0.000501	0.000132	<0.000050	<0.000050
Dissolved Silicon (Si)	mg/L	-	4.9	5.2	8.6	8.4
Dissolved Silver (Ag)	mg/L	0.0015	<0.000050	<0.000050	<0.000050	<0.000050
Dissolved Sodium (Na)	mg/L	-	9	80	90	91
Dissolved Strontium (Sr)	mg/L	-	0.15	0.28	0.38	0.38
Dissolved Thallium (Tl)	mg/L	0.002	<0.000010	0.000013	<0.000010	<0.000010
Dissolved Titanium (Ti)	mg/L	-	0.00142	<0.00030	<0.00030	<0.00030
Dissolved Uranium (U)	mg/L	0.02	0.0007	0.00119	0.00033	0.00049
Dissolved Vanadium (V)	mg/L	0.0062	0.0007	0.00098	<0.00050	0.00134
Dissolved Zinc (Zn)	mg/L	1.1	0.0015	0.0115	0.0019	<0.0010

**NOTES**

- 1) Table 2 SCS = Soil, Ground Water and Sediment Standards for Use Under Part XV.1 of the Environmental Protection Act (April 2011).
- 2) Yellow shading indicates parameter reportable detection

**TABLE 3**  
**CLIMATIC WATER BUDGET SUMMARY TABLE**  
 HYDROGEOLOGICAL ASSESSMENT AND WATER BALANCE STUDY  
 226 BROCK STREET EAST  
 UXBRIDGE, ONTARIO

Year of Climate Data Used	Total Adjusted Potential Evapotranspiration	Total Water Surplus	Total Precipitation	Soil Type	Land Use	Water Holding Capacity	Total Actual Evapotranspiration	Total Moisture Surplus used for Water Balance
	mm/yr	mm/yr	mm/yr			mm/yr	mm/yr	mm/yr
CLIMATE NORMAL 1981-2010	579.3	306.9	886.2	Fine Sandy Loam	Residential Lawn	75	545.1	341.1
					Cultivated	150	559.1	327.1
					Uncultivated	200	559.1	327.1

**NOTES:**

1) Water Holding Capacity obtained from Environmental Design Criteria of the SWM Planning and Design Manual published by the MOE in 2003.

**TABLE 4 WATER BALANCE SUMMARY**  
 HYDROGEOLOGICAL ASSESSMENT AND WATER BALANCE STUDY  
 226 BROCK STREET EAST  
 UXBRIDGE, ONTARIO

**A. OVERALL WATER BALANCE**

Characteristics		Pre-development		Post-development (No Recharge mitigation)		Change	
		Volume (m <sup>3</sup> /yr)	mm/yr	Volume (m <sup>3</sup> /yr)	mm/yr	Volume (m <sup>3</sup> /yr)	%
Input	Precipitation	23,146	886	23,146	886	0	0%
	Runon	0	0	0	0	0	0.0%
	<b>Total In</b>	<b>23,146</b>	<b>886</b>	<b>23,146</b>	<b>886</b>	<b>0</b>	<b>0.00%</b>
Output	Infiltration via Pervious Areas	6,365	244	3,053	117	-3,312	-52%
	Add: Additional Headwater Infiltration	630	24	0	0	-630	-100%
	Add: Infiltration via Rooftop Disconnect	0	0	1,685	65	1,685	>100%
	Add: Infiltration via Infiltration Trench	0	0	872	33	872	>100%
	Total Infiltration	6,994	268	5,610	215	-1,385	-20%
	Total Run-off	2,519	96	11,939	457	9,420	374.0%
	Less: Runoff Infiltrated by Headwater	-630	-24	0	0	630	-100.0%
	Less: Infiltration via Rooftop Disconnect	0	0	-1,685	-65	-1,685	-100.0%
	Less: Infiltration via Infiltration Trench	0	0	-872	-33	-872	-100.0%
	Net Runoff	1,889	72	9,382	359	7,493	396.6%
	Evapotranspiration	14,262	546	8,154	312	-6,108	-42.8%
<b>Total Out</b>	<b>23,146</b>	<b>886</b>	<b>23,146</b>	<b>886</b>	<b>0</b>	<b>0.00%</b>	

**TABLE 5 CONSTRUCTION DEWATERING ESTIMATES SUMMARY - BUILDINGS**  
 UPDATED HYDROGEOLOGICAL STUDY AND WATER BALANCE ASSESSMENT  
 226 BROCK STREET EAST  
 UXBRIDGE, ONTARIO

Building Number	Building Type	Length	Width	Area	Footing Depth Below Water Table	Footing Depth + 0.5m Below Water Table	Footing Depth Above Water Table	Construction			Total Estimated Value	Precipitation Contribution Per Building
								Conservative Rate				
								Estimated Value	With Safety Factor	Maximum ZOI		
	(m)	(m)	(m <sup>2</sup> )	(m)	(m)	(m)	(L/day)	(L/day)	(m)	(L/day)	(L/day)	
1	A	29.4	13.3	391.0	0.5-1.0	1.0-1.5	NA	38,996	58,494	24	58,494	3,910
2	B	36.5	13.3	485.5	0-0.5	0.5-1.0	NA	31,395	47,092	15	47,092	4,855
3	C	35.4	14.2	502.7	NA	NA	1.0-1.5	NA	NA	NA	NA	5,027
4	D	42.5	14.2	603.5	NA	NA	1.0-1.5	NA	NA	NA	NA	6,035
5	D	42.5	14.2	603.5	NA	NA	0.5-1.0	NA	NA	NA	NA	6,035
6	D	42.5	14.2	603.5	0.5-1.0	1.0-1.5	NA	52,115	78,173	24	78,173	6,035
7	D	42.5	14.2	603.5	0-0.5	0.5-1.0	NA	36,921	55,381	15	55,381	6,035
8	D	42.5	14.2	603.5	NA	NA	0.5-1.0	NA	NA	NA	NA	6,035
9	D	42.5	14.2	603.5	NA	NA	0.5-1.0	NA	NA	NA	NA	6,035
10	E	54.4	16.2	881.3	NA	NA	0-0.5	NA	NA	NA	NA	8,813
11	E	54.4	16.2	881.3	0-0.5	0.5-1.0	NA	49,308	73,962	15	73,962	8,813
<b>Total</b>								<b>209,000</b>	<b>313,000</b>	<b>-</b>	<b>313,000</b>	<b>68,000</b>

Note: NA - Not Applicable



**TABLE 6 DRAINAGE DEWATERING ESTIMATES SUMMARY - BUILDINGS**  
 UPDATED HYDROGEOLOGICAL STUDY AND WATER BALANCE ASSESSMENT  
 226 BROCK STREET EAST  
 UXBRIDGE, ONTARIO

Building Number	Building Type	Length	Width	Area	Footing Depth Below Water Table	Footing Depth Above Water Table	Construction			Total Estimated Value	Precipitation Contribution Per Building
							Conservative Rate				
							Estimated Value	With Safety Factor	Maximum ZOI		
		(m)	(L/day)	(L/day)	(m)	(L/day)	(L/day)				
1	A	29.4	13.3	391.0	0.5-1.0	NA	26,524	39,785	15	39,785	3,910
2	B	36.5	13.3	485.5	0-0.5	NA	20,732	31,099	5	31,099	4,855
3	C	35.4	14.2	502.7	NA	1.0-1.5	NA	NA	NA	NA	5,027
4	D	42.5	14.2	603.5	NA	1.0-1.5	NA	NA	NA	NA	6,035
5	D	42.5	14.2	603.5	NA	0.5-1.0	NA	NA	NA	NA	6,035
6	D	42.5	14.2	603.5	0.5-1.0	NA	36,921	55,381	15	55,381	6,035
7	D	42.5	14.2	603.5	0-0.5	NA	25,300	37,950	5	37,950	6,035
8	D	42.5	14.2	603.5	NA	0.5-1.0	NA	NA	NA	NA	6,035
9	D	42.5	14.2	603.5	NA	0.5-1.0	NA	NA	NA	NA	6,035
10	E	54.4	16.2	881.3	NA	0-0.5	NA	NA	NA	NA	8,813
11	E	54.4	16.2	881.3	0-0.5	NA	35,918	53,877	5	53,877	8,813
<b>Total</b>							<b>145,000</b>	<b>218,000</b>	<b>-</b>	<b>218,000</b>	<b>68,000</b>

Note: NA - Not Applicable

**TABLE 7 CONSTRUCTION DEWATERING ESTIMATES SUMMARY - UTILITIES**  
 UPDATED HYDROGEOLOGICAL STUDY AND WATER BALANCE ASSESSMENT  
 226 BROCK STREET EAST  
 UXBRIDGE, ONTARIO

Servicing Segment	Type of Servicing	Total Trench Length	Open Trench Length During Construction	No. of Trench Segments	Width	Sewer Depth Below Water Table	Sewer Depth + 1.0 m Below Water Table	Initial Elevation of Water Table	Sewer Depth Above Water Table	Construction Conservative Rate			Number of Trench Segments	Total Estimated Value	Precipitation Contribution Per Trench
										Estimated Value Per Trench	With Safety Factor	Maximum ZOI			
		(m)	(m)	(m)	(m)	(m)	(m)	(m)	(m)	(L/day)	(L/day)	(m)		(L/day)	(L/day)
Between STM MH11 and MH12	Storm (450mm dia.)	16.7	16.7	1.0	1.5	NA	NA	NA	0.5-1.0	0	0	0	1.0	0	242
Between STM MH11 and MH12	Storm (450mm dia.)	16.8	16.8	1.0	1.5	NA	NA	NA	>1.0	0	0	0	1.0	0	244
Between STM MH10 nad MH11	Storm (450mm dia.)	5.2	5.2	1.0	1.5	NA	NA	NA	0.5-1.0	0	0	0	1.0	0	75
Between STM MH11 and Jellyfish	Storm (450mm dia.)	3.4	3.4	1.0	1.5	NA	NA	NA	0-0.5	0	0	0	1.0	0	49
Between STM MH10 and Jellyfish	Storm (450mm dia.)	3.3	3.3	1.0	1.5	NA	NA	NA	0-0.5	0	0	0	1.0	0	48
Between STM MH9 and MH10	Storm (450mm dia.)	7.7	7.7	1.0	1.5	0-0.5	1.0-1.5	1.5	NA	13,206	13,206	29	1.0	13,206	112
Between STM MH8 and MH9	Storm (450mm dia.)	15.9	15.9	1.0	1.5	NA	NA	NA	0-0.5	0	0	0	1.0	0	231
Between STM MH8 and MH9	Storm (450mm dia.)	15.7	15.7	1.0	1.5	NA	NA	NA	0.5-1.0	0	0	0	1.0	0	228
Between STM MH2 and MH8	Storm (1800mm x 900mm)	40.8	40.8	1.0	2.8	1.0-1.5	2.0-2.5	2.5	NA	66,203	66,203	49	1.0	66,203	1,142
Between STM MH2 and MH8	Storm (1800mm x 900mm)	40.8	40.8	1.0	2.8	NA	NA	NA	0-0.5	0	0	0	1.0	0	1,142
Between STM MH1 and MH2	Storm (250mm dia.)	19.5	19.5	1.0	1.3	1.5-2.0	2.5-3.0	3	NA	54,065	54,065	58	1.0	54,065	244
Between STM MH2 and MH3	Storm (1800mm x 900mm)	46.1	46.1	1.0	2.8	1.5-2.0	2.5-3.0	3	NA	90,883	90,883	58	1.0	90,883	1,291
Between STM MH2 and MH3	Storm (1800mm x 900mm)	45.8	45.8	1.0	2.8	1.0-1.5	2.0-2.5	2.5	NA	70,876	70,876	49	1.0	70,876	1,282
Between STM MH7 and MH8	Storm (1800mm x 900mm)	53.9	50.0	1.1	2.8	NA	NA	NA	0.5-1.0	0	0	0	1.1	0	1,400
East of CBMH1	Storm (250mm dia.)	4.8	4.8	1.0	1.3	NA	NA	NA	0.5-1.0	0	0	0	1.0	0	60
East of CBMH1	Storm (250mm dia.)	33.2	33.2	1.0	1.3	NA	NA	NA	>1.0	0	0	0	1.0	0	415
Between STM MH6 and MH7	Storm (1800mm x 900mm)	54.1	50.0	1.1	2.8	NA	NA	NA	0.5-1.0	0	0	0	1.1	0	1,400
Between STM MH5 and MH6	Storm (1800mm x 900mm)	29.2	29.2	1.0	2.8	NA	NA	NA	0-0.5	0	0	0	1.0	0	818
Between STM MH5 and MH13	Storm (200mm dia.)	7.6	7.6	1.0	1.2	NA	NA	NA	0-0.5	0	0	0	1.0	0	91
Between STM MH5 and MH13	Storm (200mm dia.)	7.6	7.6	1.0	1.2	0-0.5	1.0-1.5	1.5	NA	12,875	12,875	29	1.0	12,875	91
Between STM MH13 to RLCB8	Storm (200mm dia.)	23.4	23.4	1.0	1.2	0-0.5	1.0-1.5	1.5	NA	22,683	22,683	29	1.0	22,683	281
Between STM MH4 and MH6	Storm (1800mm x 900mm)	70.0	50.0	1.4	2.8	NA	NA	NA	0-0.5	0	0	0	1.4	0	1,400
Between STM MH4 and MH14	Storm (200mm dia.)	5.7	5.7	1.0	1.2	NA	NA	NA	0-0.5	0	0	0	1.0	0	68
Between STM MH14 and RLCB7	Storm (200mm dia.)	24.8	24.8	1.0	1.2	NA	NA	NA	0-0.5	0	0	0	1.0	0	298
North of STM CBMH4	Storm (300mm dia.)	30.7	30.7	1.0	1.3	NA	NA	NA	0-0.5	0	0	0	1.0	0	399
Between STM CBMH4 and RLCB6	Storm (200mm dia.)	47.9	47.9	1.0	1.2	NA	NA	NA	0-0.5	0	0	0	1.0	0	575
<b>Sub Total for Storm Sewers</b>										<b>331,000</b>	<b>331,000</b>			<b>331,000</b>	<b>14,000</b>
Between SAN MH1A and MH2A	Sanitary (200mm dia.)	40.3	40.3	1.0	1.2	1.0-1.5	2.0-2.5	2.5	NA	62,264	62,264	49	1.0	62,264	484
Between SAN MH2A and MH4A	Sanitary (200mm dia.)	44.9	44.9	1.0	1.2	1.0-1.5	2.0-2.5	2.5	NA	66,614	66,614	49	1.0	66,614	539
Between SAN MH2A and MH4A, MH3A and MH4	Sanitary (200mm dia.)	69.4	50	1.4	1.2	1.5-2.0	2.5-3.0	3	NA	90,612	90,612	58	1.4	125,770	600
Between SAN MH4A and LIFT	Sanitary (200mm dia.)	40.9	40.9	1.0	1.2	2.5-3.0	3.5-4.0	4	NA	118,337	118,337	78	1.0	118,337	491
Between SAN MH4A and LIFT	Sanitary (200mm dia.)	40.3	40.3	1.0	1.2	3.5-4.0	4.5-5.0	5	NA	160,008	160,008	97	1.0	160,008	484
Between SAN LIFT and MH8A	Sanitary (75mm dia.)	19.8	19.8	1.0	1.1	4.0-4.5	5.0-5.5	5.5	NA	131,903	131,903	107	1.0	131,903	213
Between SAN LIFT and MH8A	Sanitary (75mm dia.)	19.8	19.8	1.0	1.1	NA	NA	NA	0-0.5	0	0	0	1.0	0	213
Between SAN LIFT and MH7A	Sanitary (200mm dia.)	29.4	29.4	1.0	1.2	4.0-4.5	5.0-5.5	5.5	NA	157,233	157,233	107	1.0	157,233	353
Between SAN LIFT and MH7A	Sanitary (200mm dia.)	29.4	29.4	1.0	1.2	3.5-4.0	4.5-5.0	5	NA	136,834	136,834	97	1.0	136,834	353
Between SAN MH6A and MH7A	Sanitary (200mm dia.)	56.0	50	1.1	1.2	3.5-4.0	4.5-5.0	5	NA	179,899	179,899	97	1.1	201,487	600
Between SAN MH5A and MH6A	Sanitary (200mm dia.)	34.9	34.9	1.0	1.2	2.5-3.0	3.5-4.0	4	NA	108,527	108,527	78	1.0	108,527	419
Between SAN MH5A and MH6A	Sanitary (200mm dia.)	35.5	35.5	1.0	1.2	1-1.5	2.0-2.5	2.5	NA	57,651	57,651	49	1.0	57,651	426
<b>Sub Total for Sanitary Sewers</b>										<b>1,270,000</b>	<b>1,270,000</b>			<b>1,327,000</b>	<b>5,000</b>
<b>Total</b>										<b>1,601,000</b>	<b>1,601,000</b>			<b>1,657,000</b>	<b>19,000</b>

Note: NA - Not Applicable

# APPENDIX

## **E** WATER BUDGET CALCULATIONS – PRE- DEVELOPMENT

**TABLE E-1 PRE-DEVELOPMENT WATER BUDGET (BY CATCHMENT)**  
**HYDROGEOLOGICAL ASSESSMENT AND WATER BALANCE STUDY**  
**226 BROCK STREET EAST**  
**UXBRIDGE, ONTARIO**

Subcatchment Designation	Post Dev Cat Delineation	Outlet	Area (m <sup>2</sup> )	MOE TABLE 2 Components			MOE Infiltration Factor	Adjusted MOE Infiltration Factor	Precipitation (mm/a)	Precipitation Total (m <sup>2</sup> /a)	Precipitation Surplus (mm/a)	Evapotranspiration (m <sup>2</sup> /a)	Runon		Net Surplus		Infiltration		Runoff*		Total Infiltration + Runoff (m <sup>2</sup> /a)	
				Cover	Soil	Topography							(mm/a)	(m <sup>2</sup> /a)	(mm/a)	(mm/a)	(m <sup>2</sup> /a)	(mm/a)	(m <sup>2</sup> /a)	(mm/a)		(m <sup>2</sup> /a)
Cat A-1	Cat PE-1	Offsite to the Northeast via overland flow	697.1	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	617.7	327.1	245.3	0	327.1	228.0	171.0	81.8	57.0	228.0	
Cat A-2	Cat PD-2	Offsite to the Northeast via overland flow	261.1	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	231.4	327.1	146.0	0	327.1	85.4	245.3	64.0	81.8	21.3	85.4
Cat A-3	Cat PA1-3	Offsite to the Northeast via overland flow	184.4	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	163.4	327.1	103.1	0	327.1	60.3	245.3	45.2	81.8	15.1	60.3
Cat A-4	Cat PC-4	Offsite to the Northeast via overland flow	953.1	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	844.6	327.1	532.9	0	327.1	311.7	245.3	233.8	81.8	77.9	311.7
Cat A-5	Cat PA2-5	Offsite to the Northeast via overland flow	51.0	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	45.2	327.1	28.5	0	327.1	16.7	245.3	12.5	81.8	4.2	16.7
Cat A-6	Cat PF-6	Offsite to the Northeast via overland flow	227.6	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	201.7	327.1	127.3	0	327.1	74.5	245.3	55.8	81.8	18.6	74.5
Cat A-7	Cat PE-7	Offsite to the Northeast via overland flow	129.5	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	114.7	327.1	72.4	0	327.1	42.3	245.3	31.8	81.8	10.6	42.3
Cat A-8	Cat PE-8	Offsite to the Northeast via overland flow	395.0	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	350.1	327.1	220.9	0	327.1	129.2	245.3	96.9	81.8	32.3	129.2
Cat A-9	Cat PD-9	Offsite to the Northeast via overland flow	148.1	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	131.3	327.1	82.8	0	327.1	48.5	245.3	36.3	81.8	12.1	48.5
Cat A-10	Cat PA1-10	Offsite to the Northeast via overland flow	10.3	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	9.1	327.1	5.8	0	327.1	3.4	245.3	2.5	81.8	0.8	3.4
Cat A-11	Cat PA1-11	Offsite to the Northeast via overland flow	4.9	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	4.4	327.1	2.8	0	327.1	1.6	245.3	1.2	81.8	0.4	1.6
Cat A-12	Cat PA1-12	Offsite to the Northeast via overland flow	234.6	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	207.9	327.1	131.2	0	327.1	76.7	245.3	57.5	81.8	19.2	76.7
Cat A-13	Cat PA1-13	Offsite to the Northeast via overland flow	11.2	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	9.9	327.1	6.3	0	327.1	3.7	245.3	2.8	81.8	0.9	3.7
Cat A-14	Cat PA1-14	Offsite to the Northeast via overland flow	17.4	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	15.4	327.1	9.7	0	327.1	5.7	245.3	4.3	81.8	1.4	5.7
Cat A-15	Cat PC-15	Offsite to the Northeast via overland flow	571.6	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	506.5	327.1	319.6	0	327.1	186.9	245.3	140.2	81.8	46.7	186.9
Cat A-16	Cat PC-16	Offsite to the Northeast via overland flow	571.6	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	506.5	327.1	319.6	0	327.1	186.9	245.3	140.2	81.8	46.7	186.9
Cat A-17	Cat PB-17	Offsite to the Northeast via overland flow	157.9	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	139.9	327.1	88.3	0	327.1	51.6	245.3	38.7	81.8	12.9	51.6
Cat A-18	Cat PB-18	Offsite to the Northeast via overland flow	470.6	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	417.0	327.1	263.1	0	327.1	153.9	245.3	115.4	81.8	38.5	153.9
Cat A-19	Cat PB-19	Offsite to the Northeast via overland flow	10.3	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	9.1	327.1	5.8	0	327.1	3.4	245.3	2.5	81.8	0.8	3.4
Cat A-20	Cat PB-20	Offsite to the Northeast via overland flow	10.1	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	9.0	327.1	5.7	0	327.1	3.3	245.3	2.5	81.8	0.8	3.3
Cat A-21	Cat PB-21	Offsite to the Northeast via overland flow	9.8	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	8.7	327.1	5.5	0	327.1	3.2	245.3	2.4	81.8	0.8	3.2
Cat A-22	Cat PB-22	Offsite to the Northeast via overland flow	9.8	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	8.7	327.1	5.5	0	327.1	3.2	245.3	2.4	81.8	0.8	3.2
Cat A-23	Cat PB-23	Offsite to the Northeast via overland flow	10.1	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	8.9	327.1	5.6	0	327.1	3.3	245.3	2.5	81.8	0.8	3.3
Cat A-24	Cat PB-24	Offsite to the Northeast via overland flow	10.3	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	9.2	327.1	5.8	0	327.1	3.4	245.3	2.5	81.8	0.8	3.4
Cat A-25	Cat PB-25	Offsite to the Northeast via overland flow	3.8	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	3.4	327.1	2.2	0	327.1	1.3	245.3	0.9	81.8	0.3	1.3
Cat A-26	Cat PB-26	Offsite to the Northeast via overland flow	220.5	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	195.4	327.1	123.3	0	327.1	72.1	245.3	54.1	81.8	18.0	72.1
Cat A-27	Cat PB-27	Offsite to the Northeast via overland flow	221.3	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	196.1	327.1	123.7	0	327.1	72.4	245.3	54.3	81.8	18.1	72.4
Cat A-28	Cat PB-28	Offsite to the Northeast via overland flow	42.0	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	37.2	327.1	23.5	0	327.1	13.7	245.3	10.3	81.8	3.4	13.7
Cat A-29	Cat PB-29	Offsite to the Northeast via overland flow	43.1	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	38.2	327.1	24.1	0	327.1	14.1	245.3	10.6	81.8	3.5	14.1
Cat A-30	Cat PB-30	Offsite to the Northeast via overland flow	43.2	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	38.3	327.1	24.2	0	327.1	14.1	245.3	10.6	81.8	3.5	14.1
Cat A-31	Cat PB-31	Offsite to the Northeast via overland flow	42.5	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	37.7	327.1	23.8	0	327.1	13.9	245.3	10.4	81.8	3.5	13.9
Cat A-32	Cat PB-32	Offsite to the Northeast via overland flow	42.3	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	37.5	327.1	23.7	0	327.1	13.8	245.3	10.4	81.8	3.5	13.8
Cat A-33	Cat PB-33	Offsite to the Northeast via overland flow	39.8	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	35.2	327.1	22.2	0	327.1	13.0	245.3	9.8	81.8	3.3	13.0
Cat A-34	Cat PB-34	Offsite to the Northeast via overland flow	41.5	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	36.8	327.1	23.2	0	327.1	13.6	245.3	10.2	81.8	3.4	13.6
Cat A-35	Cat PB-35	Offsite to the Northeast via overland flow	37.2	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	32.9	327.1	20.8	0	327.1	12.2	245.3	9.1	81.8	3.0	12.2
Cat A-36	Cat PB-36	Offsite to the Northeast via overland flow	39.0	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	34.6	327.1	21.8	0	327.1	12.8	245.3	9.6	81.8	3.2	12.8
Cat A-37	Cat PB-37	Offsite to the Northeast via overland flow	39.6	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	35.1	327.1	22.1	0	327.1	12.9	245.3	9.7	81.8	3.2	12.9
Cat A-38	Cat PB-38	Offsite to the Northeast via overland flow	39.3	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	34.8	327.1	22.0	0	327.1	12.9	245.3	9.6	81.8	3.2	12.9
Cat A-39	Cat PB-39	Offsite to the Northeast via overland flow	39.7	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	35.2	327.1	22.2	0	327.1	13.0	245.3	9.7	81.8	3.2	13.0
Cat A-40	Cat PB-40	Offsite to the Northeast via overland flow	71.5	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	63.3	327.1	40.0	0	327.1	23.4	245.3	17.5	81.8	5.8	23.4
Cat A-41	Cat PB-41	Offsite to the Northeast via overland flow	71.5	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	63.4	327.1	40.0	0	327.1	23.4	245.3	17.5	81.8	5.8	23.4
Cat A-42	Cat PB-42	Offsite to the Northeast via overland flow	42.0	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	37.3	327.1	23.5	0	327.1	13.8	245.3	10.3	81.8	3.4	13.8
Cat A-43	Cat PB-43	Offsite to the Northeast via overland flow	3.6	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	3.2	327.1	2.0	0	327.1	1.2	245.3	0.9	81.8	0.3	1.2
Cat A-44	Cat PB-44	Offsite to the Northeast via overland flow	15.9	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	14.1	327.1	8.9	0	327.1	5.2	245.3	3.9	81.8	1.3	5.2
Cat A-45	Cat PB-45	Offsite to the Northeast via overland flow	16.0	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	14.2	327.1	9.0	0	327.1	5.2	245.3	3.9	81.8	1.3	5.2
Cat A-46	Cat PB-46	Offsite to the Northeast via overland flow	48.2	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	42.7	327.1	27.0	0	327.1	15.8	245.3	11.8	81.8	3.9	15.8
Cat A-47	Cat PB-47	Offsite to the Northeast via overland flow	73.0	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	64.7	327.1	40.8	0	327.1	23.9	245.3	17.9	81.8	6.0	23.9
Cat A-48	Cat PB-48	Offsite to the Northeast via overland flow	74.6	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	66.1	327.1	41.7	0	327.1	24.4	245.3	18.3	81.8	6.1	24.4
Cat A-49	Cat PB-49	Offsite to the Northeast via overland flow	71.1	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	63.1	327.1	39.8	0	327.1	23.3	245.3	17.5	81.8	5.8	23.3
Cat A-50	Cat PB-50	Offsite to the Northeast via overland flow	71.5	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	63.4	327.1	40.0	0	327.1	23.4	245.3	17.5	81.8	5.8	23.4
Cat A-51	Cat PB-51	Offsite to the Northeast via overland flow	72.6	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	64.4	327.1	40.6	0	327.1	23.8	245.3	17.8	81.8	5.9	23.8
Cat A-52	Cat PB-52	Offsite to the Northeast via overland flow	71.5	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	63.4	327.1	40.0	0	327.1	23.4	245.3	17.5	81.8	5.8	23.4
Cat A-53	Cat PB-53	Offsite to the Northeast via overland flow	176.3	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	156.2	327.1	98.5	0	327.1	57.6	245.3	43.2	81.8	14.4	57.6
Cat A-54	Cat PB-54	Offsite to the Northeast via overland flow	72.1	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	63.9	327.1	40.3	0	327.1	23.6	245.3	17.7	81.8	5.9	23.6
Cat A-55	Cat PB-55	Offsite to the Northeast via overland flow	2184.0	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	1935.4	327.1	1221.1	0	327.1	714.3	245.3	535.7	81.8	178.6	714.3
Cat A-56	Cat PB-56																					

**TABLE E-1 PRE-DEVELOPMENT WATER BUDGET (BY CATCHMENT)**  
**HYDROGEOLOGICAL ASSESSMENT AND WATER BALANCE STUDY**  
**226 BROCK STREET EAST**  
**UXBRIDGE, ONTARIO**

Subcatchment Designation	Post Dev Cat Delineation	Outlet	Area (m <sup>2</sup> )	MOE TABLE 2 Components			MOE Infiltration Factor	Adjusted MOE Infiltration Factor	Precipitation (mm/a)	Precipitation Total (m <sup>3</sup> /a)	Precipitation Surplus (mm/a)	Evapotranspiration (m <sup>3</sup> /a)	Runon		Net Surplus		Infiltration		Runoff*		Total Infiltration + Runoff (m <sup>3</sup> /a)	
				Cover	Soil	Topography							(mm/a)	(m <sup>3</sup> /a)	(mm/a)	(m <sup>3</sup> /a)	(mm/a)	(m <sup>3</sup> /a)	(mm/a)	(m <sup>3</sup> /a)		(mm/a)
Cat A-86	Cat PB-86	Offsite to the Northeast via overland flow	18.6	Building	0	Open Sandy Loam	0.4	0.25	0.65	0	886.2	16.5	797.6	1.7	0	797.6	14.9	0.0	0.0	797.6	14.9	14.9
Cat A-87	Cat PB-87	Offsite to the Northeast via overland flow	53.8	Building	0	Open Sandy Loam	0.4	0.25	0.65	0	886.2	47.7	797.6	4.8	0	797.6	42.9	0.0	0.0	797.6	42.9	42.9
Cat A-88	Cat PB-88	Offsite to the Northeast via overland flow	6.0	Building	0	Open Sandy Loam	0.4	0.25	0.65	0	886.2	5.3	797.6	0.5	0	797.6	4.8	0.0	0.0	797.6	4.8	4.8
Cat A-89	Cat PB-89	Offsite to the Northeast via overland flow	38.6	Building	0	Open Sandy Loam	0.4	0.25	0.65	0	886.2	34.2	797.6	3.4	0	797.6	30.8	0.0	0.0	797.6	30.8	30.8
Cat A-90	Cat PB-90	Offsite to the Northeast via overland flow	7.1	Building	0	Open Sandy Loam	0.4	0.25	0.65	0	886.2	6.3	797.6	0.6	0	797.6	5.7	0.0	0.0	797.6	5.7	5.7
Cat A-91	Cat PB-91	Offsite to the Northeast via overland flow	27.7	Building	0	Open Sandy Loam	0.4	0.25	0.65	0	886.2	24.5	797.6	2.5	0	797.6	22.1	0.0	0.0	797.6	22.1	22.1
Cat A-92	Cat PB-92	Offsite to the Northeast via overland flow	69.5	Building	0	Open Sandy Loam	0.4	0.25	0.65	0	886.2	61.6	797.6	6.2	0	797.6	55.4	0.0	0.0	797.6	55.4	55.4
Cat A-93	Cat PD-93	Offsite to the Northeast via overland flow	120.0	Building	0	Open Sandy Loam	0.4	0.25	0.65	0	886.2	106.4	797.6	10.6	0	797.6	95.7	0.0	0.0	797.6	95.7	95.7
Cat A-94	Cat PF-94	Offsite to the Northeast via overland flow	18.1	Building	0	Open Sandy Loam	0.4	0.25	0.65	0	886.2	16.0	797.6	1.6	0	797.6	14.4	0.0	0.0	797.6	14.4	14.4
Cat A-95	Cat PD-95	Offsite to the Northeast via overland flow	78.2	Building	0	Open Sandy Loam	0.4	0.25	0.65	0	886.2	69.3	797.6	6.9	0	797.6	62.3	0.0	0.0	797.6	62.3	62.3
Cat A-96	Cat PB-96	Offsite to the Northeast via overland flow	54.6	Building	0	Open Sandy Loam	0.4	0.25	0.65	0	886.2	48.4	797.6	4.8	0	797.6	43.6	0.0	0.0	797.6	43.6	43.6
Cat A-97	Cat PD-97	Offsite to the Northeast via overland flow	86.5	Gravel	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	76.7	341.1	47.2	0	341.1	29.5	238.7	20.7	102.3	8.9	29.5
Cat A-98	Cat PA2-98	Offsite to the Northeast via overland flow	19.2	Gravel	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	17.1	341.1	10.5	0	341.1	6.6	238.7	4.6	102.3	2.0	6.6
Cat A-99	Cat PA1-99	Offsite to the Northeast via overland flow	15.2	Gravel	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	13.4	341.1	8.3	0	341.1	5.2	238.7	3.6	102.3	1.6	5.2
Cat A-100	Cat PA1-100	Offsite to the Northeast via overland flow	6.4	Gravel	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	5.6	341.1	3.5	0	341.1	2.2	238.7	1.5	102.3	0.7	2.2
Cat A-101	Cat PA1-101	Offsite to the Northeast via overland flow	37.7	Gravel	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	33.4	341.1	20.6	0	341.1	12.9	238.7	9.0	102.3	3.9	12.9
Cat A-102	Cat PB-102	Offsite to the Northeast via overland flow	46.8	Gravel	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	41.5	341.1	25.5	0	341.1	16.0	238.7	11.2	102.3	4.8	16.0
Cat A-103	Cat PB-103	Offsite to the Northeast via overland flow	13.5	Gravel	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	11.9	341.1	7.3	0	341.1	4.6	238.7	3.2	102.3	1.4	4.6
Cat A-104	Cat PB-104	Offsite to the Northeast via overland flow	4.5	Gravel	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	3.9	341.1	2.4	0	341.1	1.5	238.7	1.1	102.3	0.5	1.5
Cat A-105	Cat PB-105	Offsite to the Northeast via overland flow	0.7	Gravel	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	0.6	341.1	0.4	0	341.1	0.2	238.7	0.2	102.3	0.1	0.2
Cat A-106	Cat PD-106	Offsite to the Northeast via overland flow	202.6	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	179.6	341.1	110.5	0	341.1	69.1	238.7	48.4	102.3	20.7	69.1
Cat A-107	Cat PD-107	Offsite to the Northeast via overland flow	96.5	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	85.5	341.1	52.6	0	341.1	32.9	238.7	23.0	102.3	9.9	32.9
Cat A-108	Cat PB-108	Offsite to the Northeast via overland flow	272.7	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	241.6	341.1	148.6	0	341.1	93.0	238.7	65.1	102.3	27.9	93.0
Cat A-109	Cat PB-109	Offsite to the Northeast via overland flow	274.0	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	242.8	341.1	149.4	0	341.1	93.5	238.7	65.4	102.3	28.0	93.5
Cat A-110	Cat PB-110	Offsite to the Northeast via overland flow	106.4	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	94.3	341.1	58.0	0	341.1	36.3	238.7	25.4	102.3	10.9	36.3
Cat A-111	Cat PB-111	Offsite to the Northeast via overland flow	29.9	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	26.5	341.1	16.3	0	341.1	10.2	238.7	7.1	102.3	3.1	10.2
Cat A-112	Cat PB-112	Offsite to the Northeast via overland flow	71.6	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	63.4	341.1	39.0	0	341.1	24.4	238.7	17.1	102.3	7.3	24.4
Cat A-113	Cat PB-113	Offsite to the Northeast via overland flow	74.6	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	66.1	341.1	40.7	0	341.1	25.4	238.7	17.8	102.3	7.6	25.4
Cat A-114	Cat PB-114	Offsite to the Northeast via overland flow	67.4	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	59.8	341.1	36.8	0	341.1	23.0	238.7	16.1	102.3	6.9	23.0
Cat A-115	Cat PB-115	Offsite to the Northeast via overland flow	55.1	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	48.8	341.1	30.0	0	341.1	18.8	238.7	13.2	102.3	5.6	18.8
Cat A-116	Cat PB-116	Offsite to the Northeast via overland flow	20.0	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	17.7	341.1	10.9	0	341.1	6.8	238.7	4.8	102.3	2.0	6.8
Cat A-117	Cat PB-117	Offsite to the Northeast via overland flow	20.7	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	18.3	341.1	11.3	0	341.1	7.1	238.7	4.9	102.3	2.1	7.1
Cat A-118	Cat PB-118	Offsite to the Northeast via overland flow	82.4	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	73.0	341.1	44.9	0	341.1	28.1	238.7	19.7	102.3	8.4	28.1
Cat A-119	Cat PB-119	Offsite to the Northeast via overland flow	40.0	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	35.4	341.1	21.8	0	341.1	13.6	238.7	9.5	102.3	4.1	13.6
Cat A-120	Cat PB-120	Offsite to the Northeast via overland flow	46.8	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	41.4	341.1	25.5	0	341.1	15.9	238.7	11.2	102.3	4.8	15.9
Cat A-121	Cat PB-121	Offsite to the Northeast via overland flow	34.8	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	30.9	341.1	19.0	0	341.1	11.9	238.7	8.3	102.3	3.6	11.9
Cat A-122	Cat PB-122	Offsite to the Northeast via overland flow	115.3	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	102.2	341.1	62.8	0	341.1	39.3	238.7	27.5	102.3	11.8	39.3
Cat A-123	Cat PB-123	Offsite to the Northeast via overland flow	96.0	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	85.1	341.1	52.3	0	341.1	32.7	238.7	22.9	102.3	9.8	32.7
Cat A-124	Cat PB-124	Offsite to the Northeast via overland flow	97.5	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	86.4	341.1	53.2	0	341.1	33.3	238.7	23.3	102.3	10.0	33.3
Cat A-125	Cat PB-125	Offsite to the Northeast via overland flow	132.3	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	117.2	341.1	72.1	0	341.1	45.1	238.7	31.6	102.3	13.5	45.1
Cat A-126	Cat PB-126	Offsite to the Northeast via overland flow	1.0	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	0.9	341.1	0.5	0	341.1	0.3	238.7	0.2	102.3	0.1	0.3
Cat A-127	Cat PE-127	Offsite to the Northeast via overland flow	343.4	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	304.3	327.1	192.0	0	327.1	112.3	261.6	89.8	65.4	22.5	112.3
Cat A-128	Cat PC-128	Offsite to the Northeast via overland flow	785.5	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	696.1	327.1	439.2	0	327.1	256.9	261.6	205.5	65.4	51.4	256.9
Cat A-129	Cat PF-129	Offsite to the Northeast via overland flow	76.6	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	67.9	327.1	42.8	0	327.1	25.1	261.6	20.0	65.4	5.0	25.1
Cat A-130	Cat PE-130	Offsite to the Northeast via overland flow	257.8	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	228.5	327.1	144.2	0	327.1	84.3	261.6	67.5	65.4	16.9	84.3
Cat A-131	Cat PA1-131	Offsite to the Northeast via overland flow	10.8	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	9.6	327.1	6.0	0	327.1	3.5	261.6	2.8	65.4	0.7	3.5
Cat A-132	Cat PA1-132	Offsite to the Northeast via overland flow	12.7	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	11.2	327.1	7.1	0	327.1	4.2	261.6	3.3	65.4	0.8	4.2
Cat A-133	Cat PC-133	Offsite to the Northeast via overland flow	572.4	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	507.2	327.1	320.0	0	327.1	187.2	261.6	149.8	65.4	37.4	187.2
Cat A-134	Cat PC-134	Offsite to the Northeast via overland flow	572.4	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	507.2	327.1	320.0	0	327.1	187.2	261.6	149.8	65.4	37.4	187.2
Cat A-135	Cat PB-135	Offsite to the Northeast via overland flow	320.4	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	283.9	327.1	179.1	0	327.1	104.8	261.6	83.8	65.4	21.0	104.8
Cat A-136	Cat PB-136	Offsite to the Northeast via overland flow	9.8	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	8.7	327.1	5.5	0	327.1	3.2	261.6	2.6	65.4	0.6	3.2
Cat A-137	Cat PB-137	Offsite to the Northeast via overland flow	9.8	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	8.7	327.1	5.5	0	327.1	3.2	261.6	2.6	65.4	0.6	3.2
Cat A-138	Cat PB-138	Offsite to the Northeast via overland flow	5.8	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	5.2	327.1	3.3	0	327.1	1.9	261.6	1.5	65.4	0.4	1.9
Cat A-139	Cat PB-139	Offsite to the Northeast via overland flow	9.6	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	8.5	327.1	5.4	0	327.1	3.1	261.6	2.5	65.4	0.6	3.1
Cat A-140	Cat PB-140	Offsite to the Northeast via overland flow	12.0	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	10.6	327.1	6.7	0	327.1	3.9	261.6	3.1	65.4	0.8	3.9
Cat A-141	Cat PB-141	Offsite to the Northeast via overland flow	41.2																			

**TABLE E-1 PRE-DEVELOPMENT WATER BUDGET (BY CATCHMENT)**  
 HYDROGEOLOGICAL ASSESSMENT AND WATER BALANCE STUDY  
 226 BROCK STREET EAST  
 UXBRIDGE, ONTARIO

Subcatchment Designation	Post Dev Cat Delineation	Outlet	Area (m <sup>2</sup> )	MOE TABLE 2 Components			MOE Infiltration Factor	Adjusted MOE Infiltration Factor	Precipitation (mm/a)	Precipitation Total (m <sup>3</sup> /a)	Precipitation Surplus (mm/a)	Evapotranspiration (m <sup>3</sup> /a)	Runon		Net Surplus		Infiltration		Runoff*		Total Infiltration + Runoff (m <sup>3</sup> /a)		
				Cover	Soil	Topography							(mm/a)	(m <sup>3</sup> /a)	(mm/a)	(m <sup>3</sup> /a)	(mm/a)	(m <sup>3</sup> /a)	(mm/a)	(m <sup>3</sup> /a)		(mm/a)	(m <sup>3</sup> /a)
Cat A-171	Cat PF-171	Offsite to the Northeast via overland flow	817.4	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	724.4	327.1	457.1	0	0	327.1	267.4	245.3	200.5	81.8	66.8	267.4
Cat A-172	Cat PF-172	Offsite to the Northeast via overland flow	712.6	Cultivated	0.1	Open Sandy Loam	0.4	0.25	0.75	0.75	886.2	631.5	327.1	398.4	0	0	327.1	233.1	245.3	174.8	81.8	58.3	233.1
Cat A-173	Cat PF-173	Offsite to the Northeast via overland flow	77.5	Building	0	Open Sandy Loam	0.4	0.25	0.65	0	886.2	68.7	797.6	6.9	0	0	797.6	61.8	0.0	0.0	797.6	61.8	61.8
Cat A-174	Cat PF-174	Offsite to the Northeast via overland flow	2.3	Building	0	Open Sandy Loam	0.4	0.25	0.65	0	886.2	2.1	797.6	0.2	0	0	797.6	1.8	0.0	0.0	797.6	1.8	1.8
Cat A-175	Cat PF-175	Offsite to the Northeast via overland flow	152.5	Gravel	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	135.2	341.1	83.2	0	0	341.1	52.0	238.7	36.4	102.3	15.6	52.0
Cat A-176	Cat PF-176	Offsite to the Northeast via overland flow	6.0	Gravel	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	5.3	341.1	3.3	0	0	341.1	2.0	238.7	1.4	102.3	0.6	2.0
Cat A-177	Cat PF-177	Offsite to the Northeast via overland flow	5.2	Gravel	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	4.6	341.1	2.8	0	0	341.1	1.8	238.7	1.2	102.3	0.5	1.8
Cat A-178	Cat PF-178	Offsite to the Northeast via overland flow	840.4	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	744.7	341.1	458.1	0	0	341.1	286.6	238.7	200.6	102.3	86.0	286.6
Cat A-179	Cat PF-179	Offsite to the Northeast via overland flow	14.3	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	12.7	341.1	7.8	0	0	341.1	4.9	238.7	3.4	102.3	1.5	4.9
Cat A-180	Cat PF-180	Offsite to the Northeast via overland flow	449.3	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	398.2	341.1	245.0	0	0	341.1	153.3	238.7	107.3	102.3	46.0	153.3
Cat A-181	Cat PD-181	Offsite to the Northeast via overland flow	24.4	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	21.7	341.1	13.3	0	0	341.1	8.3	238.7	5.8	102.3	2.5	8.3
Cat A-182	Cat PD-182	Offsite to the Northeast via overland flow	331.4	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	293.7	341.1	180.7	0	0	341.1	113.0	238.7	79.1	102.3	33.9	113.0
Cat A-183	Cat PD-183	Offsite to the Northeast via overland flow	375.3	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	332.6	341.1	204.6	0	0	341.1	128.0	238.7	89.6	102.3	38.4	128.0
Cat A-184	Cat PA2-184	Offsite to the Northeast via overland flow	13.7	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	12.1	341.1	7.5	0	0	341.1	4.7	238.7	3.3	102.3	1.4	4.7
Cat A-185	Cat PA2-185	Offsite to the Northeast via overland flow	65.7	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	58.2	341.1	35.8	0	0	341.1	22.4	238.7	15.7	102.3	6.7	22.4
Cat A-186	Cat PF-186	Offsite to the Northeast via overland flow	106.6	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	94.5	341.1	58.1	0	0	341.1	36.4	238.7	25.5	102.3	10.9	36.4
Cat A-187	Cat PF-187	Offsite to the Northeast via overland flow	24.1	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	21.3	341.1	13.1	0	0	341.1	8.2	238.7	5.8	102.3	2.5	8.2
Cat A-188	Cat PF-188	Offsite to the Northeast via overland flow	171.7	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	152.1	341.1	93.6	0	0	341.1	58.6	238.7	41.0	102.3	17.6	58.6
Cat A-189	Cat PD-189	Offsite to the Northeast via overland flow	59.8	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	53.0	341.1	32.6	0	0	341.1	20.4	238.7	14.3	102.3	6.1	20.4
Cat A-190	Cat PD-190	Offsite to the Northeast via overland flow	105.7	Lawns	0.05	Open Sandy Loam	0.4	0.25	0.7	0.7	886.2	93.7	341.1	57.6	0	0	341.1	36.0	238.7	25.2	102.3	10.8	36.0
Cat A-191	Cat PF-191	Offsite to the Northeast via overland flow	246.0	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	218.0	327.1	137.5	0	0	327.1	80.5	261.6	64.4	65.4	16.1	80.5
Cat A-192	Cat PF-192	Offsite to the Northeast via overland flow	181.8	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	161.1	327.1	101.6	0	0	327.1	59.4	261.6	47.6	65.4	11.9	59.4
Cat A-193	Cat PA1-193	Offsite to the Northeast via overland flow	143.6	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	127.2	327.1	80.3	0	0	327.1	47.0	261.6	37.6	65.4	9.4	47.0
Cat A-194	Cat PA1-194	Offsite to the Northeast via overland flow	47.9	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	42.5	327.1	26.8	0	0	327.1	15.7	261.6	12.5	65.4	3.1	15.7
Cat A-195	Cat PA1-195	Offsite to the Northeast via overland flow	4.3	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	3.8	327.1	2.4	0	0	327.1	1.4	261.6	1.1	65.4	0.3	1.4
Cat A-196	Cat PA1-196	Offsite to the Northeast via overland flow	150.5	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	133.4	327.1	84.2	0	0	327.1	49.2	261.6	39.4	65.4	9.8	49.2
Cat A-197	Cat PA1-197	Offsite to the Northeast via overland flow	27.9	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	24.7	327.1	15.6	0	0	327.1	9.1	261.6	7.3	65.4	1.8	9.1
Cat A-198	Cat PB-198	Offsite to the Northeast via overland flow	110.5	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	98.0	327.1	61.8	0	0	327.1	36.2	261.6	28.9	65.4	7.2	36.2
Cat A-199	Cat PB-199	Offsite to the Northeast via overland flow	13.7	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	12.1	327.1	7.7	0	0	327.1	4.5	261.6	3.6	65.4	0.9	4.5
Cat A-200	Cat PB-200	Offsite to the Northeast via overland flow	12.1	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	10.8	327.1	6.8	0	0	327.1	4.0	261.6	3.2	65.4	0.8	4.0
Cat A-201	Cat PB-201	Offsite to the Northeast via overland flow	61.3	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	54.3	327.1	34.3	0	0	327.1	20.0	261.6	16.0	65.4	4.0	20.0
Cat A-202	Cat PB-202	Offsite to the Northeast via overland flow	1682.9	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	886.2	1491.4	327.1	941.0	0	0	327.1	550.4	261.6	440.3	65.4	110.1	550.4
<b>Pre-Development Catchment A Total</b>		<b>Offsite to the Northeast via overland flow</b>	<b>26,118</b>								<b>886.2</b>	<b>23,146</b>	<b>340.1</b>	<b>14,262</b>	<b>0</b>	<b>0</b>	<b>340.1</b>	<b>8,884</b>	<b>244</b>	<b>6,365</b>	<b>96</b>	<b>2,519</b>	<b>8,884</b>
<b>SITE TOTAL</b>			<b>26,118</b>								<b>886.2</b>	<b>23,146</b>	<b>340.1</b>	<b>14,262</b>	<b>0</b>	<b>0</b>	<b>340.1</b>	<b>8,884</b>	<b>244</b>	<b>6,365</b>	<b>96</b>	<b>2,519</b>	<b>8,884</b>

# APPENDIX

## **F** WATER BUDGET CALCULATIONS – POST DEVELOPMENT

TABLE F-1 POST-DEVELOPMENT WATER BUDGET (BY CATCHMENT)  
HYDROGEOLOGICAL ASSESSMENT AND WATER BALANCE STUDY  
226 BROOK STREET EAST  
UXBRIDGE, ONTARIO

ANNUAL PRECIPITATION mm	EVAPORATION AND IMPERVIOUS AREAS		
	%	mm	%
886	10%	89	73%
		89	646

On-Site Subcatchment Designation	Outlet	Total Area (m <sup>2</sup> )	Impervious						Pervious		MOE TABLE 2 Components	MOE Infiltration Factor	Adjusted MOE Infiltration Factor	Inputs			Outputs																							
			Total Impervious		Assumed Buildings		Assumed Road/Parking/Amenities		Other Impervious					Total Pervious		Annual Average (m <sup>3</sup> /yr)	Surplus (Pervious) (m <sup>3</sup> /yr)	Surplus (Impervious) (m <sup>3</sup> /yr)	Total Inputs (m <sup>3</sup> /yr)	Evapotranspiration			Pervious Areas	Roof/ p Discoun	Infiltration Trenches	Total Infiltration	Pervious	Landscape Area Redirecte	Building	Road/ Driveway/Amenities	Other Impervious	Total Runoff	Total Runoff	Roof/Infiltrated	Infiltration Trenches	Net Runoff		Total Outputs		
			% of Total Area	(m <sup>2</sup> )	% of Impervious Area	(m <sup>2</sup> )	% of Impervious Area	(m <sup>2</sup> )	% of Total Area	(m <sup>2</sup> )				Cover	Soil					Topography	Pervious	Impervious														Evapotranspiration	Pervious Areas	Total Runoff	Total Runoff	Roof/Infiltrated
Cat PA1-3	Offsite to the north via overland flow	184.4	0%	0.0	0%	0.0	0%	0.0	0%	184	Lawns	0.05	0.7	163	63	0	163	101	0	101	44	0	0	44	19	0	0	0	0	19	0	0	102	19	886	163				
Cat PA1-10	Offsite to the north via overland flow	10.3	0%	10.3	0%	0.0	0%	100%	10.3	0.0	0.0	0.0	0.0	9	0	8	9	0	1	1	0	0	0	0	0	0	8	8	0	0	0	0	798	8	886	9				
Cat PA1-11	Offsite to the north via overland flow	4.9	100%	4.9	0%	0.0	0%	100%	4.9	0.0	0.0	0.0	0	0	0	0	0	0	0	0	0	0	0	0	0	4	4	0	0	0	0	0	0	798	4	886	4			
Cat PA1-12	Offsite to the north via overland flow	234.6	100%	234.6	0%	0.0	0%	100%	234.6	0.0	0.0	0.0	0	0	0	0	0	208	0	167	208	0	0	0	0	167	0	0	0	0	0	0	0	0	399	94	886	208		
Cat PA1-13	Offsite to the north via overland flow	11.2	100%	11.2	0%	0.0	0%	100%	11.2	0.0	0.0	0.0	0	0	0	0	0	10	0	9	10	0	0	0	0	0	0	9	9	0	0	0	0	0	798	9	886	10		
Cat PA1-14	Offsite to the north via overland flow	17.4	100%	17.4	0%	0.0	0%	100%	17.4	0.0	0.0	0.0	0	0	0	0	0	15	0	14	15	0	0	0	0	0	0	14	14	0	0	0	0	0	798	14	886	15		
Cat PA1-85	Offsite to the north via overland flow	7.2	0%	0.0	0%	0.0	0%	0.0	0.0	100%	7	Lawns	0.05	0.7	6	2	0	6	4	0	4	2	0	0	2	1	0	0	0	1	0	0	0	0	102	1	886	6		
Cat PA1-99	Offsite to the north via overland flow	15.2	0%	0.0	0%	0.0	0%	0.0	0.0	100%	15	Lawns	0.05	0.7	13	5	0	13	8	0	8	4	0	0	4	2	0	0	0	0	2	0	0	0	0	102	2	886	13	
Cat PA1-100	Offsite to the north via overland flow	6.4	100%	6.4	0%	0.0	0%	100%	6.4	0.0	0.0	0.0	0	0	0	5	6	0	5	6	1	1	0	0	0	0	5	5	0	0	0	0	0	0	798	5	886	6		
Cat PA1-101	Offsite to the north via overland flow	37.7	100%	37.7	100%	37.7	0%	0%	0.0	0.0	0.0	0.0	0	0	0	0	0	33	0	30	33	0	3	3	0	15	0	0	30	30	-15	0	0	0	399	15	886	33		
Cat PA1-131	Offsite to the north via overland flow	10.8	100%	10.8	0%	0.0	0%	100%	10.8	0.0	0.0	0.0	0	0	0	0	0	10	0	9	10	0	1	1	0	0	0	9	9	0	0	0	0	0	0	798	9	886	10	
Cat PA1-132	Offsite to the north via overland flow	12.7	100%	12.7	100%	12.7	0%	0%	0.0	0.0	0.0	0.0	0	0	0	0	0	11	0	11	0	1	1	0	5	0	10	10	-5	0	0	0	0	0	399	5	886	11		
Cat PA1-193	Offsite to the north via overland flow	143.6	0%	0.0	0%	0.0	0%	0%	0.0	100%	144	Lawns	0.05	0.7	127	49	0	127	78	0	78	34	0	0	34	15	0	0	0	15	0	0	0	0	0	102	15	886	127	
Cat PA1-194	Offsite to the north via overland flow	47.9	0%	0.0	0%	0.0	0%	0%	0.0	100%	48	Lawns	0.05	0.7	42	16	0	42	26	0	26	11	0	0	11	5	0	0	0	5	0	0	0	0	0	102	5	886	42	
Cat PA1-195	Offsite to the north via overland flow	4.3	100%	4.3	0%	0.0	0%	100%	4.3	0.0	0.0	0.0	0	0	0	0	0	4	0	0	0	0	0	0	0	0	0	3	3	0	0	0	0	0	798	3	886	4		
Cat PA1-196	Offsite to the north via overland flow	150.5	100%	150.5	100%	150.5	0%	0%	0.0	0.0	0.0	0.0	0	0	0	0	0	133	0	133	0	13	13	0	60	0	120	120	-60	0	0	0	0	0	399	60	886	133		
Cat PA1-197	Offsite to the north via overland flow	27.9	100%	27.9	100%	27.9	0%	0%	0.0	0.0	0.0	0.0	0	0	0	0	0	27.9	0	22	27.9	0	2	2	0	11	0	0	22	22	-11	0	0	0	0	399	11	886	25	
<b>Post-Development Catchment PA1 Total</b>	<b>Offsite to the north via overland flow</b>	<b>927</b>	<b>57%</b>	<b>529</b>	<b>50%</b>	<b>463</b>	<b>7%</b>	<b>65</b>	<b>0</b>	<b>43%</b>	<b>398</b>			<b>821</b>	<b>45</b>	<b>17</b>	<b>0</b>	<b>821</b>	<b>218</b>	<b>47</b>	<b>264</b>	<b>95</b>	<b>185</b>	<b>0</b>	<b>280</b>	<b>41</b>	<b>0</b>	<b>370</b>	<b>52</b>	<b>0</b>	<b>422</b>	<b>462</b>	<b>-185</b>	<b>0</b>	<b>0</b>	<b>300</b>	<b>278</b>	<b>886</b>	<b>821</b>	
Cat PA2-5	Offsite to the north via overland flow	51.0	0%	0.0	0%	0.0	0%	0%	0.0	100%	51	Lawns	0.05	0.7	45	17	0	45	28	0	28	12	0	0	12	5	0	0	0	0	0	0	0	0	0	102	5	886	45	
Cat PA2-98	Offsite to the north via overland flow	19.2	0%	0.0	0%	0.0	0%	0%	0.0	100%	19	Lawns	0.05	0.7	17	7	0	17	10	0	10	5	0	0	5	2	0	0	0	0	2	0	0	0	0	0	102	2	886	17
Cat PA2-184	Offsite to the north via overland flow	13.7	0%	0.0	0%	0.0	0%	0%	0.0	100%	14	Lawns	0.05	0.7	12	5	0	12	7	0	7	3	0	0	3	1	0	0	0	0	1	0	0	0	0	0	102	1	886	12
Cat PA2-185	Offsite to the north via overland flow	65.7	0%	0.0	0%	0.0	0%	0%	0.0	100%	66	Lawns	0.05	0.7	58	22	0	58	36	0	36	16	0	0	16	7	0	0	0	0	0	0	0	0	0	0	102	7	886	58
<b>Post-Development Catchment PA2 Total</b>	<b>Offsite to the north via overland flow</b>	<b>150</b>	<b>0%</b>	<b>0</b>	<b>0%</b>	<b>0</b>	<b>0%</b>	<b>0</b>	<b>0</b>	<b>100%</b>	<b>150</b>			<b>133</b>	<b>0</b>	<b>0</b>	<b>133</b>	<b>82</b>	<b>0</b>	<b>82</b>	<b>36</b>	<b>0</b>	<b>0</b>	<b>36</b>	<b>15</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>15</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>102</b>	<b>15</b>	<b>886</b>	<b>133</b>			
Cat PB-17	Offsite to the north via onsite catchbasins and storm sewers	157.9	100%	157.9	100%	157.9	0%	0%	0.0	0%	0	Building	0	0	140	0	126	140	0	14	14	0	0	0	0	0	0	126	126	0	0	0	0	0	0	798	126	886	140	
Cat PB-18	Offsite to the north via onsite catchbasins and storm sewers	470.6	100%	470.6	100%	470.6	0%	0%	0.0	0%	0	Building	0	0	417	0	375	417	0	42	42	0	0	0	0	0	0	375	375	0	0	0	0	0	0	0	798	375	886	417
Cat PB-19	Offsite to the north via onsite catchbasins and storm sewers	10.3	100%	10.3	0%	0.0	0%	0%	0.0	100%	10.3	0.0	0.0	0	0	8	9	0	1	1	0	0	0	0	0	0	0	8	8	0	0	0	0	0	0	0	798	8	886	9
Cat PB-20	Offsite to the north via onsite catchbasins and storm sewers	10.1	100%	10.1	0%	0.0	0%	0%	0.0	100%	10.1	0.0	0.0	0	0	8	9	0	1	1	0	0	0	0	0	0	0	8	8	0	0	0	0	0	0	0	798	8	886	9
Cat PB-21	Offsite to the north via onsite catchbasins and storm sewers	9.8	100%	9.8	0%	0.0	0%	0%	0.0	100%	9.8	0.0	0.0	0	0	8	9	0	1	1	0	0	0	0	0	0	0	8	8	0	0	0	0	0	0	0	798	8	886	9
Cat PB-22	Offsite to the north via onsite catchbasins and storm sewers	9.8	100%	9.8	0%	0.0	0%	0%	0.0	100%	9.8	0.0	0.0	0	0	8	9	0	1	1	0	0	0	0	0	0	0	8	8	0	0	0	0	0	0	0	798	8	886	9
Cat PB-23	Offsite to the north via onsite catchbasins and storm sewers	10.1	100%	10.1	0%	0.0	0%	0%	0.0	100%	10.1	0.0	0.0	0	0	8	9	0	1	1	0	0	0	0	0	0	0	8	8	0	0	0	0	0	0	0	798	8	886	9
Cat PB-24	Offsite to the north via onsite catchbasins and storm sewers	10.3	100%	10.3	0%	0.0	0%	0%	0.0	100%	10.3	0.0	0.0	0	0	8	9	0	1	1	0	0	0	0	0	0	0	8	8	0	0	0	0	0	0	0	798	8	886	9
Cat PB-25	Offsite to the north via onsite catchbasins and storm sewers	3.8	100%	3.8	0%	0.0	0%	0%	0.0	100%	3.8	0.0	0.0	0	0	3	3	0	0	0	0	0	0	0	0	0	0	3	3	0	0	0	0	0	0	0	798	3	886	3
Cat PB-26	Offsite to the north via onsite catchbasins and storm sewers	220.5	100%	220.5	100%	220.5	0%	0%	0.0	0%	0	Building	0	0	195	0	176	195	0	20	20	0	0	0	0	0	0	176	176	0	0	0	0	0	0	0	798	176	886	195
Cat PB-27	Offsite to the north via onsite catchbasins and storm sewers	221.3	100%	221.3	100%	221.3																																		





TABLE F-1 POST-DEVELOPMENT WATER BUDGET (BY CATCHMENT)  
 HYDROGEOLOGICAL ASSESSMENT AND WATER BALANCE STUDY  
 226 BROOK STREET EAST  
 UXBRIDGE, ONTARIO

ANNUAL PRECIPITATION	EVAPORATION AND EVAPOTRANSPIRATION FACTORS		
	mm	%	mm
886	10%	89	73%
			646

On-Site Subcatchment Designation	Outlet	Total Area (m <sup>2</sup> )	Impervious							Pervious		MOE TABLE 2 Components			MOE Infiltration Factor	Adjusted MOE Infiltration Factor	Inputs			Outputs																																
			Total Impervious		Assumed Buildings		Assumed Road/Parking/ Amenities		Other Impervious	Total Pervious		Cover	Soil	Topography			Annual Average (m <sup>3</sup> /yr)	Precipitation		Total Inputs (m <sup>3</sup> /yr)	Evapotranspiration			Infiltration			Runoff				Total Outputs																					
			% of Total Area	(m <sup>2</sup> )	% of Impervious Area	(m <sup>2</sup> )	% of Impervious Area	(m <sup>2</sup> )	(m <sup>2</sup> )	(m <sup>2</sup> )	% of Total Area							(m <sup>2</sup> )	Pervious		Impervious	Total	Pervious	Impervious	Total	Pervious	Roof p Discon	Infiltration Trenches	Total	Pervious	Landscaped Area Redirecte	Building	Road/ Driveway/ Amenities	Other Impervious	Total Impervious	Total Runoff	Rooftop Runoff Infiltrated	Infiltration Trenches		Net Runoff		Total Outputs										
			(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)			(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)	(mm/yr)											
Cat PF-6	Off-site to the north	227.6	0%	0.0	0%	0.0	0%	0.0	0.0	100%	228	Drainage Feature	0.2	Open Sandy Loam	0.4	0.25	0.85	0.85	202	55	0	202	147	0	147	46	0	0	46	8	0	0	0	0	0	0	0	8	0	0	0	36	8	886	202							
Cat PF-94	Off-site to the north	18.1	0%	0.0	0%	0.0	0%	0.0	0.0	100%	18	Drainage Feature	0.2	Open Sandy Loam	0.4	0.25	0.85	0.85	16	4	0	16	12	0	12	4	0	0	4	1	0	0	0	0	0	0	0	0	0	0	36	1	886	16								
Cat PF-129	Off-site to the north	76.6	0%	0.0	0%	0.0	0%	0.0	0.0	100%	77	Drainage Feature	0.2	Open Sandy Loam	0.4	0.25	0.85	0.85	68	18	0	68	49	0	49	16	0	0	16	3	0	0	0	0	0	0	0	0	0	0	0	36	3	886	68							
Cat PF-171	Off-site to the north	817.4	0%	0.0	0%	0.0	0%	0.0	0.0	100%	817	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	724	267	0	724	457	0	457	214	0	0	214	53	0	0	0	0	0	0	0	0	0	0	0	53	0	0	65	53	886	724				
Cat PF-172	Off-site to the north	712.6	0%	0.0	0%	0.0	0%	0.0	0.0	100%	713	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	631	233	0	631	398	0	398	186	0	0	186	47	0	0	0	0	0	0	0	0	0	0	0	0	47	0	0	65	47	886	631			
Cat PF-173	Off-site to the north	77.5	0%	0.0	0%	0.0	0%	0.0	0.0	100%	78	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	69	25	0	69	43	0	43	20	0	0	20	5	0	0	0	0	0	0	0	0	0	0	0	0	5	0	0	65	5	886	69			
Cat PF-174	Off-site to the north	2.3	0%	0.0	0%	0.0	0%	0.0	0.0	100%	2	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	2	1	0	2	1	0	1	1	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	65	0	886	2			
Cat PF-175	Off-site to the north	152.5	0%	0.0	0%	0.0	0%	0.0	0.0	100%	153	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	135	50	0	135	85	0	85	40	0	0	40	10	0	0	0	0	0	0	0	0	0	0	0	0	0	10	0	0	65	10	886	135		
Cat PF-176	Off-site to the north	6.0	0%	0.0	0%	0.0	0%	0.0	0.0	100%	6	Drainage Feature	0.2	Open Sandy Loam	0.4	0.25	0.85	0.85	5	1	0	5	4	0	4	1	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	36	0	886	5			
Cat PF-177	Off-site to the north	5.2	0%	0.0	0%	0.0	0%	0.0	0.0	100%	5	Drainage Feature	0.2	Open Sandy Loam	0.4	0.25	0.85	0.85	5	1	0	5	3	0	3	1	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	36	0	886	5				
Cat PF-178	Off-site to the north	840.4	0%	0.0	0%	0.0	0%	0.0	0.0	100%	840	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	745	275	0	745	470	0	470	220	0	0	220	55	0	0	0	0	0	0	0	0	0	0	0	0	0	55	0	0	65	55	886	745		
Cat PF-179	Off-site to the north	14.3	0%	0.0	0%	0.0	0%	0.0	0.0	100%	14	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	13	5	0	13	8	0	8	4	0	0	4	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	65	1	886	13	
Cat PF-180	Off-site to the north	449.3	0%	0.0	0%	0.0	0%	0.0	0.0	100%	449	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	398	147	0	398	251	0	251	118	0	0	118	29	0	0	0	0	0	0	0	0	0	0	0	0	0	0	29	0	0	65	29	886	398	
Cat PF-186	Off-site to the north	106.6	0%	0.0	0%	0.0	0%	0.0	0.0	100%	107	Drainage Feature	0.2	Open Sandy Loam	0.4	0.25	0.85	0.85	95	26	0	95	69	0	69	22	0	0	22	4	0	0	0	0	0	0	0	0	0	0	0	0	0	0	4	0	0	36	4	886	95	
Cat PF-187	Off-site to the north	24.1	0%	0.0	0%	0.0	0%	0.0	0.0	100%	24	Drainage Feature	0.2	Open Sandy Loam	0.4	0.25	0.85	0.85	21	6	0	21	16	0	16	5	0	0	5	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	36	1	886	21	
Cat PF-188	Off-site to the north	171.7	0%	0.0	0%	0.0	0%	0.0	0.0	100%	172	Drainage Feature	0.2	Open Sandy Loam	0.4	0.25	0.85	0.85	152	41	0	152	111	0	111	35	0	0	35	6	0	0	0	0	0	0	0	0	0	0	0	0	0	6	0	0	36	6	886	152		
Cat PF-191	Off-site to the north	246.0	0%	0.0	0%	0.0	0%	0.0	0.0	100%	246	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	218	80	0	218	138	0	138	64	0	0	64	16	0	0	0	0	0	0	0	0	0	0	0	0	0	0	16	0	0	65	16	886	218	
Cat PF-192	Off-site to the north	181.8	0%	0.0	0%	0.0	0%	0.0	0.0	100%	182	Uncultivated	0.15	Open Sandy Loam	0.4	0.25	0.8	0.8	161	59	0	161	102	0	102	48	0	0	48	12	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	12	0	0	65	12	886	161
<b>Post-Development Catchment PF Total</b>	<b>Off-site to the north</b>	<b>4,130</b>	<b>0%</b>	<b>0</b>	<b>0%</b>	<b>0</b>	<b>0%</b>	<b>0</b>	<b>0</b>	<b>100%</b>	<b>4,130</b>								<b>3,660</b>	<b>1,296</b>	<b>0</b>	<b>3,660</b>	<b>2,365</b>	<b>0</b>	<b>2,365</b>	<b>1,044</b>	<b>0</b>	<b>0</b>	<b>1,044</b>	<b>251</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>251</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>61</b>	<b>251</b>	<b>886</b>	<b>3,660</b>		
<b>Total Site</b>		<b>26,118</b>	<b>52%</b>	<b>13,574</b>	<b>25%</b>	<b>6,506</b>	<b>27%</b>	<b>7,068</b>	<b>0</b>	<b>48%</b>	<b>12,544</b>									<b>23,146</b>	<b>2,652</b>	<b>10,826</b>	<b>23,146</b>	<b>6,951</b>	<b>1,203</b>	<b>8,154</b>	<b>3,053</b>	<b>1,685</b>	<b>872</b>	<b>5,610</b>	<b>1,112</b>	<b>0</b>	<b>5,189</b>	<b>5,637</b>	<b>0</b>	<b>10,826</b>	<b>11,939</b>	<b>-1,685</b>	<b>-33</b>	<b>-872</b>	<b>359</b>	<b>9,382</b>	<b>886</b>	<b>23,146</b>								

**APPENDIX A4**

GEOMORPHIX REPORT


# Technical Design Brief: Tributary of Uxbridge Creek

## Town of Uxbridge, Ontario



Prepared for:  
Westlane Development Group Ltd.  
2 Farr Avenue  
Sharon, Ontario L0G 1V0

September 2, 2021  
PN20094




Report Prepared by: GEO Morphix Ltd.  
36 Main Street North, PO Box 205  
Campbellville, ON  
L0P 1B0

Report Title: Technical Design Brief: Tributary of Uxbridge Creek  
Town of Uxbridge, Ontario

Project Number: PN20094  
Status: Final  
Version: 1.2  
First Submission Date: October 27, 2020  
Revision Date: September 2, 2021

Prepared by: Lindsay Davis, M. Sc., P.Geo., CAN-CISEC, Ben Miller,  
B. Sc., CAN-CISEC  
Approved by: Paul Villard, Ph.D., P.Geo., CAN-CISEC, EP, CERP  
Approval Date: September 2, 2021



## Table of Contents

1	Introduction.....	1
2	Existing Conditions .....	1
	2.1 Geology.....	1
	2.2 Field Observations .....	2
3	Natural Bioswale Design .....	2
	3.1 Design Objectives.....	2
	3.2 Bioswale Geometries.....	2
	3.3 Bioswale Corridor .....	5
	3.4 Natural Erosion Control .....	5
4	Design Implementation .....	5
	4.1 Construction Timing .....	5
	4.2 Best Management Practices .....	6
	4.3 Post-Construction Monitoring .....	6
5	References .....	8

## List of Tables

<b>Table 1</b>	Bankfull parameters of the proposed bioswale.....	4
----------------	---	---

## Appendices

### Appendix A Site Map



## 1 Introduction

This design brief provides design recommendations for a bioswale design as part of the proposed 226 Brock Street residential development in the Town of Uxbridge, Ontario. The design serves to convey flows from the SWM Pond to the downstream tie in at Brock Street. A site map is provided in **Appendix A**. The bioswale design serves to improve form and function for this headwater drainage feature, enhance terrestrial diversity and the provision of organics, as well as enhance the retention and detention of flow and sediments.

In developing the design, the following activities were completed:

- A review of the available background materials, including the Conceptual Technical Design Brief (GEO Morphix Ltd., 2018)
- Provide details for the bioswale design including planform, cross sections, and necessary bioengineering details
- Hydraulic sizing of the bioswale materials
- Define corridor requirements
- Recommendations for design implementation including construction timing, and best management practices
- Development of a post-construction monitoring plan

This design brief is provided to facilitate review of the design, which outlines the current geomorphological condition of **Reach UCT1** and design considerations, provides technical details and recommendations for implementation, and monitoring of the proposed design.

## 2 Existing Conditions

Headwater drainage feature morphology and planform are largely governed by the flow regime and the availability and type of sediments (i.e., surficial geology) within the feature corridor. Physiography, riparian vegetation and land use also physically influence the headwater drainage feature. These factors are explored as they not only offer insight into what governs feature geomorphology, but also potential changes that could be expected in the future as they relate to a proposed activity. Field observations provide us with an in-depth understanding of the factors that impact feature geomorphology within the study area.

### 2.1 Geology

The study area is within the Peterborough Drumlin Field physiographic region, which is characterized as a drumlin field of various morphologies and orientation (OGS, 2010). The surficial geology is comprised of fine-textured glaciolacustrine deposits and ice-contact stratified deposits. The fine-textured glaciolacustrine deposits are located on the north side of the property and consist mainly of silt and clay with minor sand and gravel present. The ice contact stratified deposits are located at the south end of the property and consist of sand-gravel and minor silt, with clay and till present (OGS, 2003).



## 2.2 Field Observations

Field observations of **Reach UCT1** were completed on April 10, May 28, and July 19, 2018 previously as part of the conceptual design. The conceptual report recommended under the OSAP Headwater Drainage Assessment that *no management* was required for the reach based on the limited hydrology of the swale feature. However, the proponent wishes to retain the feature on the landscape as an enhanced bioswale. Given the feature has limited morphological variability as noted in the Conceptual Design Brief (GEO Morphix Ltd., 2018) restoration of the feature provides an opportunity to improve form and function and increase habitat and morphological variability.

## 3 Natural Bioswale Design

### 3.1 Design Objectives

As previously mentioned, the headwater drainage feature has limited morphology and degraded physical instream habitat conditions. The conceptual design has been reviewed previously by Lake Simcoe Region Conservation Authority and has been generally accepted. The below recommendation are consistent with those provided in the Conceptual Design Brief (GEO Morphix Ltd., 2018).

The proposed design will be a stable bioswale to provide a naturalized form and function. Headwater features like this reach provide detention and retention functions with regards to both flow and sediment. To maintain and enhance these functions, the design needs to provide good communication with the floodplain, as well as diversity in morphology. As such, online wet meadow features will be constructed throughout the corridor. These features enhance terrestrial habitat by increasing diversity and providing a more natural floodplain form. They also provide functional benefits by storing and discharging water over longer attenuated periods.

From a habitat perspective, the important contributions of the headwater drainage feature include organic inputs to the system, and provision of a complex valley system with elements that have a wide range of hydroperiods. The inclusion of a shallow and deep undulation typology with online wet meadow features provides a wide range of hydroperiods.


The primary objectives of the design, therefore, are to:

- Convey flows from the SWMP to the downstream channel
- Improve the function of the headwater drainage feature as well as its interaction with the floodplain
- Improve water quality by extending detention of water through online wet meadow features
- Improve riparian habitat by installing woody plantings and floodplain features

### 3.2 Bioswale Geometries

A bioswale containing shallow and deep undulations will convey flows along the south of the property into an enhanced bioswale feature with online wet meadows that flows along the east of the property. This feature will provide significant improvements to the headwater drainage feature, as it essentially replicates a natural system. When it is assessed to be an appropriate feature, a bioswale system offers numerous benefits, namely:



- 
- Bed relief for flow variability
  - Improve the function of the headwater drainage feature as well as its interaction with the floodplain
  - Improve water quality by extending detention of water through online wet meadow features and providing infiltration
  - Provide organic inputs through vegetation establishment

Bioswale dimensions are determined by bankfull discharge, as this represents what is generally considered the feature-forming discharge. Back-calculation of discharge from a reference reach, along with support from hydrological modelling, is usually the most appropriate. Due to the lack of a defined feature, and historical impacts to the headwater drainage feature because of agricultural activities, the computed discharge could not be considered accurate or reliable. Additionally, due to changes in hydrology likely to occur as a result of the development, a more appropriate discharge based on hydrological modelling was determined for the reach. Vincent & Associates (2000) completed hydrologic modelling upon review of post-development conditions and computed a bankfull discharge of 0.07 m<sup>3</sup>/s. This discharge outlets from the Block 57 stormwater management (SWM) pond and is based on the 2-year storm event (Vincent & Associates, 2000).

Shallow and deep undulation geometries, as well as anticipated bankfull flow conditions, are provided in **Table 1**. A simple Manning's approach was used to size the bioswale dimensions. Since deep undulations contain dead space, this model overpredicts the amount of discharge that they convey. The modelled values for the shallow undulations give a better prediction of the bioswale capacity. The bioswale design comprises of a single reach, which begins as a straight bioswale within a narrow corridor extending 136 m before entering a wider corridor where the bioswale extends 173 m and contains online wetland features. The entire bioswale design is characterized by a constant bankfull gradient of 0.54% and has a total length of 312 m. The bankfull width and depth range from 1.20 m to 1.40 m and 0.15 m to 0.25 m for the shallow and deep undulations, respectively.

**Table 1. Bankfull parameters of the proposed bioswale**

Bioswale parameter	Bioswale Geometries	
	Shallow Undulation	Deep Undulation
Bankfull width (m)†	1.20	1.40
Average bankfull depth (m)†	0.11	0.14
Maximum bankfull depth (m)†	0.15	0.25
Bankfull width-to-depth ratio	8.00	5.60
Bioswale gradient (%)	1.8	0.54
Bankfull gradient (%)	0.54	0.54
Manning's roughness coefficient, <i>n</i>	0.04	0.03
Mean bankfull velocity (m/s) *	0.67	0.63
Bankfull discharge (m <sup>3</sup> /s) *	0.09	0.13
Discharge to accommodate (m <sup>3</sup> /s)	0.07	0.07
Tractive force at bankfull (N/m <sup>2</sup> )††	26.48	14.71
Stream power (W/m)††	15.19	7.48
Unit stream power (W/m <sup>2</sup> )††	14.47	7.87
Maximum grain size entrained (m) **	0.03	0.02
Mean grain size entrained **	0.02	0.01

† Based on bankfull gradient


†† Based on riffle gradient

\* Based on Manning's equation; as pools contain ineffective space, the velocity and discharge conveyed in them are not presented

\*\* Based on Shields equation, assuming Shields parameter equals 0.06 (gravel)

The sizing of proposed substrate materials was guided by a review of hydraulic conditions in the typical headwater drainage feature cross sections. To provide for a stable bed and level of sorting, native material is proposed for the shallow and deep undulations. A mix of topsoil and granular 'b' is proposed for the online wet meadows to provide for a stable bed and level of sorting, while still maintaining the character of the native material and providing slightly higher stability and opportunity for sediment sorting. Granular 'b' consists of a mix of stone where approximately 20% - 50% of the stone is greater than 0.005 m in diameter, but nothing larger than 0.15 m in diameter. These materials will always have a core of sediment that is not entrained under bankfull flow conditions. A mix of relatively larger substrate (0.15 - 0.20 m diameter riverstone) and granular 'b' is proposed for the stone core wetland, located immediately downstream of the SWM pond headwall. These materials will provide higher stability and will always have a core of sediment that is not entrained under larger storm events (i.e., 100-yr).

The bioswale banks and online wet meadows will be restored using native plant species. This includes appropriate species for the various seed mixes as well as woody vegetation. The plantings are intended to enhance the terrestrial habitat through the provision of habitat diversity, increase floodplain soil stability, and increase floodplain roughness and sedimentation. A tree compensation plan has been completed by Cosburn Nauboris Ltd. Landscape Architects to provide compensation



for the trees being removed along the southern property limit. Additional plantings for the remainder of the corridor are provided on drawing RES-1 completed by GEO Morphix Ltd.

### **3.3 Bioswale Corridor**

The bioswale is expected to fully vegetated and have intermittent flows. Given the limited energy and vegetation control, the feature is unlikely to migrate or adjust its planform resulting in no erosion hazard associated with the feature. The valley walls are less than 2.5 m in height, therefore it is not considered a confined system and does not require an erosion setback.

Online wet meadow features will be constructed in addition to the bioswale. These features provide functional benefits such as short-term water retention and sediment banking. Additionally, these features enhance local recharge by allowing for infiltration. Mounds are to be included within the wet meadows to provide added morphological variation.

### **3.4 Natural Erosion Control**

Newly constructed features can be vulnerable to erosion. This is particularly true before vegetation has established along the bioswale banks. While low-flow events should not intensify erosion, the concern for erosion occurs when there are high flows or precipitation events during construction.

For immediate erosion protection, mechanical stabilization in the form of biodegradable erosion control blankets (i.e., coir cloth, jute mat, etc.) should be used. As the blankets will biodegrade over time, this serves as a short-term stabilization measure.

For long-term stability, implementation of a planting plan is recommended. This includes deep rooting native grasses and other herbaceous species seeded along and within bioswale sections, prescription of flood tolerant native shrub and tree species, and use of seed banks within the local soil. Shrubs should be planted close to the bioswale margins to provided maximum benefit with respect to stabilization and bioswale cover.


Potential erosion locations (i.e., along the outside meander bends, immediately downstream of wet meadow features, etc.) should be anticipated, and should be reflected in the planting plan. Live staking and shrub stock should be used adjacent to the bioswale bank to provide immediate benefit as well as long-term infilling. If appropriate live staking methods are followed, this method should provide greater benefits than simple potted or bare root shrub plating. This is because of the potential for higher densities with live staking.

## **4 Design Implementation**

### **4.1 Construction Timing**

Based on resident fish species and their respective life cycles, in-stream work will be restricted to July 1<sup>st</sup> to March 31<sup>st</sup>, unless otherwise directed by the Ministry of Natural Resources and Forestry (MNRF).

Vegetation removals associated with clearing, site access and staging should occur outside the key breeding bird period for migratory birds, identified by Environment Canada, to ensure compliance



with the Migratory Birds Convention Act (MBCA), 1994 and Migratory Bird Regulations. The breeding season for migratory birds in this part of the country typically extends from as early as March 1 to as late as September 15. Should tree removals be required during the key breeding bird season, a qualified biologist should inspect those trees 24 to 48 hours prior to removal to ensure that they do not contain nesting birds. It is understood that the MBCA is not restricted to cutting woody vegetation, but also applies to topsoil stripping and grubbing activities, as there are ground nesting bird species that are protected under the Act.

## **4.2 Best Management Practices**

Site inspection should be performed by an inspector with experience overseeing natural feature construction works, as this type of work differs considerably from engineering projects. An experienced inspector will be able to provide quick and appropriate response to issues that may arise and ensure that construction proceeds in accordance with the approved design and contract.

The limits of construction will be delineated to prevent unanticipated impacts to natural surroundings, including trees and the headwater drainage feature. Most of the bioswale can be constructed without interference to the existing headwater drainage feature. To complete the connection with the existing feature, flows will be conveyed around the work area using cofferdams and bypass pumping such that the bioswale can be constructed fully isolated from the active flow area.

All isolated work areas will be dewatered to perform work under dry conditions. Water will be pumped to a sediment filtration system located at least 30 m from the receiving headwater drainage feature and be allowed to naturally flow over a well-vegetation surface and ultimately return to the headwater drainage feature downstream of the work area. This will allow particles to settle before reaching the headwater drainage feature.

All materials and equipment will be stored and operated in such a manner that prevents any deleterious substances from entering the water. Vehicle and equipment re-fuelling and/or maintenance will be conducted away from the headwater drainage feature and be free of fluid leaks and externally cleaned/degreased to prevent the release of deleterious substances.

## **4.3 Post-Construction Monitoring**

A post-construction monitoring program is recommended to assess the performance of the implemented design. Monitoring observations can also be used to determine the need for remedial works. Monitoring is recommended for two full calendar years following the year of construction.

The following monitoring and reporting activities are proposed:

- General observations of the bioswale works should be documented after construction and after the first large flooding event to identify any potential areas of erosion concern
- Collection of a photographic record of site conditions
- Total station as-built survey of the bioswale planform, longitudinal profile and cross sections just after construction to obtain reference data for the following two years
- A general vegetation survey in the spring of each year to ensure plant survivability (minimum 90%)

- Re-survey of the longitudinal profile and monumented cross sections for two years following construction
- A yearly report for the first year, with a final report at the end of the two-year period

The monitoring would commence immediately after construction and sites would be reviewed annually to identify natural variability of the system. Reporting would be provided annually, with a summary report at the end of each year. Any plants found within a two-year period that are dead, defective or not in a healthy growing condition will be replaced as part of the warranty.

We trust this report meets your requirements. Should you have any questions, please contact us.

Respectfully submitted,



Paul Villard Ph.D., P.Geo., CAN-CISEC, EP, CERP  
Director, Principal Geomorphologist



Lindsay Davis, M.Sc., P.Geo., CAN-CISEC  
Geomorphologist



## 5 References

GEO Morphix Ltd. 2018. Conceptual Design Brief: Tributary of Uxbridge Creek. Town of Uxbridge, Ontario. Project No.: 18072.

Ontario Geological Survey (OGS). 2003. Surficial Geology of Southern Ontario.

Stanfield, L. (editor). 2013. Ontario Stream Assessment Protocol. Version 9.0. Fisheries Policy Section. Ontario Ministry of Natural Resources. Peterborough, Ontario. 505 Pages.

Toronto and Region Conservation Authority and Credit Valley Conservation (TRCA/CVC). 2014. Evaluation, Classification and Management of Headwater Drainage Features Guidelines

Vincent & Associates. 2000. Coral Creek Homes Stormwater Management Detention Facility. Drawing No. SW-1



## **Appendix A Site Map**



HERREMA BOULEVARD

LOW BOULEVARD

FOURTH AVENUE

DONLAND LANE

BROCK STREET

Stormwater Management Pond

NEIKIDD LANE

PLANKS LANE

BROWNSCOMBE CRESCENT

Tributary of Uxbridge Creek

**GEO MORPHIX**

**Tributary of Uxbridge Creek**

226 Brock Street,  
Town of Uxbridge


Westlane Development Group Ltd.

0 50


Metres

Imagery: Google Earth Pro, 2016.






KEY MAP  
N.T.S.



PLANFORM  
1:250



PROFILE  
H = 1:500; V=1:50

GENERAL NOTES

1. ALL CONTRACT DRAWINGS, SPECIFICATIONS AND APPLICABLE PERMITS MUST BE KEPT ON SITE DURING CONSTRUCTION FOR REFERENCE.
2. THE CONTRACTOR MUST NOTIFY THE CONTRACT ADMINISTRATOR AND CONSERVATION AUTHORITY OF THE INTENT TO COMMENCE WORK AT LEAST 48 HOURS IN ADVANCE.
3. THE CONTRACTOR IS RESPONSIBLE FOR ALL UTILITY LOCATES.
4. LAYOUT MUST BE REVIEWED AND APPROVED BY THE CONTRACT ADMINISTRATOR.
5. DESIGNER OR REPRESENTATIVE SHALL BE PRESENT DURING CONSTRUCTION TO PROVIDE GUIDANCE ON INSTALLATION OF THE FEATURES.

TIMING OF WORKS

1. WORKS SHALL BE COMPLETED BETWEEN JULY 1ST TO MARCH 31ST.
2. TREE CLEARING SHOULD BE COMPLETED OUTSIDE THE BIRD NESTING SEASON TO COMPLY WITH THE FEDERAL MIGRATORY BIRDS CONVENTION ACT. ANY TREES THAT REQUIRE REMOVAL OUTSIDE OF THIS TIMING WINDOW MUST FIRST BE INSPECTED BY A QUALIFIED BIOLOGIST 24-48 HOURS PRIOR TO REMOVAL TO DETERMINE THE PRESENCE OF NESTING BIRDS.
3. THE WEATHER FORECAST SHOULD BE CONTINUALLY MONITORED TO ENSURE THAT WORKS ARE UNDERTAKEN ONLY DURING FAVOURABLE WEATHER CONDITIONS.
4. COMPLETE THE WORKS WITH MINIMAL AVOIDABLE INTERRUPTIONS ONCE THEY COMMENCE.

SITE AND MATERIAL MANAGEMENT

1. ALL CONSTRUCTION EQUIPMENT AND MATERIALS (IMPORTED OR EXCAVATED) MUST BE STORED AT LEAST 30 m AWAY FROM ANY WATERBODY IN A STABLE AREA ABOVE THE ACTIVE FLOODPLAIN, OR IN A DESIGNATED STAGING/STORAGE AREA.
2. IN THE EVENT OF AN UNEXPECTED STORM, ALL UNFIXED ITEMS THAT HAVE THE POTENTIAL TO CAUSE A SPILL OR AN OBSTRUCTION TO FLOW MUST BE MOVED TO A STABLE AREA ABOVE ACTIVE FLOODPLAIN.
3. STOCKPILES MUST BE LOCATED OUTSIDE THE ISOLATED WORK AREAS.
4. STABILIZE STOCKPILED SOILS THAT ARE STORED FOR PROLONGED PERIODS WITH THE APPLICATION OF A NURSE CROP AT A RATE OF 60 kg/ha.
5. STABILIZE, TEMPORARILY OR PERMANENTLY, ANY DISTURBED AREAS AS WORK PROGRESSES, OR SOON AS CONDITIONS ALLOW. ON SOILS THAT WILL BE EXPOSED FOR PROLONG PERIODS, TEMPORARILY INSTALL A BIODEGRADABLE EROSION CONTROL BLANKET ON EXPOSED SOILS, OR APPLY A NURSE CROP AT A RATE OF 60 KG/HA.
6. MINIMIZE THE AREA OF DISTURBANCE TO THE EXTENT POSSIBLE.
7. ALL VEGETATION, ADJACENT TO THE WORK AREA, MUST BE PROTECTED AND DELINEATED WITH CONSTRUCTION FENCING OR TREE PROTECTION BARRIERS.
8. ALL GRADES IN THE AREA REGULATED BY THE CONSERVATION AUTHORITY MUST BE MAINTAINED OR MATCHED, UNLESS OTHERWISE AUTHORIZED BY THE APPLICABLE PERMIT.

EROSION AND SEDIMENT CONTROL

1. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSTALLED PRIOR TO START OF WORKS.
2. SEDIMENT CONTROLS MUST BE INSPECTED DAILY TO ENSURE THAT THEY ARE IN GOOD REPAIR AND FUNCTIONING AS INTENDED.
3. EROSION AND SEDIMENT CONTROLS MUST BE MAINTAINED DURING CONSTRUCTION, AND ANY REQUIRED REPAIRS OR REPLACEMENTS MUST BE COMPLETED WITHIN 24 HOURS AFTER THEY HAVE BEEN IDENTIFIED DURING THE MONITORING.
4. EROSION AND SEDIMENT CONTROL MEASURES MAY REQUIRE PERIODIC ADJUSTMENTS TO REFLECT CHANGING SITE CONDITIONS. THE CONTRACTOR WILL BE RESPONSIBLE FOR THESE ADJUSTMENTS TO ENSURE PROPER FUNCTION.
5. ANY CHANGES TO THE EROSION AND SEDIMENT CONTROL PLAN BEYOND MINOR ADJUSTMENTS MUST BE APPROVED BY THE CONTRACT ADMINISTRATOR.
6. ADDITIONAL EROSION AND SEDIMENT CONTROL SUPPLIES MUST BE KEPT ON SITE IN ORDER TO FACILITATE IMMEDIATE REPAIRS AND/OR UPGRADES AS NEEDED.
7. ALL TEMPORARY SEDIMENT CONTROLS MUST BE REMOVED AFTER THE CONTRACT ADMINISTRATOR DEEMS THE SITE TO BE STABLE.

DELETERIOUS SUBSTANCE CONTROL/SPILL MANAGEMENT

1. PREVENT THE RELEASE OF SEDIMENT, SEDIMENT-LADEN WATER, RAW CONCRETE, CONCRETE LEACHATE OR ANY OTHER DELETERIOUS SUBSTANCES INTO ANY WATERBODY, RAINWATER, OR STORM SEWER SYSTEM.
2. ENSURE EQUIPMENT AND MACHINERY ARE IN GOOD OPERATING CONDITION (POWER WASHED), FREE OF LEAKS, EXCESS OIL, AND GREASE.
3. NO EQUIPMENT REFUELLING OR SERVICING SHOULD BE UNDERTAKEN WITHIN 30 m OF ANY WATERCOURSE OR SURFACE WATER DRAINAGE.
4. A SPILL CONTAINMENT KIT MUST BE READILY ACCESSIBLE ON SITE IN THE EVENT OF A RELEASE OF A DELETERIOUS SUBSTANCE TO THE ENVIRONMENT. ON-SITE STAFF MUST BE TRAINED IN ITS USE.
5. THE CONTRACT ADMINISTRATOR MUST BE NOTIFIED IMMEDIATELY IN THE EVENT OF A SPILL OF DELETERIOUS SUBSTANCE.

WORK AREA ISOLATION

1. ALL WORK IN ISOLATED WORK AREAS MUST BE COMPLETED IN THE DRY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.
2. THE UNWATERING DISCHARGE LOCATION MUST BE LOCATED AT LEAST 30 m FROM ANY WATERCOURSE OR WETLAND IN AN AREA WITH DENSE VEGETATIVE GROUNDCOVER, AND WHERE THE DISCHARGE CAN RETURN TO THE WATERBODY DOWNSTREAM OF THE WORK AREA OVER THE GROUNDCOVER.

5.	21/09/02	LD	THIRD DETAILED DESIGN SUBMISSION TO LSRCA
4.	21/05/04	LD	SECOND DETAILED DESIGN SUBMISSION TO LSRCA
3.	20/10/27	LD	FIRST DETAILED DESIGN SUBMISSION TO LSRCA
2.	MARCH 2019	LD	SECOND SUBMISSION LSRCA
1.	AUGUST 2018	LD	FIRST SUBMISSION LSRCA
	DATE	BY	REVISIONS


DESIGNED BY: PV  
DRAWN BY: LD / BM  
CHECKED BY: PV  
DATE: SEPTEMBER 2, 2021

PAUL VILLARD  
PRACTISING MEMBER  
0957  
ONTARIO  
21/09/02

GEO MORPHIX  
Geomorphology  
Earth Science  
Observations  
36 Main Street North, PO Box 205  
Campbellville, Ontario L0P 1B0  
T: 416.920.0926  
www.geomorphix.com

226 BROCK STREET EAST  
WESTLANE DEVELOPMENT GROUP LTD.

BIOSWALE DESIGN  
PLANFORM AND PROFILE



KEY MAP  
N.T.S.

GENERAL NOTES

1. ALL CONTRACT DRAWINGS, SPECIFICATIONS AND APPLICABLE PERMITS MUST BE KEPT ON SITE DURING CONSTRUCTION FOR REFERENCE.
2. THE CONTRACTOR MUST NOTIFY THE CONTRACT ADMINISTRATOR AND CONSERVATION AUTHORITY OF THE INTENT TO COMMENCE WORK AT LEAST 48 HOURS IN ADVANCE.
3. THE CONTRACTOR IS RESPONSIBLE FOR ALL UTILITY LOCATES.
4. LAYOUT MUST BE REVIEWED AND APPROVED BY THE CONTRACT ADMINISTRATOR.
5. DESIGNER OR REPRESENTATIVE SHALL BE PRESENT DURING CONSTRUCTION TO PROVIDE GUIDANCE ON INSTALLATION OF THE FEATURES.

TIMING OF WORKS

1. WORKS SHALL BE COMPLETED BETWEEN JULY 1ST TO MARCH 31ST.
2. TREE CLEARING SHOULD BE COMPLETED OUTSIDE THE BIRD NESTING SEASON TO COMPLY WITH THE FEDERAL MIGRATORY BIRDS CONVENTION ACT. ANY TREES THAT REQUIRE REMOVAL OUTSIDE OF THIS TIMING WINDOW MUST FIRST BE INSPECTED BY A QUALIFIED BIOLOGIST 24-HOURS PRIOR TO REMOVAL TO DETERMINE THE PRESENCE OF NESTING BIRDS.
3. THE WEATHER FORECAST SHOULD BE CONTINUALLY MONITORED TO ENSURE THAT WORKS ARE UNDERTAKEN ONLY DURING FAVOURABLE WEATHER CONDITIONS.
4. COMPLETE THE WORKS WITH MINIMAL AVOIDABLE INTERRUPTIONS ONCE THEY COMMENCE.

SITE AND MATERIAL MANAGEMENT

1. ALL CONSTRUCTION EQUIPMENT AND MATERIALS (IMPORTED OR EXCAVATED) MUST BE STORED AT LEAST 30 m AWAY FROM ANY WATERBODY IN A STABLE AREA ABOVE THE ACTIVE FLOODPLAIN, OR IN A DESIGNATED STAGING/STORAGE AREA.
2. IN THE EVENT OF AN UNEXPECTED STORM, ALL UNFIXED ITEMS THAT HAVE THE POTENTIAL TO CAUSE A SPILL OR AN OBSTRUCTION TO FLOW MUST BE MOVED TO A STABLE AREA ABOVE ACTIVE FLOODPLAIN.
3. STOCKPILES MUST BE LOCATED OUTSIDE THE ISOLATED WORK AREAS.
4. STABILIZE STOCKPILED SOILS THAT ARE STORED FOR PROLONGED PERIODS WITH THE APPLICATION OF A NURSE CROP AT A RATE OF 60 KG/HA.
5. STABILIZE, TEMPORARILY OR PERMANENTLY, ANY DISTURBED AREAS AS WORK PROGRESSES, OR SOON AS CONDITIONS ALLOW. ON SOILS THAT WILL BE EXPOSED FOR PROLONG PERIODS, TEMPORARILY INSTALL A BIODEGRADABLE EROSION CONTROL BLANKET ON EXPOSED SOILS, OR APPLY A NURSE CROP AT A RATE OF 60 KG/HA.
6. MINIMIZE THE AREA OF DISTURBANCE TO THE EXTENT POSSIBLE.
7. ALL VEGETATION, ADJACENT TO THE WORK AREA, MUST BE PROTECTED AND DELINEATED WITH CONSTRUCTION FENCING OR THE PROTECTION BARRIERS.
8. ALL GRADES IN THE AREA REGULATED BY THE CONSERVATION AUTHORITY MUST BE MAINTAINED OR MATCHED, UNLESS OTHERWISE AUTHORIZED IN THE APPLICABLE PERMIT.

EROSION AND SEDIMENT CONTROL

1. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSTALLED PRIOR TO START OF WORKS.
2. SEDIMENT CONTROLS MUST BE INSPECTED DAILY TO ENSURE THAT THEY ARE IN GOOD REPAIR AND FUNCTIONING AS INTENDED.
3. EROSION AND SEDIMENT CONTROLS MUST BE MAINTAINED DURING CONSTRUCTION, AND ANY REQUIRED REPAIRS OR REPLACEMENTS MUST BE COMPLETED WITHIN 24 HOURS AFTER THEY HAVE BEEN IDENTIFIED DURING THE MONITORING.
4. EROSION AND SEDIMENT CONTROLS MUST BE ADJUSTED PERIODICALLY TO REFLECT CHANGING SITE CONDITIONS. THE CONTRACTOR WILL BE RESPONSIBLE FOR THESE ADJUSTMENTS TO ENSURE PROPER FUNCTION.
5. ANY CHANGES TO THE EROSION AND SEDIMENT CONTROL PLAN BEYOND MINOR ADJUSTMENTS MUST BE APPROVED BY THE CONTRACT ADMINISTRATOR.
6. ADDITIONAL EROSION AND SEDIMENT CONTROL SUPPLIES MUST BE KEPT ON SITE IN WORKS TO FACILITATE IMMEDIATE REPAIRS AND/OR UPGRADES AS NEEDED.
7. ALL TEMPORARY SEDIMENT CONTROLS MUST BE REMOVED AFTER THE CONTRACT ADMINISTRATOR DEEMS THE SITE TO BE STABLE.

DELETERIOUS SUBSTANCE CONTROL/SPILL MANAGEMENT

1. PREVENT THE RELEASE OF SEDIMENT, SEDIMENT-LADEN WATER, RAW CONCRETE, CONCRETE LEACHATE OR ANY OTHER DELETERIOUS SUBSTANCES INTO ANY WATERBODY, RAINWE OR STORM SEWER SYSTEM.
2. ENSURE EQUIPMENT AND MACHINERY ARE IN GOOD OPERATING CONDITION (POWER WASHED), FREE OF LEAKS, EXCESS OIL, AND GREASE.
3. NO EQUIPMENT REFUELLING OR SERVICING SHOULD BE UNDERTAKEN WITHIN 30 m OF ANY WATERCOURSE OR SURFACE WATER DRAINAGE.
4. A SPILL CONTAINMENT KIT MUST BE READILY ACCESSIBLE ON SITE IN THE EVENT OF A RELEASE OF A DELETERIOUS SUBSTANCE TO THE ENVIRONMENT. ON-SITE STAFF MUST BE TRAINED IN ITS USE.
5. THE CONTRACT ADMINISTRATOR MUST BE NOTIFIED IMMEDIATELY IN THE EVENT OF A SPILL OF DELETERIOUS SUBSTANCE.

WORK AREA ISOLATION

1. ALL WORK IN ISOLATED WORK AREAS MUST BE COMPLETED IN THE DRY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.
2. THE UNWATERING DISCHARGE LOCATION MUST BE LOCATED AT LEAST 30 m FROM ANY WATERCOURSE OR WETLAND IN AN AREA WITH DENSE VEGETATIVE GROUNDCOVER, AND WHERE THE DISCHARGE CAN RETURN TO THE WATERBODY DOWNSTREAM OF THE WORK AREA OVER THE GROUND COVER.

5.	21/09/02	LD	THIRD DETAILED DESIGN SUBMISSION TO LSRCA
4.	21/05/04	LD	SECOND DETAILED DESIGN SUBMISSION TO LSRCA
3.	20/10/27	LD	FIRST DETAILED DESIGN SUBMISSION TO LSRCA
2.	MARCH 2019	LD	SECOND SUBMISSION LSRCA
1.	AUGUST 2018	LD	FIRST SUBMISSION LSRCA

DESIGNED BY: PV	CHECKED BY: PV
DRAWN BY: LD / BM	DATE: SEPTEMBER 2, 2021

PAULEY VILLARD  
PRACTISING MEMBER  
0957  
ONTARIO  
21/09/02


Geomorphology  
Earth Science  
Observations

36 Main Street North, PO Box 205  
Campbellville, Ontario L0P 1B0


T: 416.920.0926  
www.geomorphix.com

226 BROCK STREET EAST  
WESTLANE DEVELOPMENT GROUP LTD.


BIOSWALE DESIGN  
PLANFORM AND PROFILE




PLANFORM  
1:250




PROFILE  
H = 1:500; V=1:50




CROSS SECTION A-A'




CROSS SECTION B-B'




CROSS SECTION C-C'




CROSS SECTION D-D'



CROSS SECTION E-E'



CROSS SECTION F-F'




CROSS SECTION G-G'

**LEGEND**  
 AREA TO CUT  
 AREA TO FILL

**CROSS SECTIONS**

H=1:100

V=1:10



**KEY MAP**  
N.T.S.

**GENERAL NOTES**

1. ALL CONTRACT DRAWINGS, SPECIFICATIONS AND APPLICABLE PERMITS MUST BE KEPT ON SITE DURING CONSTRUCTION FOR REFERENCE.
2. THE CONTRACTOR MUST NOTIFY THE CONTRACT ADMINISTRATOR AND CONSERVATION AUTHORITY OF THE INTENT TO COMMENCE WORK AT LEAST 48 HOURS IN ADVANCE.
3. THE CONTRACTOR IS RESPONSIBLE FOR ALL UTILITY LOCATES.
4. LAYOUT MUST BE REVIEWED AND APPROVED BY THE CONTRACT ADMINISTRATOR.
5. DESIGNER OR REPRESENTATIVE SHALL BE PRESENT DURING CONSTRUCTION TO PROVIDE GUIDANCE ON INSTALLATION OF THE FEATURES.

**TIMING OF WORKS**

1. WORKS SHALL BE COMPLETED BETWEEN JULY 1ST TO MARCH 31ST.
2. TREE CLEARING SHOULD BE COMPLETED OUTSIDE THE BIRD NESTING SEASON TO COMPLY WITH THE FEDERAL MISYATORY BIRDS CONVENTION ACT. ANY TREES THAT REQUIRE REMOVAL OUTSIDE OF THIS TIMING WINDOW MUST FIRST BE INSPECTED BY A QUALIFIED BIOLOGIST 24-48 HOURS PRIOR TO REMOVAL TO DETERMINE THE PRESENCE OF NESTING BIRDS.
3. THE WEATHER FORECAST SHOULD BE CONTINUALLY MONITORED TO ENSURE THAT WORKS ARE UNDERTAKEN ONLY DURING FAVOURABLE WEATHER CONDITIONS.
4. COMPLETE THE WORKS WITH MINIMAL AVOIDABLE INTERRUPTIONS ONCE THEY COMMENCE.

**SITE AND MATERIAL MANAGEMENT**

1. ALL CONSTRUCTION EQUIPMENT AND MATERIALS (IMPORTED OR EXCAVATED) MUST BE STORED AT LEAST 30 m AWAY FROM ANY WATERBODY IN A STABLE AREA ABOVE THE ACTIVE FLOODPLAIN, OR IN A DESIGNATED STAGING/STORAGE AREA.
2. IN THE EVENT OF AN UNEXPECTED SPILL, ALL UNIDENTIFIED ITEMS THAT HAVE THE POTENTIAL TO CAUSE A SPILL OR AN OBSTRUCTION TO FLOW MUST BE MOVED A STABLE AREA ABOVE ACTIVE FLOODPLAIN.
3. STOCKPILES MUST BE LOCATED OUTSIDE THE ISOLATED WORK AREAS.
4. STABILIZE STOCKPILED SOILS THAT ARE STORED FOR PROLONGED PERIODS WITH THE APPLICATION OF A NURSE CROP AT A RATE OF 60 KG/ha.
5. STABILIZE, TEMPORARILY OR PERMANENTLY, ANY DISTURBED AREAS AS WORK PROGRESSES, OR SOON AS CONDITIONS ALLOW, OR SOILS THAT WILL BE EXPOSED FOR PROLONG PERIODS, TEMPORARILY INSTALL A BIODEGRADABLE EROSION CONTROL BLANKET ON EXPOSED SOILS, OR APPLY A NURSE CROP AT A RATE OF 60 KG/ha.
6. MINIMIZE THE AREA OF DISTURBANCE TO THE EXTENT POSSIBLE.
7. ALL VEGETATION, ADJACENT TO THE WORK AREA, MUST BE PROTECTED AND DELINEATED WITH CONSTRUCTION FENCING OR TREE PROTECTION BARRIERS.
8. ALL GRADES IN THE AREA REGULATED BY THE CONSERVATION AUTHORITY MUST BE MAINTAINED OR MATCHED, UNLESS OTHERWISE AUTHORIZED IN THE APPLICABLE PERMIT.

**EROSION AND SEDIMENT CONTROL**

1. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSTALLED PRIOR TO START OF WORKS.
2. SEDIMENT CONTROLS MUST BE INSPECTED DAILY TO ENSURE THAT THEY ARE IN GOOD REPAIR AND FUNCTIONING AS INTENDED.
3. EROSION AND SEDIMENT CONTROLS MUST BE MAINTAINED DURING CONSTRUCTION, AND ANY REQUIRED REPAIRS OR REPLACEMENTS MUST BE COMPLETED WITHIN 24 HOURS AFTER THEY HAVE BEEN IDENTIFIED DURING THE MONITORING.
4. EROSION AND SEDIMENT CONTROLS MAY REQUIRE PERIODIC ADJUSTMENTS TO REFLECT CHANGING SITE CONDITIONS. THE CONTRACTOR WILL BE RESPONSIBLE FOR THESE ADJUSTMENTS TO ENSURE PROPER FUNCTION.
5. ANY CHANGES TO THE EROSION AND SEDIMENT CONTROL PLAN BEYOND MINOR ADJUSTMENTS MUST BE APPROVED BY THE CONTRACT ADMINISTRATOR.
6. ADDITIONAL EROSION AND SEDIMENT CONTROL SUPPLIES MUST BE KEPT ON SITE IN ORDER TO FACILITATE IMMEDIATE REPAIRS AND/OR UPGRADES AS NEEDED.
7. ALL TEMPORARY SEDIMENT CONTROLS MUST BE REMOVED AFTER THE CONTRACT ADMINISTRATOR DEEMS THE SITE TO BE STABLE.

**DELETERIOUS SUBSTANCE CONTROL/SPILL MANAGEMENT**

1. PREVENT THE RELEASE OF SEDIMENT, SEDIMENT-LADEN WATER, RAW CONCRETE, CONCRETE LEACHATE OR ANY OTHER DELETERIOUS SUBSTANCES INTO ANY WATERBODY, RAINWATER OR STORM SEWER SYSTEM.
2. ENSURE EQUIPMENT AND MACHINERY ARE IN GOOD OPERATING CONDITION (POWER WASHED), FREE OF LEAKS, EXCESS OIL, AND GREASE.
3. NO EQUIPMENT REFUELLING OR SERVICING SHOULD BE UNDERTAKEN WITHIN 30 m OF ANY WATERCOURSE OR SURFACE WATER DRAINAGE.
4. A SPILL CONTAINMENT KIT MUST BE READILY ACCESSIBLE ON SITE IN THE EVENT OF A RELEASE OF A DELETERIOUS SUBSTANCE TO THE ENVIRONMENT. ON-SITE STAFF MUST BE TRAINED IN ITS USE.
5. THE CONTRACT ADMINISTRATOR MUST BE NOTIFIED IMMEDIATELY IN THE EVENT OF A SPILL OF DELETERIOUS SUBSTANCE.

**WORK AREA ISOLATION**

1. ALL WORK IN ISOLATED WORK AREAS MUST BE COMPLETED IN THE DRY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.
2. THE UNWATERING DISCHARGE LOCATION MUST BE LOCATED AT LEAST 30 m FROM ANY WATERCOURSE OR WETLAND IN AN AREA WITH DENSE VEGETATION GROUNDCOVER, AND WHERE THE DISCHARGE CAN RETURN TO THE WATERBODY DOWNSTREAM OF THE WORK AREA OVER THE GROUNDCOVER.

5.	21/09/02	LD	THIRD DETAILED DESIGN SUBMISSION TO LSRCA
4.	21/05/04	LD	SECOND DETAILED DESIGN SUBMISSION TO LSRCA
3.	20/10/27	LD	FIRST DETAILED DESIGN SUBMISSION TO LSRCA
2.	MARCH 2019	LD	SECOND SUBMISSION LSRCA
1.	AUGUST 2018	LD	FIRST SUBMISSION LSRCA
	DATE	BY	REVISIONS

DESIGNED BY: PV CHECKED BY: PV

DRAWN BY: LD / BM DATE: SEPTEMBER 2, 2021


PAUL V. VILLARD  
PRACTISING MEMBER  
0957  
21/09/02

**GEO MORPHIX**  
Geomorphology  
Earth Science  
Observations


36 Main Street North, PO Box 205  
Campbellville, Ontario L0P 1B0  
T: 416.920.0926  
www.geomorphix.com

**226 BROCK STREET EAST  
WESTLANE DEVELOPMENT GROUP LTD.**


**BIOSWALE DESIGN  
CROSS SECTIONS**




KEY MAP  
N.T.S.



BIOSWALE FEATURES  
N.T.S.



ONLINE WET MEADOW  
N.T.S.



STONE CORE WET MEADOW  
N.T.S.

**GENERAL NOTES**

1. ALL CONTRACT DRAWINGS, SPECIFICATIONS AND APPLICABLE PERMITS MUST BE KEPT ON SITE DURING CONSTRUCTION FOR REFERENCE.
2. TREE CLEARING SHOULD BE COMPLETED OUTSIDE THE BIRD NESTING SEASON TO COMPLY WITH THE FEDERAL MIGRATORY BIRDS CONVENTION ACT. ANY TREES THAT REQUIRE REMOVAL OUTSIDE OF THIS TIMING WINDOW MUST FIRST BE INSPECTED BY A QUALIFIED BIOLOGIST 24-48 HOURS PRIOR TO REMOVAL TO DETERMINE THE PRESENCE OF NESTING BIRDS.
3. THE CONTRACTOR IS RESPONSIBLE FOR ALL UTILITY LOCATIONS.
4. LAYOUT MUST BE REVIEWED AND APPROVED BY THE CONTRACT ADMINISTRATOR.
5. DESIGNER OR REPRESENTATIVE SHALL BE PRESENT DURING CONSTRUCTION TO PROVIDE GUIDANCE ON INSTALLATION OF THE FEATURES.

**TIMING OF WORKS**

1. WORKS SHALL BE COMPLETED BETWEEN JULY 1ST TO MARCH 31ST.
2. TREE CLEARING SHOULD BE COMPLETED OUTSIDE THE BIRD NESTING SEASON TO COMPLY WITH THE FEDERAL MIGRATORY BIRDS CONVENTION ACT. ANY TREES THAT REQUIRE REMOVAL OUTSIDE OF THIS TIMING WINDOW MUST FIRST BE INSPECTED BY A QUALIFIED BIOLOGIST 24-48 HOURS PRIOR TO REMOVAL TO DETERMINE THE PRESENCE OF NESTING BIRDS.
3. THE WEATHER FORECAST SHOULD BE CONTINUALLY MONITORED TO ENSURE THAT WORKS ARE UNDERTAKEN ONLY DURING FAVOURABLE WEATHER CONDITIONS.
4. COMPLETE THE WORKS WITH MINIMAL AVOIDABLE INTERRUPTIONS ONCE THEY COMMENCE.

**SITE AND MATERIAL MANAGEMENT**

1. ALL CONSTRUCTION EQUIPMENT AND MATERIALS (IMPORTED OR EXCAVATED) MUST BE STORED AT LEAST 30 m AWAY FROM ANY WATERBODY IN A STABLE AREA ABOVE THE ACTIVE FLOODPLAIN, OR IN A DESIGNATED STAGING/STORAGE AREA.
2. IN THE EVENT OF AN UNEXPECTED STORM, ALL UNFIXED ITEMS THAT HAVE THE POTENTIAL TO CAUSE A SPILL OR AN OBSTRUCTION TO FLOW MUST BE MOVED TO A STABLE AREA ABOVE ACTIVE FLOODPLAIN.
3. STOCKPILES MUST BE LOCATED OUTSIDE THE ISOLATED WORK AREAS.
4. STABILIZE STOCKPILED SOILS THAT ARE STORED FOR PROLONGED PERIODS WITH THE APPLICATION OF A NURSE CROP AT A RATE OF 60 KG/HA.
5. STABILIZE, TEMPORARILY OR PERMANENTLY, ANY DISTURBED AREAS AS WORK PROGRESSES, OR SOON AS CONDITIONS ALLOW, ON SOILS THAT WILL BE EXPOSED FOR PROLONG PERIODS. TEMPORARILY INSTALL A BIODEGRADABLE EROSION CONTROL BLANKET ON EXPOSED SOILS, OR APPLY A NURSE CROP AT A RATE OF 60 KG/HA.
6. MINIMIZE THE AREA OF DISTURBANCE TO THE EXTENT POSSIBLE.
7. ALL VEGETATION ADJACENT TO THE WORK AREA, MUST BE PROTECTED AND DELINEATED WITH CONSTRUCTION FENCING OR TREE PROTECTION BARRIERS.
8. ALL GRADES IN THE AREA REGULATED BY THE CONSERVATION AUTHORITY MUST BE MAINTAINED OR MATCHED, UNLESS OTHERWISE AUTHORIZED IN THE APPLICABLE PERMIT.

**EROSION AND SEDIMENT CONTROL**

1. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSTALLED PRIOR TO START OF WORKS.
2. SEDIMENT CONTROLS MUST BE INSPECTED DAILY TO ENSURE THAT THEY ARE IN GOOD REPAIR AND FUNCTIONING AS INTENDED.
3. EROSION AND SEDIMENT CONTROLS MUST BE MAINTAINED DURING CONSTRUCTION, AND ANY REQUIRED REPAIRS OR REPLACEMENTS MUST BE COMPLETED WITHIN 24 HOURS AFTER THEY HAVE BEEN IDENTIFIED DURING THE MONITORING.
4. EROSION AND SEDIMENT CONTROLS MAY REQUIRE PERIODIC ADJUSTMENTS TO REFLECT CHANGING SITE CONDITIONS. THE CONTRACTOR WILL BE RESPONSIBLE FOR THESE ADJUSTMENTS TO ENSURE PROPER FUNCTION.
5. ANY CHANGES TO THE EROSION AND SEDIMENT CONTROL PLAN BEYOND MINOR ADJUSTMENTS MUST BE APPROVED BY THE CONTRACT ADMINISTRATOR.
6. ADDITIONAL EROSION AND SEDIMENT CONTROL SUPPLIES MUST BE KEPT ON SITE IN ORDER TO FACILITATE IMMEDIATE REPAIRS AND/OR UPGRADES AS NEEDED.
7. ALL TEMPORARY SEDIMENT CONTROLS MUST BE REMOVED AFTER THE CONTRACT ADMINISTRATOR DEEMS THE SITE TO BE STABLE.

**DELETERIOUS SUBSTANCE CONTROL/SPILL MANAGEMENT**

1. PREVENT THE RELEASE OF SEDIMENT, SEDIMENT-LADEN WATER, RAW CONCRETE, CONCRETE LEACHATE OR ANY OTHER DELETERIOUS SUBSTANCES INTO ANY WATERBODY, NAIVE OR STORM SEWER SYSTEM.
2. ENSURE EQUIPMENT AND MACHINERY ARE IN GOOD OPERATING CONDITION (POWER WASHED), FREE OF LEAKS, EXCESS OIL AND GREASE.
3. NO EQUIPMENT FUELLING OR SERVICING SHOULD BE UNDERTAKEN WITHIN 30 m OF ANY WATERCOURSE OR SURFACE WATER DRAINAGE.
4. A SPILL CONTAINMENT KIT MUST BE READILY ACCESSIBLE ON SITE IN THE EVENT OF A RELEASE OF A DELETERIOUS SUBSTANCE TO THE ENVIRONMENT. ONSITE STAFF MUST BE TRAINED IN ITS USE.
5. THE CONTRACT ADMINISTRATOR MUST BE NOTIFIED IMMEDIATELY IN THE EVENT OF A SPILL OF DELETERIOUS SUBSTANCE.

**WORK AREA ISOLATION**

1. ALL WORK IN ISOLATED WORK AREAS MUST BE COMPLETED IN THE DRY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.
2. THE UNWATERING DISCHARGE LOCATION MUST BE LOCATED AT LEAST 30 m FROM ANY WATERCOURSE OR WETLAND IN AN AREA WITH DENSE VEGETATIVE GROUNDCOVER AND WHERE THE DISCHARGE CAN RETURN TO THE WATERBODY DOWNSTREAM OF THE WORK AREA OVER THE GROUND COVER.

5.	21/09/02	LD	THIRD DETAILED DESIGN SUBMISSION TO LSRCA
4.	21/05/04	LD	SECOND DETAILED DESIGN SUBMISSION TO LSRCA
3.	20/10/27	LD	FIRST DETAILED DESIGN SUBMISSION TO LSRCA
2.	MARCH 2019	LD	SECOND SUBMISSION LSRCA
1.	AUGUST 2018	LD	FIRST SUBMISSION LSRCA


DATE	BY	REVISIONS
DESIGNED BY: PV	CHECKED BY: PV	
DRAWN BY: LD / BM	DATE: SEPTEMBER 2, 2021	

**GEO MORPHIX**  
Geomorphology  
Earth Science  
Observations


36 Main Street North, PO Box 205  
Campbellville, Ontario L0P 1B0  
T: 416.920.0926  
www.geomorphix.com

226 BROCK STREET EAST  
WESTLANE DEVELOPMENT GROUP LTD.

BIOSWALE DESIGN  
RESTORATION DETAILS




**PLANFORM**  
1:250



- NOTES**
1. PUMPING RATE MUST MATCH WORKING FLOW CONDITIONS.
  2. IMPERMEABLE BARRIER (PLASTIC SHEET) TO COVER THE BAGS TO LIMIT SEEPAGE INTO WORK AREA.
  3. BAGS TO BE FILLED WITH PEA-GRAVEL.
  4. PEA-GRAVEL TO BE DISTRIBUTED IN CHANNEL AFTER WORKS ARE COMPLETE AT THE DISCRETION OF CONSTRUCTION CONTRACT ADMIN.
  5. BACKUP PUMP AND HOSE SHALL BE KEPT ONSITE TO ADDRESS FAILURES AND HIGH FLOW CONDITIONS.

**PEA-GRAVEL BAG COFFERDAM AND BYPASS PUMPING**  
N.T.S.



**SILT FENCE**  
N.T.S.

**SUGGESTED SEQUENCE OF CONSTRUCTION**

1. DESIGNER OR REPRESENTATIVE SHALL BE PRESENT DURING CONSTRUCTION TO PROVIDE GUIDANCE ON INSTALLATION OF THE FEATURES GIVEN THE WORKS DIFFER FROM ENGINEERING PROJECTS.
2. CONSTRUCTION CONTRACT ADMINISTRATOR TO REVIEW SITE CONDITIONS PRIOR TO COMMENCEMENT OF WORK.
3. MONITORING WEATHER TO ENSURE IN-WATER WORKS IS COMPLETED UNDER LOW-FLOW CONDITIONS.
4. INSTALL SILT FENCE TO ISOLATE THE WORK AREA.
5. CONSTRUCT AS MUCH AS ENHANCED BIOSWALE AS POSSIBLE WITHOUT INTERFERENCE TO THE EXISTING FEATURE, INCLUDING DOWNSTREAM TIE-IN.
6. STABILIZE ANY DISTURBED AREA WITH SEED AND 100% BIODEGRADABLE EROSION CONTROL BLANKET (BIONET C125BN OR APPROVED EQUIVALENT).
7. INSTALL COFFERDAMS AND PUMP FLOWS AROUND WORK ARE TO COMPLETE TIE-IN WITH EXISTING FEATURE AT THE UPSTREAM EXTENT.
8. INTRODUCE FLOWS TO THE FEATURE ONCE THE SITE HAS BEEN DEEMED STABLE BY THE DESIGNER OR REPRESENTATIVE.
9. REMOVE EROSION AND SEDIMENT CONTROL MEASURES ONCE AREA IS DEEMED STABLE BY THE DESIGNER OR REPRESENTATIVE.

**GENERAL NOTES**

1. ALL CONTRACT DRAWINGS, SPECIFICATIONS AND APPLICABLE PERMITS MUST BE KEPT ON SITE DURING CONSTRUCTION FOR REFERENCE.
2. TREE CLEARING SHOULD BE COMPLETED OUTSIDE THE BIRD NESTING SEASON TO COMPLY WITH THE FEDERAL MIGRATORY BIRDS CONVENTION ACT. ANY TREES THAT REQUIRE REMOVAL OUTSIDE OF THIS TIMING WINDOW MUST FIRST BE INSPECTED BY A QUALIFIED BIOLOGIST 24-48 HOURS PRIOR TO REMOVAL TO DETERMINE THE PRESENCE OF NESTING BIRDS.
3. THE WEATHER FORECAST SHOULD BE CONTINUALLY MONITORED TO ENSURE THAT WORKS ARE UNDERTAKEN ONLY DURING FAVOURABLE WEATHER CONDITIONS.
4. COMPLETE THE WORKS WITH MINIMAL UNNECESSARY INTERRUPTIONS ONCE THEY COMMENCE.

**TIMING OF WORKS**

1. WORKS SHALL BE COMPLETED BETWEEN JULY 1ST TO MARCH 31ST.
2. TREE CLEARING SHOULD BE COMPLETED OUTSIDE THE BIRD NESTING SEASON TO COMPLY WITH THE FEDERAL MIGRATORY BIRDS CONVENTION ACT. ANY TREES THAT REQUIRE REMOVAL OUTSIDE OF THIS TIMING WINDOW MUST FIRST BE INSPECTED BY A QUALIFIED BIOLOGIST 24-48 HOURS PRIOR TO REMOVAL TO DETERMINE THE PRESENCE OF NESTING BIRDS.
3. THE WEATHER FORECAST SHOULD BE CONTINUALLY MONITORED TO ENSURE THAT WORKS ARE UNDERTAKEN ONLY DURING FAVOURABLE WEATHER CONDITIONS.
4. COMPLETE THE WORKS WITH MINIMAL UNNECESSARY INTERRUPTIONS ONCE THEY COMMENCE.

**SITE AND MATERIAL MANAGEMENT**

1. ALL CONSTRUCTION EQUIPMENT AND MATERIALS (IMPORTED OR EXCAVATED) MUST BE STORED AT LEAST 30 m AWAY FROM ANY WATERBODY IN A STABLE AREA ABOVE THE ACTIVE FLOORPLAN, OR IN A DESIGNATED STAGING/STORAGE AREA.
2. IN THE EVENT OF AN UNEXPECTED STORM, ALL UNFIXED ITEMS THAT HAVE THE POTENTIAL TO CAUSE A SPILL OR AN OBSTRUCTION TO FLOW MUST BE MOVED A STABLE AREA ABOVE ACTIVE FLOORPLAN.
3. STOCKPILES MUST BE LOCATED OUTSIDE THE WORK AREAS.
4. STABILIZE STOCKPILED SOILS THAT ARE STORED FOR PROLONGED PERIODS WITH THE APPLICATION OF A NURSE CROP AT A RATE OF 60 kg/ha.
5. STABILIZE, TEMPORARILY OR PERMANENTLY, ANY DISTURBED AREAS AS WORK PROGRESSES, OR SOON AS CONDITIONS ALLOW, ON SOILS THAT WILL BE EXPOSED FOR PROLONGED PERIODS. TEMPORARILY INSTALL A BIODEGRADABLE EROSION CONTROL BLANKET ON EXPOSED SOILS, OR APPLY A NURSE CROP AT A RATE OF 60 kg/ha.
6. MINIMIZE THE AREA OF DISTURBANCE TO THE EXTENT POSSIBLE.
7. ALL VEGETATION, ADJACENT TO THE WORK AREA, MUST BE PROTECTED AND DELINEATED WITH CONSTRUCTION FENCING OR TREE PROTECTION BARRIERS.
8. ALL GRADES IN THE AREA REGULATED BY THE CONSERVATION AUTHORITY MUST BE MAINTAINED OR MATCHED, UNLESS OTHERWISE AUTHORIZED IN THE APPLICABLE PERMIT.

**EROSION AND SEDIMENT CONTROL**

1. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSTALLED PRIOR TO START OF WORKS.
2. SEDIMENT CONTROLS MUST BE INSPECTED DAILY TO ENSURE THAT THEY ARE IN GOOD REPAIR AND FUNCTIONING AS INTENDED.
3. EROSION AND SEDIMENT CONTROLS MUST BE MAINTAINED DURING CONSTRUCTION, AND ANY REQUIRED REPAIRS OR REPLACEMENTS MUST BE COMPLETED WITHIN 24 HOURS AFTER THEY HAVE BEEN IDENTIFIED DURING THE MONITORING.
4. EROSION AND SEDIMENT CONTROLS MAY REQUIRE PERIODIC ADJUSTMENTS TO REFLECT CHANGING SITE CONDITIONS. THE CONTRACTOR WILL BE RESPONSIBLE FOR THESE ADJUSTMENTS TO ENSURE PROPER FUNCTION.
5. ANY CHANGES TO THE EROSION AND SEDIMENT CONTROL PLAN BEYOND MINOR ADJUSTMENTS MUST BE APPROVED BY THE CONTRACT ADMINISTRATOR.
6. ADDITIONAL EROSION AND SEDIMENT CONTROL SUPPLIES MUST BE KEPT ON SITE IN ORDER TO FACILITATE IMMEDIATE REPAIRS AND/OR UPGRADES AS NEEDED.
7. ALL TEMPORARY SEDIMENT CONTROLS MUST BE REMOVED AFTER THE CONTRACT ADMINISTRATOR DEEMS THE SITE TO BE STABLE.

**DELETERIOUS SUBSTANCE CONTROL/SPILL MANAGEMENT**

1. PREVENT THE RELEASE OF SEDIMENT, SEDIMENT-LADEN WATER, RAW CONCRETE, CONCRETE LEACHATE OR ANY OTHER DELETERIOUS SUBSTANCES INTO ANY WATERBODY, SURFACE OR STORM SEWER SYSTEM.
2. ENSURE EQUIPMENT AND MACHINERY ARE IN GOOD OPERATING CONDITION (POWER WASHED), FREE OF LEAKS, EXCESS OIL AND GREASE.
3. NO EQUIPMENT REFUELLING OR SERVICING SHOULD BE UNDERTAKEN WITHIN 30 m OF ANY WATERCOURSE OR SURFACE WATER CHANNEL.
4. A SPILL CONTAINMENT KIT MUST BE READILY ACCESSIBLE ON SITE IN THE EVENT OF A RELEASE OF A DELETERIOUS SUBSTANCE TO THE ENVIRONMENT. ONSITE STAFF MUST BE TRAINED IN ITS USE.
5. THE CONTRACT ADMINISTRATOR MUST BE NOTIFIED IMMEDIATELY IN THE EVENT OF A SPILL OF DELETERIOUS SUBSTANCE.

**WORK AREA ISOLATION**

1. ALL WORK IN ISOLATED WORK AREAS MUST BE COMPLETED IN THE DRY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.
2. THE UNWATERING DISCHARGE LOCATION MUST BE LOCATED AT LEAST 30 m FROM ANY WATERCOURSE OR WETLAND IN AN AREA WITH DENSE VEGETATIVE GROUNDCOVER, AND WHERE THE DISCHARGE CAN RETURN TO THE WATERBODY DOWNSTREAM OF THE WORK AREA OVER THE GROUND COVER.

5.	21/09/02	LD	THIRD DETAILED DESIGN SUBMISSION TO LSRCA
4.	21/05/04	LD	SECOND DETAILED DESIGN SUBMISSION TO LSRCA
3.	20/10/27	LD	FIRST DETAILED DESIGN SUBMISSION TO LSRCA
2.	MARCH 2019	LD	SECOND SUBMISSION LSRCA
1.	AUGUST 2018	LD	FIRST SUBMISSION LSRCA

DATE	BY	REVISIONS
DESIGNED BY: PV	CHECKED BY: PV	
DRAWN BY: LD / BM	DATE: SEPTEMBER 2, 2021	


PAUL VILLARD  
PRACTISING MEMBER  
0957  
ONTARIO

**GEO MORPHIX**  
Geomorphology  
Earth Science  
Observations


36 Main Street North, PO Box 205  
Campbellville, Ontario L0P 1B0  
T: 416.920.0926  
www.geomorphix.com

**226 BROCK STREET EAST**  
**WESTLANE DEVELOPMENT GROUP LTD.**

**BIOSWALE DESIGN**  
**PHASING AND EROSION AND SEDIMENT**  
**CONTROL PLAN**




**PLANFORM**  
1:500



**SPECIES AND QUANTITIES**

I.D.	COMMON NAME	SPECIES	QTY	CONDITION / SIZE
AR	RED MAPLE	<i>Acer rubrum</i>	3	100 cm HT. WHIP
CO	COMMON HACKBERRY	<i>Celtis occidentalis</i>	3	60 mm CAL. B&B
JC	BUTTERNUT	<i>Juglans cinerea</i>	5	60 mm CAL. B&B
QM	BUROAK	<i>Quercus macrocarpa</i>	3	100 cm HT. WHIP
TA	BASSWOOD	<i>Tilia americana</i>	3	100 cm HT. WHIP

**NOTE:**  
ANY TREES FOUND TO BE DEAD, DEFECTIVE OR NOT IN A HEALTHY GROWING CONDITION WITHIN 2 YEARS OF PLANTING SHALL BE REPLACED AND RE-GUARANTEED FOR AN ADDITIONAL YEAR FROM THE DATE OF REPLACEMENT.



**RIPARIAN SEED MIX**

COMMON NAME	SPECIES	% OF MIX
BLUE VERVAIN	<i>Verbena hastata</i>	3
BLUNT BROOM SEDGE	<i>Carex scoparia</i>	5
FOX SEDGE	<i>Carex vulpinoidea</i>	30
GREEN BULRUSH	<i>Scirpus atrovirens</i>	10
PURPLE STEMMED ASTER	<i>Aster puniceus</i>	5
SPOTTED JOE PYE WEED	<i>Eupatorium maculatum</i>	2
SWAMP MILKWEED	<i>Asclepias incarnata</i>	10
SWEET FLAG	<i>Acorus americana</i>	5
VIRGINIA WILD RYE	<i>Elymus virginicus</i>	30

**NOTES**


- APPLY SEED MIX AT A RATE OF 30 kg PER HECTARE.
- SEEDING SHALL OVERLAP ADJACENT GROUND COVER BY 300 mm.
- APPLY OAT OR RYE NURSE CROP AT A RATE OF 25 kg PER HECTARE.
- WATER SOIL AFTER SEED APPLICATION.

**WETLAND MEADOW SEED MIX**

COMMON NAME	SPECIES	% OF MIX
BEBB'S SEDGE	<i>Carex bebbii</i>	1
BLUE LOBELIA	<i>Lobelia siphilitica</i>	1
BLUE VERVAIN	<i>Verbena hastata</i>	10
BONESET	<i>Eupatorium perfoliatum</i>	1
DARK GREEN BULRUSH	<i>Scirpus atrovirens</i>	1
FOWL BLUEGRASS	<i>Poa palustris</i>	20
FOX SEDGE	<i>Carex vulpinoidea</i>	27
NEW ENGLAND ASTER	<i>Aster novae-angliae</i>	2
PURPLE STEMMED ASTER	<i>Aster puniceus</i>	1
SOFT RUSH	<i>Juncus effusus</i>	2
SPOTTED JOE PYE WEED	<i>Eupatorium maculatum</i>	1
SQUARE STEMMED MONKEY FLOWER	<i>Mimulus ringens</i>	2
SWAMP MILKWEED	<i>Asclepias incarnata</i>	1
TALL MANNAGRASS	<i>Glyceria grandis</i>	2
VIRGINIA WILD RYE	<i>Elymus virginicus</i>	27
WOOLGRASS	<i>Scirpus cyperinus</i>	1

**NOTES**

- APPLY SEED MIX AT A RATE OF 25 kg PER HECTARE WITHIN WETLANDS (SEE WETLAND DETAIL).
- SEEDING SHALL OVERLAP ADJACENT GROUND COVER BY 300 mm.
- APPLY COMMON OAT (*Avena sativa*) NURSE CROP AT A RATE OF 25 kg PER HECTARE.



- GENERAL NOTES**
- ALL CONTRACT DRAWINGS, SPECIFICATIONS AND APPLICABLE PERMITS MUST BE KEPT ON SITE DURING CONSTRUCTION FOR REFERENCE.
  - THE CONTRACTOR MUST NOTIFY THE CONTRACT ADMINISTRATOR AND CONSERVATION AUTHORITY OF THE INTENT TO COMMENCE WORK AT LEAST 48 HOURS IN ADVANCE.
  - THE CONTRACTOR IS RESPONSIBLE FOR ALL UTILITY LOCATES.
  - LANDFILL MUST BE REVIEWED AND APPROVED BY THE CONTRACT ADMINISTRATOR.
  - DESIGNER OR REPRESENTATIVE SHALL BE PRESENT DURING CONSTRUCTION TO PROVIDE GUIDANCE ON INSTALLATION OF THE FEATURES.

- TIMING OF WORKS**
- WORKS SHALL BE COMPLETED BETWEEN JULY 1ST TO MARCH 31ST.
  - TREE CLEARING SHOULD BE COMPLETED OUTSIDE THE BIRD NESTING SEASON TO COMPLY WITH THE FEDERAL MIGRATORY BIRD CONVENTION ACT. ANY TREES THAT REQUIRE REMOVAL OUTSIDE OF THIS TIMING WINDOW MUST FIRST BE INSPECTED BY A QUALIFIED BIOLOGIST 24-48 HOURS PRIOR TO REMOVAL TO DETERMINE THE PRESENCE OF NESTING BIRDS.
  - THE WEATHER FORECAST SHOULD BE CONTINUALLY MONITORED TO ENSURE THAT WORKS ARE UNDERTAKEN ONLY DURING FAVOURABLE WEATHER CONDITIONS.
  - COMPLETE THE WORKS WITH MINIMAL AVOIDABLE INTERRUPTIONS ONCE THEY COMMENCE.

- SITE AND MATERIAL MANAGEMENT**
- ALL CONSTRUCTION EQUIPMENT AND MATERIALS (IMPORTED OR EXCAVATED) MUST BE STORED AT LEAST 30 m AWAY FROM ANY WATERBODY IN A STABLE AREA ABOVE THE ACTIVE FLOODPLAIN, OR IN A DESIGNATED STAGING/STORAGE AREA.
  - IN THE EVENT OF AN UNEXPECTED STORM, ALL UNFIXED ITEMS THAT HAVE THE POTENTIAL TO CAUSE A SPILL OR AN OBSTRUCTION TO FLOW MUST BE MOVED A STABLE AREA ABOVE ACTIVE FLOODPLAIN.
  - STOCKPILES MUST BE LOCATED OUTSIDE THE ISOLATED WORK AREAS.
  - STABILIZE STOCKPILED SOILS THAT ARE STORED FOR PROLONGED PERIODS WITH THE APPLICATION OF A NURSE CROP AT A RATE OF 60 kg/ha.
  - STABILIZE, TEMPORARILY OR PERMANENTLY, ANY DISTURBED AREAS AS WORK PROGRESSES, OR SOON AS CONDITIONS ALLOW. ON SOILS THAT WILL BE EXPOSED FOR PROLONG PERIODS, TEMPORARILY INSTALL A BIODEGRADABLE EROSION CONTROL BLANKET ON EXPOSED SOILS, OR APPLY A NURSE CROP AT A RATE OF 60 kg/ha.
  - MINIMIZE THE AREA OF DISTURBANCE TO THE EXTENT POSSIBLE.
  - ALL VEGETATION ADJACENT TO THE WORK AREA, MUST BE PROTECTED AND DELINEATED WITH CONSTRUCTION FENCING OR TREE PROTECTION BARRIERS.
  - ALL GRASSES IN THE AREA REGULATED BY THE CONSERVATION AUTHORITY MUST BE MAINTAINED OR MATCHED, UNLESS OTHERWISE AUTHORIZED IN THE APPLICABLE PERMIT.

- EROSION AND SEDIMENT CONTROL**
- ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSTALLED PRIOR TO START OF WORKS.
  - SEDIMENT CONTROLS MUST BE INSPECTED DAILY TO ENSURE THAT THEY ARE IN GOOD REPAIR AND FUNCTIONING AS INTENDED.
  - EROSION AND SEDIMENT CONTROLS MUST BE MAINTAINED DURING CONSTRUCTION, AND ANY REQUIRED REPAIRS OR REPLACEMENTS MUST BE COMPLETED WITHIN 24 HOURS AFTER THEY HAVE BEEN IDENTIFIED DURING THE MONITORING.
  - EROSION AND SEDIMENT CONTROLS MAY REQUIRE PERIODIC ADJUSTMENTS TO REFLECT CHANGING SITE CONDITIONS. THE CONTRACTOR WILL BE RESPONSIBLE FOR THESE ADJUSTMENTS TO ENSURE PROPER FUNCTION.
  - ANY CHANGES TO THE EROSION AND SEDIMENT CONTROL PLAN BEYOND MINOR ADJUSTMENTS MUST BE APPROVED BY THE CONTRACT ADMINISTRATOR.
  - ADDITIONAL EROSION AND SEDIMENT CONTROL SUPPLIES MUST BE KEPT ON SITE IN ORDER TO FACILITATE IMMEDIATE REPAIRS AND/OR UPGRADES AS NEEDED.
  - ALL TEMPORARY SEDIMENT CONTROLS MUST BE REMOVED AFTER THE CONTRACT ADMINISTRATOR DEEMS THE SITE TO BE STABLE.

- DELETERIOUS SUBSTANCE CONTROL/SPILL MANAGEMENT**
- PREVENT THE RELEASE OF SEDIMENT, SEDIMENT-LADEN WATER, RAW CONCRETE, CONCRETE LEACHATE OR ANY OTHER DELETERIOUS SUBSTANCES INTO ANY WATERBODY, RAVIDE OR STORM SEWER SYSTEM.
  - ENSURE EQUIPMENT AND MACHINERY ARE IN GOOD OPERATING CONDITION (POWER WASHED), FREE OF LEAKS, EXCESS OIL, AND GREASE.
  - NO EQUIPMENT REFUELLING OR SERVICING SHOULD BE UNDERTAKEN WITHIN 30 m OF ANY WATERCOURSE OR SURFACE WATER DRAINAGE.
  - A SPILL CONTAINMENT KIT MUST BE READILY ACCESSIBLE ON SITE IN THE EVENT OF A RELEASE OF A DELETERIOUS SUBSTANCE TO THE ENVIRONMENT. ON-SITE STAFF MUST BE TRAINED IN ITS USE.
  - THE CONTRACT ADMINISTRATOR MUST BE NOTIFIED IMMEDIATELY IN THE EVENT OF A SPILL OF DELETERIOUS SUBSTANCE.

- WORK AREA ISOLATION**
- ALL WORK IN ISOLATED WORK AREAS MUST BE COMPLETED IN THE DRY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.
  - THE UNWATERING DISCHARGE LOCATION MUST BE LOCATED AT LEAST 30 m FROM ANY WATERCOURSE OR WETLAND IN AN AREA WITH DENSE VEGETATIVE GROUND COVER, AND WHERE THE DISCHARGE CAN RETURN TO THE WATERBODY DOWNSTREAM OF THE WORK AREA OVER THE GROUND COVER.

NO.	DATE	BY	REVISIONS
5.	21/09/02	LD	THIRD DETAILED DESIGN SUBMISSION TO LSRCA
4.	21/05/04	LD	SECOND DETAILED DESIGN SUBMISSION TO LSRCA
3.	20/10/27	LD	FIRST DETAILED DESIGN SUBMISSION TO LSRCA
2.	MARCH 2019	LD	SECOND SUBMISSION LSRCA
1.	AUGUST 2018	LD	FIRST SUBMISSION LSRCA

DESIGNED BY: PV      CHECKED BY: PV  
DRAWN BY: LD / BM      DATE: SEPTEMBER 2, 2021

PROFESSIONAL GEOSCIENTIST  
PAUL V. VILLARD  
PRACTISING MEMBER  
0957  
ONTARIO  
21/09/02

**GEO MORPHIX**  
Geomorphology  
Earth Sciences  
Observations

36 Main Street North, PO Box 205  
Campbellville, Ontario L0P 1B0  
T: 416.920.0926  
www.geomorphix.com


**226 BROCK STREET EAST**  
**WESTLANE DEVELOPMENT GROUP LTD.**

**BIOSWALE DESIGN**  
**RESTORATION PLAN AND DETAILS**

PROJECT No.: 20094	DRAWING No.: RES-1
SCALE: AS NOTED	SHEET 6 OF 6

**APPENDIX A5**  
**Coral Creek Pond Drawing**


STORM EVENT	PRE-DEVELOPMENT FLOW (m <sup>3</sup> /s)	ULTIMATE			INTERIM		
		CONTROLLED OUTFLOW (m <sup>3</sup> /s)	VOLUME (m <sup>3</sup> )	ELEVATION (m)	CONTROLLED OUTFLOW (m <sup>3</sup> /s)	VOLUME (m <sup>3</sup> )	ELEVATION (m)
2	0.21	0.07	2,670	271.65+/-	0.03	1,678	271.40+/-
5	0.35	0.16	3,757	271.85+/-	0.05	2,746	271.65+/-
10	0.46	0.29	4,268	271.95+/-	0.08	3,539	271.80+/-
25	0.62	0.50	4,946	272.05+/-	0.19	3,986	271.90+/-
50	0.74	0.67	5,416	272.10+/-	0.28	4,356	271.95+/-
100	0.88	0.86	5,912	272.20+/-	0.39	4,756	272.00+/-



### ESTATES OF AVONLEA

- GENERAL NOTES:**
- DURING CONSTRUCTION, SEDIMENT FOREBAY AREA TO BE FREQUENTLY CHECKED FOR BUILD-UP OF SEDIMENT. FOREBAY TO BE CLEANED OUT ONCE 0.5m OF SEDIMENT HAS ACCUMULATED.
  - IMPERMEABLE CLAY LINER (OR APPROVED EQUIVALENT) TO BE PROVIDED FROM BOTTOM OF FACILITY UP TO 0.5m ABOVE THE 100 YEAR HIGH WATER LEVEL. LINER TO BE 0.5m THICK AND CONSTRUCTED FROM ON SITE MATERIAL, IF AVAILABLE, AND IN ACCORDANCE WITH ADVICE FROM THE SITE'S GEOTECHNICAL REPRESENTATIVE FOR THE PROJECT.
  - ALL POND AREAS, WITH THE EXCEPTION OF THE PERMANENT WET PORTIONS OF THE POND DEEPER THAN 0.30m, SHALL BE HYDROSEED ON 300mm OF NATIVE TOPSOIL.
  - BOTTOM OF WETLAND AREA TO HAVE APPROXIMATELY 300mm NATIVE MATERIAL.
  - HYDROSEED TO BE LOW MAINTENANCE GROUND COVER APPROVED BY THE LANDSCAPE ARCHITECT.
  - ANTI-SEEPAGE COLLARS TO BE USED ON PIPES AT THE CONTROL STRUCTURE.

- NOTE: BERM CONSTRUCTION**
- BERMS TO BE COMPACTED TO 95% SPD AT A MAXIMUM OF 150mm LIFTS.
  - FOUNDATION SUBGRADE OF BERMS TO BE STRIPPED OF TOPSOIL AND ORGANIC MATERIAL PRIOR TO CONSTRUCTION.
  - BERMS TO BE CONSTRUCTED OF CLEAN EARTH FILL FREE OF ANY ORGANIC MATERIAL, COBBLES AND BOULDERS.
  - ALL CONSTRUCTION AND MATERIALS TO BE INSPECTED AND APPROVED BY A GEOTECHNICAL ENGINEER.



No.	Revision	Date	By	Approved
4				
3				
2				
1				

ACCEPTED TO BE IN ACCORDANCE WITH THE TOWNSHIP OF UXBRIDGE STANDARDS. THIS ACCEPTANCE IS NOT TO BE CONSTRUED AS VERIFICATION OF ENGINEERING CONTENT.

TOWNSHIP ENGINEER: \_\_\_\_\_  
 DATE: \_\_\_\_\_

APPROVED  
 Department of Works  
 Region of Durham  
 Date: \_\_\_\_\_


CORPORATION OF THE TOWNSHIP OF UXBRIDGE

### CORAL CREEK HOMES STORMWATER MANAGEMENT DETENTION FACILITY

**VINCENT & ASSOCIATES**  
 Consulting Engineers & Project Managers  
 3300 Highway No.7 West, Suite 340, Vaughan, L4K 4M3 (905) 669-3655

Scale: 1:300  
 Drawn By: ACAD  
 Designed By: LK  
 Checked By: VJD  
 Date: JULY 2000

Project No: 97077  
 Drawing No: SW-1





APPENDIX B  
STORMWATER MANAGEMENT  
CALCULATIONS

APPENDIX B.1 BACKGROUND INFORMATION

APPENDIX B.2 PRE-DEVELOPMENT CALCULATIONS

APPENDIX B.3 POST DEVELOPMENT CALCULATIONS (QUANTITY)

APPENDIX B.4 QUALITY CONTROL

APPENDIX B.5 WATER BALANCE/INFILTRATION TRENCH





APPENDIX B.6 PHOSPHORUS CALCULATIONS

APPENDIX B.7 OVERLAND FLOW ANALYSIS

APPENDIX B.8 CHANNEL CONVEYANCE CALCULATIONS

APPENDIX B.9 EROSION AND SEDIMENT CONTROL

APPENDIX B.1  
BACKGROUND INFORMATION



EXTERNAL  
13.0 ha.  
 $Q_{100} = 1420 \text{ l/s}$   
EXTERNAL FLOW  
100 YEAR TOTAL  
CAPTURE  
(REFER TO STORMWATER  
MANAGEMENT REPORT)

- LEGEND**
- 0.90 EXTERNAL DRAINAGE AREA (ha.)
  - 0.65 RUN-OFF COEFFICIENT
  - 0.17 INTERNAL DRAINAGE AREA (ha.)
  - 0.55 RUN-OFF COEFFICIENT
  - DRAINAGE BOUNDARY
  - OVERLAND FLOW ROUTE
  - - - - - LIMIT OF PONDING ON R.O.W. DURING 100 YEAR EVENT

4			
3			
2			
1			
No.	Revision	Date	By

**APPROVED**

TOWNSHIP ENGINEER: \_\_\_\_\_  
 DATE: \_\_\_\_\_

Department of Works  
 Region of Durham  
 Date: \_\_\_\_\_

CORPORATION OF THE TOWNSHIP OF UXBRIDGE


CORAL CREEK HOMES  
**STORM DRAINAGE PLAN**

**VINCENT & ASSOCIATES**  
 Consulting Engineers & Project Managers

3300 Highway No.7 West, Suite 340, Vaughan, L4K 4M3 (905) 669-3655

	Scale: 1:1000	Project No. 97077
	Drawn By: ACAD	Drawing No. ST-1
	Designed By: SH/CE	
	Checked By: VJD	
	Date: JULY 2000	


STORM EVENT	PRE-DEVELOPMENT FLOW (m <sup>3</sup> /s)	ULTIMATE		INTERIM			
		CONTROLLED OUTFLOW (m <sup>3</sup> /s)	VOLUME (m <sup>3</sup> )	ELEVATION (m)	CONTROLLED OUTFLOW (m <sup>3</sup> /s)	VOLUME (m <sup>3</sup> )	ELEVATION (m)
2	0.21	0.07	2,670	271.65+/-	0.03	1,678	271.40+/-
5	0.35	0.16	3,757	271.85+/-	0.05	2,746	271.65+/-
10	0.46	0.29	4,268	271.95+/-	0.08	3,539	271.80+/-
25	0.62	0.50	4,946	272.05+/-	0.19	3,986	271.90+/-
50	0.74	0.67	5,416	272.10+/-	0.28	4,356	271.95+/-
100	0.88	0.86	5,912	272.20+/-	0.39	4,756	272.00+/-



### ESTATES OF AVONLEA

- GENERAL NOTES:**
- DURING CONSTRUCTION, SEDIMENT FOREBAY AREA TO BE FREQUENTLY CHECKED FOR BUILD-UP OF SEDIMENT. FOREBAY TO BE CLEANED OUT ONCE 0.5m OF SEDIMENT HAS ACCUMULATED.
  - IMPERMEABLE CLAY LINER (OR APPROVED EQUIVALENT) TO BE PROVIDED FROM BOTTOM OF FACILITY UP TO 0.5m ABOVE THE 100 YEAR HIGH WATER LEVEL. LINER TO BE 0.5m THICK AND CONSTRUCTED FROM ON SITE MATERIAL, IF AVAILABLE, AND IN ACCORDANCE WITH ADVICE FROM THE SITE'S GEOTECHNICAL REPRESENTATIVE FOR THE PROJECT.
  - ALL POND AREAS, WITH THE EXCEPTION OF THE PERMANENT WET PORTIONS OF THE POND DEEPER THAN 0.30m, SHALL BE HYDROSEED ON 300mm OF NATIVE TOPSOIL.
  - BOTTOM OF WETLAND AREA TO HAVE APPROXIMATELY 300mm NATIVE MATERIAL.
  - HYDROSEED TO BE LOW MAINTENANCE GROUND COVER APPROVED BY THE LANDSCAPE ARCHITECT.
  - ANTI-SEEPAGE COLLARS TO BE USED ON PIPES AT THE CONTROL STRUCTURE.

- NOTE: BERM CONSTRUCTION**
- BERMS TO BE COMPACTED TO 95% SPD AT A MAXIMUM OF 150mm LIFTS.
  - FOUNDATION SUBGRADE OF BERMS TO BE STRIPPED OF TOPSOIL AND ORGANIC MATERIAL PRIOR TO CONSTRUCTION.
  - BERMS TO BE CONSTRUCTED OF CLEAN EARTH FILL FREE OF ANY ORGANIC MATERIAL, COBBLES AND BOULDERS.
  - ALL CONSTRUCTION AND MATERIALS TO BE INSPECTED AND APPROVED BY A GEOTECHNICAL ENGINEER.



No.	Revision	Date	By	Approved
4				
3				
2				
1				

ACCEPTED TO BE IN ACCORDANCE WITH THE TOWNSHIP OF UXBRIDGE STANDARDS. THIS ACCEPTANCE IS NOT TO BE CONSTRUED AS VERIFICATION OF ENGINEERING CONTENT.

TOWNSHIP ENGINEER: \_\_\_\_\_  
 DATE: \_\_\_\_\_


APPROVED  
 Department of Works  
 Region of Durham  
 Date: \_\_\_\_\_

CORPORATION OF THE TOWNSHIP OF UXBRIDGE


### CORAL CREEK HOMES STORMWATER MANAGEMENT DETENTION FACILITY

**VINCENT & ASSOCIATES**  
 Consulting Engineers & Project Managers  
 3300 Highway No.7 West, Suite 340, Vaughan, L4K 4M3 (905) 669-3655

Scale: 1:300	Project No.: 97077
Drawn By: ACAD	Drawing No.: SW-1
Designed By: LK	
Checked By: VJD	
Date: JULY 2000	



\\2018-0302\100\_Technical\Drawings\2021\Figures\2018-0302-SFR-DAP1-DAP2.dwg (DAP-01)



**IBI GROUP**  
 Unit 300 – 8133 Warden Avenue  
 Markham ON L6G 1B3 Canada  
 tel 905 763 2322 fax 905 763 9983  
[ibigroup.com](http://ibigroup.com)


**LEGEND**

- PROPERTY LINE
- EXISTING STORM DRAINAGE AREA BOUNDARY
- EXISTING OVERLAND FLOW DIRECTION



**PRE DEVELOPMENT DRAINAGE AREA PLAN**  
 WESTLANE DEVELOPMENTS LTD.  
 SOUTH BROCK STREET DEVELOPMENT  
 TOWN OF UXBRIDGE  
 REGIONAL MUNICIPALITY OF DURHAM

DATE:	JANUARY 2021	PROJECT No.:	2018-0302
SCALE:	1:1500	FIGURE No.:	DAP-1



1. EQUATION FOR TYPICAL INTENSITY-DURATION-FREQUENCY CURVES:  $I = \frac{C}{T^k}$  (mm/hrs)

$I_2 = \frac{645}{(T+5)^{0.786}}$      $I_5 = \frac{904}{(T+5)^{0.788}}$      $I_{10} = \frac{1055}{(T+5)^{0.788}}$      $I_{25} = \frac{1234}{(T+4)^{0.787}}$      $I_{100} = \frac{1799}{(T+5)^{0.810}}$

2. THE ABOVE EQUATION ARE ONLY VALID FOR T=10 MINUTES TO 1440 MINUTES

APPROVED	TOWNSHIP OF UXBRIDGE	DATE OF ISSUE MARCH 1989
REVISION	RAINFALL INTENSITY DURATION CURVES	DRAWING No.
DATE OF REVISION		US-600

APPENDIX B.2  
PRE-DEVELOPMENT CALCULATIONS

Roy Johnson, P. Eng.

**Pre- Development Composite Runoff Coefficient**

South Brock Street Development  
File No. 2018-0302  
44417

**Drainage Area A1 Pre**

	(ha)		
<b>Total Area:</b>	2.61		
<b>Impervious:</b>	0.17	<b>Coefficient:</b>	0.95
<b>Landscaping:</b>	2.44	<b>Coefficient:</b>	0.25
<b>Composite C:</b>	<b>0.30</b>		
<b>Percent Impervious</b>	<b>6.52%</b>		

**Drainage Area EXT. 1 External Drainage (Uncontrolled Area from Coral Subdivision)**

	(ha)		
<b>Total Area:</b>	0.60		
<b>Impervious:</b>	0.17	<b>Coefficient:</b>	0.95
<b>Landscaping:</b>	0.43	<b>Coefficient:</b>	0.25
<b>Composite C:</b>	<b>0.45</b>		
<b>Percent Impervious</b>	<b>28.33%</b>		



Roy Johnson, P. Eng.

**Peak Time Calculations  
Pre Development**

South Brock Street Development  
File No. 2018-0302  
Aug-21

Area Number	Area	Runoff Coefficient	Length	Change in Elevation	Slope	Log Slope
-	(ha)	-	(m)	-	%	%
A1 Pre	2.61	0.30	228	2.66	1.2	0.07

**Uplands Method**

		Velocity	Time to peak (hour)	Time of Concentration (min)
<b>Forest &amp; Hay Meadow</b>	A1 Pre	0.08	0.52	47
	0	0.08	0.00	0
<b>Woodland, &amp; Fallow</b>	A1 Pre	0.16	0.26	24
	0	0.15	0.00	0
<b>Pasture</b>	A1 Pre	0.23	0.19	17
	0	0.21	0.00	0
<b>Cultivated Straight Row</b>	A1 Pre	0.29	0.15	13
	0	0.27	0.00	0
<b>Bare Soil</b>	A1 Pre	0.32	0.13	12
	0	0.29	0.00	0
<b>Grassed Waterway</b>	A1 Pre	0.48	0.09	8
	0	0.45	0.00	0
<b>Upland Gullies &amp; Paved Areas</b>	A1 Pre	0.65	0.07	6
	0	0.60	0.00	0

**Rational Method  
Pre-Development Flow Calculation**

South Brock Street Development  
File No. 2018-0302  
44417

Roy Johnson, P. Eng.

**Input Parameters**

Area Number	Area	C	Tc
	(ha)		(min.)
A1 Pre	2.61	0.30	13
EXT. 1	0.60	0.45	10

Formula:	$I = a(T+b)^c$	
	a,b,c	Constants
	T	Time of concentration
	I	Rainfall intensity

**Rational Method Calculations**

IDF Data Set: Town of Uxbridge  
Event **2-Year**

a = 645.0  
b = 5.0  
c = 0.786

Area Number	A	C	AC	Tc	I	Q	Q
	(ha)			(min.)	(mm/h)	(m <sup>3</sup> /s)	(L/s)
A1 Pre	2.61	0.30	0.77	13	65.8	0.141	140.9
EXT. 1	0.60	0.45	0.27	10	76.8	0.057	57.4

IDF Data Set: Town of Uxbridge  
Event **5-Year**

a = 904.0  
b = 5.0  
c = 0.788

Area Number	A	C	AC	Tc	I	Q	Q
	(ha)			(min.)	(mm/h)	(m <sup>3</sup> /s)	(L/s)
A1 Pre	2.61	0.30	0.77	13	91.7	0.196	196.4
EXT. 1	0.60	0.45	0.27	10	107.0	0.080	80.0

IDF Data Set: Town of Uxbridge  
Event **10-Year**

a = 1065.0  
b = 5.0  
c = 0.788

Area Number	A	C	AC	Tc	I	Q	Q
	(ha)			(min.)	(mm/h)	(m <sup>3</sup> /s)	(L/s)
A1 Pre	2.61	0.30	0.77	13	108.0	0.231	231.4
EXT. 1	0.60	0.45	0.27	10	126.1	0.094	94.2

IDF Data Set: Town of Uxbridge  
Event **25-Year**

a = 1234.0  
b = 4.0  
c = 0.787

Area Number	A	C	AC	Tc	I	Q	Q
	(ha)			(min.)	(mm/h)	(m <sup>3</sup> /s)	(L/s)
A1 Pre	2.61	0.30	0.77	13	131.2	0.281	281.0
EXT. 1	0.60	0.45	0.27	10	154.6	0.116	115.5

IDF Data Set: Town of Uxbridge  
Event **100-Year**

a = 1799.0  
b = 5.0  
c = 0.810

Area Number	A	C	AC	Tc	I	Q	Q
	(ha)			(min.)	(mm/h)	(m <sup>3</sup> /s)	(L/s)
A1 Pre	2.61	0.30	0.77	13	171.1	0.367	366.6
EXT. 1	0.60	0.45	0.27	10	200.6	0.150	149.9

APPENDIX B.3  
POST DEVELOPMENT CALCULATIONS (QUANTITY  
CONTROL)



**COLE**

Roy Johnson, P. Eng.

**Post Development Composite Runoff Coefficient**

South Brock Street Development  
File No. 2018-0302  
44417

**Drainage Area A1 Post Uncontrolled- Naturalized Swale**



	(ha)		
Total Area:	0.38		
Impervious:	0.00	Coefficient:	0.95
Landscaping:	0.38	Coefficient:	0.25
Composite C:	<b>0.25</b>		
Percent Impervious	<b>0.0%</b>		

**Drainage Area A2 Post Uncontrolled to North**

	(ha)		
Total Area:	0.13		
Impervious:	0.07	Coefficient:	0.95
Landscaping:	0.06	Coefficient:	0.25
Composite C:	<b>0.61</b>		
Percent Impervious	<b>50.77%</b>		


**Drainage Area A3 Post Controlled to Ditch**

	(ha)		
Total Area:	2.10		
Impervious:	1.34	Coefficient:	0.95
Landscaping:	0.75	Coefficient:	0.25
Composite C:	<b>0.70</b>		
Percent Impervious	<b>64.1%</b>		



I:\2018-0302\100\_1\emed\70\_1\18-0302-SFF-DAP1-DAP2.dwg (DAP-02)

**IBI GROUP**  
 Unit 300 – 8133 Warden Avenue  
 Markham ON L6G 1B3 Canada  
 tel 905 763 2322 fax 905 763 9983  
 ibigroup.com

**LEGEND**  
 - - - - - PROPERTY LINE  
 ——— PROPOSED STORM DRAINAGE AREA BOUNDARY  
 PROPOSED OVERLAND FLOW DIRECTION

A1POST  
 0.25ha | 0.50  
 DRAINAGE AREA IN HECTARES  
 STORM DRAINAGE AREA NUMBER  
 RUNOFF COEFFICIENT

**POST DEVELOPMENT DRAINAGE AREA PLAN**  
 WESTLANE DEVELOPMENTS LTD.  
 SOUTH BROCK STREET DEVELOPMENT  
 TOWN OF UXBRIDGE  
 REGIONAL MUNICIPALITY OF DURHAM

DATE: JANUARY 2021	PROJECT No.: 2018-0302
SCALE: 1:1500	FIGURE No.: DAP-2



Partially Filled Pipes Calculations  
Two Year Event

Partially Filled Pipes are Calculated using the End Area Method  
 The average area of each end of the filled pipe is multiplied by the wetted length to give the volume.  
 Full pipes are calculated by taking the full end area of the pipe multiplied by the length of the pipe and method 1 and 2 calculations are ignored.  
 The horizontal wetted length of the pipe is calculated by taking the flow depth at the downstream end up to a maximum of the upstream invert and dividing by the slope.  
 The wetted length is predominantly useful in the calculations for when only one end of the pipe is submerged.  
 If the flow depth at one manhole end is equal to or higher than the pipe diameter it is considered full at that end  
 If the flow depth at one manhole end is 0 or negative then that pipe diameter is considered empty at that end and has a wetted end area of 0, therefore neither Method 1 nor Method 2 would be applicable.

	Method 1 If flow depth < radius	Method 2 If flow depth ≥ radius
solve for		
circular segment height	$h = d$	$h = 2r - d$
central angle	$\theta = 2 \arccos\left(\frac{r-h}{r}\right)$	$\theta = 2 \arccos\left(\frac{r-h}{r}\right)$
circular segment area	$K = \frac{r^2(\theta - \sin \theta)}{2}$	$K = \frac{r^2(\theta - \sin \theta)}{2}$
arc length	$s = r \times \theta$	$s = r \times \theta$
flow area	$A = K$	$A = r^2 - K$
wetted perimeter	$P_w = s$	$P_w = 2\pi r - s$
hydraulic radius	$R_h = \frac{A}{P_w}$	$R_h = \frac{A}{P_w}$

Volume of Stored Water = Upstream and Downstream Wetted Average Area x Length of Pipe  
 Water Elevation 270.21 m

Pipe Storage

Pipe Start and End Locations	MH#	Pipe Diameter (m)	Radius (m)	Pipe Invert (m)	Pipe Obvert(m)	Flat/Horizontal Length of Pipe (m)	Full Length of Pipe (Accounts for Slope)	Slope %	Slope (m/m)	Flow Depth Above Pipe Invert(d)	Check Flow Depth > 0 (If NO then following calculations are not applicable)	Water Depth Type (Method 1 flow depth < radius, Method 2 Flow Depth ≥ radius, Full (full pipe), Empty (N/A))	h	θ	K	s	A	Pw	Rk	Wetted End Area (m2)	Upstream and Downstream Wetted Average Area (m2)	Horizontal Wetted Length (m)	Actual Volume (m3)	
Upstream Manhole	8	0.25	0.13	269.66	269.91					0.55	YES	Full	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	0.05			
Downstream Manhole	9	0.25	0.13	269.50	269.75	32.00	32.00	0.50	0.005	0.71	YES	Full	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	0.05	0.05	32.00	1.57

Note Full Pipe Lengths are lower than Servicing Drawing Lengths because they are measured from End to End

Total Pipe Volume 1.57

Partially Filled Pipes are Calculated using the End Area Method  
 The average area of each end of the filled pipe is multiplied by the wetted length to give the volume.  
 The horizontal wetted length of the pipe is calculated by taking the flow depth at the downstream end up to a maximum of the upstream invert and dividing by the slope.  
 The wetted length is predominantly useful in the calculations for when only one end of the pipe is submerged.  
 If the flow depth at one manhole end is equal to or higher than the pipe diameter it is considered full at that end  
 If the flow depth at one manhole end is 0 or negative then that pipe diameter is considered empty at that end and has a wetted end area of 0

Volume of Stored Water = Upstream and Downstream Wetted Average Area x Length of Pipe  
 Water Elevation 270.21 m

Box Pipe Storage

Pipe Start and End Locations	MH#	Pipe Width (m)	Height (m)	Pipe Invert (m)	Pipe Obvert(m)	Flat/Horizontal Length of Pipe (m)	Full Length of Pipe (Accounts for Slope)	Slope %	Slope (m/m)	Flow Depth Above Pipe Invert(d)	Check Flow Depth > 0 (If NO then following calculations are not applicable)	Pipe End Empty, Partially Full or Full	Wetted End Area (m²)	Upstream and Downstream Wetted Average Area (m²)	Horizontal Wetted Length (m)	Full Wetted Length (m) Only applicable if pipe is full	Actual Volume (m³)
Upstream Manhole	2	1.8	0.90	269.99	270.89					0.22	YES	PartiallyFull	0.40				
Downstream Manhole	8	1.8	0.90	269.75	270.65	80.00	80.00	0.30	0.003	0.46	YES	PartiallyFull	0.84	0.62	80.00	80.00	49.59
Upstream Manhole	3	1.8	0.90	270.36	271.26					0.00	NO	EMPTY	FALSE				
Downstream Manhole	2	1.8	0.90	270.08	270.98	92.00	92.00	0.30	0.003	0.13	YES	PartiallyFull	0.24	0.12	44.79	92.00	5.42
Upstream Manhole	7	1.8	0.90	269.85	270.75					0.36	YES	PartiallyFull	0.65				
Downstream Manhole	8	1.8	0.90	269.69	270.59	54.00	54.00	0.30	0.003	0.52	YES	PartiallyFull	0.94	0.80	54.00	54.00	43.10
Upstream Manhole	6	1.8	0.90	270.04	270.94					0.17	YES	PartiallyFull	0.31				
Downstream Manhole	7	1.8	0.90	269.88	270.78	54.00	54.00	0.30	0.003	0.33	YES	PartiallyFull	0.60	0.46	54.00	54.00	24.63
Upstream Manhole	5	1.8	0.90	270.22	271.12					0.00	NO	EMPTY	FALSE				
Downstream Manhole	6	1.8	0.90	270.13	271.03	29.33	29.33	0.30	0.003	0.08	YES	PartiallyFull	0.15	0.08	28.13	29.33	2.14
Upstream Manhole	4	1.8	0.90	270.34	271.24					0.00	NO	EMPTY	FALSE				
Downstream Manhole	6	1.8	0.90	270.13	271.03	70.00	70.00	0.30	0.003	0.08	YES	PartiallyFull	0.15	0.08	28.13	70.00	2.14

Note Full Pipe Lengths are lower than Servicing Drawing Lengths because they are measured from End to End

Total Pipe Volume (m³) 127.01



Partially Filled Pipes Calculations  
Five Year Event

Partially Filled Pipes are Calculated using the End Area Method  
 The average area of each end of the filled pipe is multiplied by the wetted length to give the volume.  
 Full pipes are calculated by taking the full end area of the pipe multiplied by the length of the pipe and method 1 and 2 calculations are ignored.  
 The horizontal wetted length of the pipe is calculated by taking the flow depth at the downstream end up to a maximum of the upstream invert and dividing by the slope.  
 The wetted length is predominantly useful in the calculations for when only one end of the pipe is submerged.  
 If the flow depth at one manhole end is equal to or higher than the pipe diameter it is considered full at that end  
 If the flow depth at one manhole end is 0 or negative then that pipe diameter is considered empty at that end and has a wetted end area of 0, therefore neither Method 1 nor Method 2 would be applicable.

	Method 1 if flow depth < radius	Method 2 if flow depth ≥ radius
solve for		
circular segment height	$h = d$	$h = 2r - d$
central angle	$\theta = 2 \arccos\left(\frac{r-h}{r}\right)$	$\theta = 2 \arccos\left(\frac{r-h}{r}\right)$
circular segment area	$K = \frac{r^2(\theta - \sin \theta)}{2}$	$K = \frac{r^2(\theta - \sin \theta)}{2}$
arc length	$s = r \times \theta$	$s = r \times \theta$
flow area	$A = K$	$A = r^2 - K$
wetted perimeter	$F_w = s$	$F_w = 2r - s$
hydraulic radius	$R_h = \frac{A}{F_w}$	$R_h = \frac{A}{F_w}$

Volume of Stored Water = Upstream and Downstream Wetted Average Area x Length of Pipe  
 Water Elevation 270.34 m

Pipe Storage

Pipe Start and End Locations	MH#	Pipe Diameter (m)	Radius (m)	Pipe Invert (m)	Pipe Obvert (m)	Flat/Horizontal Length of Pipe (m)	Full Length of Pipe (Accounts for Slope)	Slope %	Slope (m/m)	Flow Depth Above Pipe Invert (d)	Check Flow Depth > 0 (IF NO then following calculations are not applicable)	Water Depth Type (Method 1 flow depth < radius, Method 2 Flow Depth >= radius, Full (full pipe), Empty (N/A))	h	θ	K	s	A	Pw	Rk	Wetted End Area (m2)	Upstream and Downstream Wetted Average Area (m2)	Horizontal Wetted Length (m)	Actual Volume (m3)
Upstream Manhole	8	0.45	0.23	269.66	270.11					0.68	YES	Full	N/A	N/A	N/A	N/A	N/A	N/A	N/A	0.16			
Downstream Manhole	9	0.45	0.23	269.50	269.95	2				0.84	YES	Full	N/A	N/A	N/A	N/A	N/A	N/A	N/A	0.16			
						8	8.00	0.50	0.005												0.16	8.00	1.27
																					<b>Total Pipe Volume</b>	<b>1.27</b>	

Note Full Pipe Lengths are lower than Servicing Drawing Lengths because they are measured from End to End

Partially Filled Pipes are Calculated using the End Area Method  
 The average area of each end of the filled pipe is multiplied by the wetted length to give the volume.  
 The horizontal wetted length of the pipe is calculated by taking the flow depth at the downstream end up to a maximum of the upstream invert and dividing by the slope.  
 The wetted length is predominantly useful in the calculations for when only one end of the pipe is submerged.  
 If the flow depth at one manhole end is equal to or higher than the pipe diameter it is considered full at that end  
 If the flow depth at one manhole end is 0 or negative then that pipe diameter is considered empty at that end and has a wetted end area of 0

Volume of Stored Water = Upstream and Downstream Wetted Average Area x Length of Pipe  
 Water Elevation 270.34 m

Box Pipe Storage

Pipe Start and End Locations	MH#	Pipe Width (m)	Height (m)	Pipe Invert (m)	Pipe Obvert (m)	Flat/Horizontal Length of Pipe (m)	Full Length of Pipe (Accounts for Slope)	Slope %	Slope (m/m)	Flow Depth Above Pipe Invert (d)	Check Flow Depth > 0 (IF NO then following calculations are not applicable)	Pipe End Empty, Partially Full or Full	Wetted End Area (m²)	Upstream and Downstream Wetted Average Area (m²)	Horizontal Wetted Length (m)	Full Wetted Length (m) Only applicable if pipe is full	Actual Volume (m³)
Upstream Manhole	2	1.8	0.90	269.99	270.89					0.35	YES	PartiallyFull	0.64				
Downstream Manhole	8	1.8	0.90	269.75	270.65					0.59	YES	PartiallyFull	1.07				
						80.00	80.00	0.30	0.003				0.85	80.00	80.00	68.39	
Upstream Manhole	3	1.8	0.90	270.36	271.26					0.00	NO	EMPTY	FALSE				
Downstream Manhole	2	1.8	0.90	270.08	270.98					0.26	YES	PartiallyFull	0.48				
						92.00	92.00	0.30	0.003				0.24	88.30	92.00	21.05	
Upstream Manhole	7	1.8	0.90	269.85	270.75					0.49	YES	PartiallyFull	0.89				
Downstream Manhole	8	1.8	0.90	269.69	270.59					0.65	YES	PartiallyFull	1.18				
						54.00	54.00	0.30	0.003				1.03	54.00	54.00	55.78	
Upstream Manhole	6	1.8	0.90	270.04	270.94					0.30	YES	PartiallyFull	0.55				
Downstream Manhole	7	1.8	0.90	269.88	270.78					0.46	YES	PartiallyFull	0.84				
						54.00	54.00	0.30	0.003				0.69	54.00	54.00	37.32	
Upstream Manhole	5	1.8	0.90	270.22	271.12					0.13	YES	PartiallyFull	0.23				
Downstream Manhole	6	1.8	0.90	270.13	271.03					0.21	YES	PartiallyFull	0.39				
						29.33	29.33	0.30	0.003				0.31	29.33	29.33	9.02	
Upstream Manhole	4	1.8	0.90	270.34	271.24					0.00	YES	PartiallyFull	0.01				
Downstream Manhole	6	1.8	0.90	270.13	271.03					0.21	YES	PartiallyFull	0.39				
						70.00	70.00	0.30	0.003				0.20	70.00	70.00	13.85	
																<b>Total Pipe Volume (m³)</b>	<b>205.42</b>

Note Full Pipe Lengths are lower than Servicing Drawing Lengths because they are measured from End to End



Partially Filled Pipes Calculations  
For One Hundred Year Event

Partially Filled Pipes are Calculated using the End Area Method  
The average area of each end of the filled pipe is multiplied by the wetted length to give the volume.  
Full pipes are calculated by taking the full end area of the pipe multiplied by the length of the pipe and method 1 and 2 calculations are ignored.  
The horizontal wetted length of the pipe is calculated by taking the flow depth at the downstream end up to a maximum of the upstream invert and dividing by the slope.  
The wetted length is predominantly useful in the calculations for when only one end of the pipe is submerged.  
If the flow depth at one manhole end is equal to or higher than the pipe diameter it is considered full at that end  
If the flow depth at one manhole end is 0 or negative then that pipe diameter is considered empty at that end and has a wetted end area of 0, therefore neither Method 1 nor Method 2 would be applicable.

	Method 1 if flow depth < radius	Method 2 if flow depth > radius
solve for		
circular segment height	$h = r - d$	$h = 2r - d$
central angle	$\theta = 2 \arccos\left(\frac{r-h}{r}\right)$	$\theta = 2 \arccos\left(\frac{r-h}{r}\right)$
circular segment area	$K = \frac{r^2}{2}(\theta - \sin \theta)$	$K = \frac{r^2}{2}(\theta - \sin \theta)$
arc length	$s = r \times \theta$	$s = r \times \theta$
flow area	$A = K$	$A = r^2 - K$
wetted perimeter	$P_w = s$	$P_w = 2r - s$
hydraulic radius	$R_h = \frac{A}{P_w}$	$R_h = \frac{A}{P_w}$

Volume of Stored Water = Upstream and Downstream Wetted Average Area x Length of Pipe  
Water Elevation: 271.58m

Pipe Storage

Pipe Start and End Locations	MNH	Pipe Diameter (m)	Radius (m)	Pipe Invert (m)	Pipe Obvert (m)	Flat/Horizontal Length of Pipe (m)	Full Length of Pipe (Accounts for Slope)	Slope %	Slope (m/m)	Flow Depth Above Pipe Invert (m)	Check Flow Depth > 0 (If NO then following calculations are not applicable)	Water Depth Type (Method 1 flow depth < radius, Method 2 flow depth > radius, Full (Full pipe), Empty (N/A))	h	theta	K	s	A	Pw	Rk	Wetted End Area (m2)	Upstream and Downstream Wetted Average Area (m2)	Horizontal Wetted Length (m)	Actual Volume (m3)
Upstream Manhole	8	0.45	0.23	269.66	270.11					1.48	YES	Full	N/A	N/A	N/A	N/A	N/A	N/A	N/A	0.16			
Downstream Manhole	9	0.45	0.23	269.50	269.95	32.00	32.00	0.50	0.005	1.64	YES	Full	N/A	N/A	N/A	N/A	N/A	N/A	N/A	0.16	0.16	32.00	5.09

Note Full Pipe Lengths are lower than Servicing Drawing Lengths because they are measured from End to End

Total Pipe Volume 5.09

Partially Filled Pipes are Calculated using the End Area Method  
The average area of each end of the filled pipe is multiplied by the wetted length to give the volume.  
The horizontal wetted length of the pipe is calculated by taking the flow depth at the downstream end up to a maximum of the upstream invert and dividing by the slope.  
The wetted length is predominantly useful in the calculations for when only one end of the pipe is submerged.  
If the flow depth at one manhole end is equal to or higher than the pipe diameter it is considered full at that end  
If the flow depth at one manhole end is 0 or negative then that pipe diameter is considered empty at that end and has a wetted end area of 0

Volume of Stored Water = Upstream and Downstream Wetted Average Area x Length of Pipe  
Water Elevation: 271.58m

Box Pipe Storage

Pipe Start and End Locations	MNH	Pipe Width (m)	Height (m)	Pipe Invert (m)	Pipe Obvert (m)	Flat/Horizontal Length of Pipe (m)	Full Length of Pipe (Accounts for Slope)	Slope %	Slope (m/m)	Flow Depth Above Pipe Invert (m)	Check Flow Depth > 0 (If NO then following calculations are not applicable)	Pipe End Empty, Partially Full or Full	Wetted End Area (m <sup>2</sup> )	Upstream and Downstream Wetted Average Area (m <sup>2</sup> )	Horizontal Wetted Length (m)	Full Wetted Length (m) Only applicable if pipe is full	Actual Volume (m <sup>3</sup> )
Upstream Manhole	2	1.8	0.90	269.99	270.89					0.90	YES	FULL	1.62				
Downstream Manhole	8	1.8	0.90	269.75	270.65	80.00	80.00	0.30	0.003	0.90	YES	FULL	1.62	1.62	80.00	80.00	129.60
Upstream Manhole	3	1.8	0.90	270.36	271.26					0.79	YES	PartiallyFull	1.42				
Downstream Manhole	2	1.8	0.90	270.08	270.98	92.00	92.00	0.30	0.003	0.90	YES	FULL	1.62	1.52	92.00	92.00	139.62
Upstream Manhole	7	1.8	0.90	269.85	270.75					0.90	YES	FULL	1.62				
Downstream Manhole	8	1.8	0.90	269.69	270.59	54.00	54.00	0.30	0.003	0.90	YES	FULL	1.62	1.62	54.00	54.00	87.48
Upstream Manhole	6	1.8	0.90	270.04	270.94					0.90	YES	FULL	1.62				
Downstream Manhole	7	1.8	0.90	269.88	270.78	54.00	54.00	0.30	0.003	0.90	YES	FULL	1.62	1.62	54.00	54.00	87.48
Upstream Manhole	5	1.8	0.90	270.22	271.12					0.90	YES	FULL	1.62				
Downstream Manhole	6	1.8	0.90	270.13	271.03	29.33	29.33	0.30	0.003	0.90	YES	FULL	1.62	1.62	29.33	29.33	47.52
Upstream Manhole	4	1.8	0.90	270.34	271.24					0.80	YES	PartiallyFull	1.44				
Downstream Manhole	6	1.8	0.90	270.13	271.03	70.00	70.00	0.30	0.003	0.90	YES	FULL	1.62	1.53	70.00	70.00	107.24

Note Full Pipe Lengths are lower than Servicing Drawing Lengths because they are measured from End to End

Total Pipe Volume (m<sup>3</sup>) 598.94





Roy Johnson, P. Eng.

**Modified Rational Method - Two Year Storm  
Site Flow and Storage Summary**  
South Brock Street Development  
File No. 2018-0302  
44417

		Uncontrolled- Natural Swale		Uncontrolled- To Brock Street		Controlled- To Discharge into Creek			
		Drainage Areas	A1 Post	Drainage Areas	A2 Post	Drainage Areas	A3 Post		
		Area =	0.38 ha	Area =	0.13 ha	Area =	2.10 ha		
		"C" =	0.25	"C" =	0.61	"C" =	0.70		
		AC1 =	0.09	AC2 =	0.08	AC3 =	1.46		
		Tc =	10.0 min	Tc =	10.0 min	Tc =	10.0 min		
		Time Increment =	5 min	Time Increment =	5 min	Time Increment =	5.0 min		
		Release Rate (R1) =	20.2 L/s	Release Rate (R2) =	16.8 L/s	Controlled Release Rate (R3) =	101.9 L/s		
						Max. Required Storage Volume =	132.4 m <sup>3</sup>		
						Max. Storage Available =	496.56 m <sup>3</sup>		
<b>2-Year Design Storm</b>						<b>Uncontrolled Release Rate =</b>		<b>37.0</b>	<b>L/s</b>
						<b>Controlled Release Rate =</b>		<b>101.9</b>	<b>L/s</b>
						<b>Total Release Rate =</b>		<b>138.9</b>	<b>L/s</b>
						<b>Target Release Rate (2 Yr Pre) =</b>		<b>140.9</b>	<b>L/s</b>
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)
Time (min)	Rainfall Intensity (mm/hr)	Storm Runoff (m <sup>3</sup> /s)	Runoff Volume (m <sup>3</sup> )	Storm Runoff (m <sup>3</sup> /s)	Runoff Volume (m <sup>3</sup> )	Storm Runoff (m <sup>3</sup> /s)	Runoff Volume (m <sup>3</sup> )	Allowable Released Volume (m <sup>3</sup> )	Storage Volume (m <sup>3</sup> )
	$I = A(T+B)^C$	$(3) = [(2)*AC1] / 360$	$(4) = (3)*(1)*60$	$(5) = [(2)*AC2] / 360$	$(6) = (5)*(1)*60$	$(7) = [(2)*AC3] / 360$	$(8) = (7)*(1)*60$	$(9) = [(R3) / 1000]*(1)*60$	$(10) = (8)-(9)$
10.0	76.8	0.020	12.1	0.017	10.1	0.312	187.3	61.2	126.2
15.0	61.2	0.016	14.5	0.013	12.0	0.249	224.1	91.7	132.4
20.0	51.4	0.014	16.2	0.011	13.5	0.209	250.8	122.3	128.5
25.0	44.5	0.012	17.6	0.010	14.6	0.181	271.6	152.9	118.7
30.0	39.4	0.010	18.7	0.009	15.5	0.160	288.7	183.5	105.3
35.0	35.5	0.009	19.7	0.008	16.3	0.144	303.3	214.0	89.3
40.0	32.4	0.009	20.5	0.007	17.0	0.132	316.0	244.6	71.4
45.0	29.8	0.008	21.2	0.007	17.6	0.121	327.2	275.2	52.0
50.0	27.6	0.007	21.9	0.006	18.1	0.112	337.3	305.8	31.6
55.0	25.8	0.007	22.5	0.006	18.6	0.105	346.5	336.3	10.2
60.0	24.2	0.006	23.0	0.005	19.1	0.099	355.0	366.9	0.0
65.0	22.9	0.006	23.5	0.005	19.5	0.093	362.8	397.5	0.0
70.0	21.7	0.006	24.0	0.005	19.9	0.088	370.1	428.1	0.0
75.0	20.6	0.005	24.4	0.005	20.3	0.084	376.9	458.6	0.0
80.0	19.6	0.005	24.8	0.004	20.6	0.080	383.3	489.2	0.0
85.0	18.8	0.005	25.2	0.004	20.9	0.076	389.4	519.8	0.0
90.0	18.0	0.005	25.6	0.004	21.2	0.073	395.2	550.4	0.0
95.0	17.3	0.005	26.0	0.004	21.5	0.070	400.6	580.9	0.0
100.0	16.6	0.004	26.3	0.004	21.8	0.068	405.9	611.5	0.0
105.0	16.0	0.004	26.6	0.004	22.1	0.065	410.8	642.1	0.0
110.0	15.5	0.004	26.9	0.003	22.3	0.063	415.6	672.7	0.0
115.0	15.0	0.004	27.2	0.003	22.6	0.061	420.2	703.2	0.0
120.0	14.5	0.004	27.5	0.003	22.8	0.059	424.7	733.8	0.0
125.0	14.1	0.004	27.8	0.003	23.1	0.057	428.9	764.4	0.0
130.0	13.6	0.004	28.1	0.003	23.3	0.056	433.0	795.0	0.0
135.0	13.3	0.003	28.3	0.003	23.5	0.054	437.0	825.5	0.0
140.0	12.9	0.003	28.6	0.003	23.7	0.052	440.9	856.1	0.0
145.0	12.6	0.003	28.8	0.003	23.9	0.051	444.6	886.7	0.0
150.0	12.2	0.003	29.0	0.003	24.1	0.050	448.2	917.3	0.0
155.0	11.9	0.003	29.3	0.003	24.3	0.049	451.8	947.8	0.0
160.0	11.7	0.003	29.5	0.003	24.5	0.047	455.2	978.4	0.0
165.0	11.4	0.003	29.7	0.002	24.6	0.046	458.5	1009.0	0.0



Roy Johnson, P. Eng.

**Modified Rational Method - Five Year Storm  
Site Flow and Storage Summary**  
South Brock Street Development  
File No. 2018-0302  
44417

		Uncontrolled- Natural Swale		Uncontrolled- To Brock Street		Controlled- To Discharge into Creek			
		Drainage Areas	A1 Post	Drainage Areas	A2 Post	Drainage Areas	A3 Post		
		Area =	0.38 ha	Area =	0.13 ha	Area =	2.10 ha		
		"C" =	0.25	"C" =	0.61	"C" =	0.70		
		AC1 =	0.09	AC2 =	0.08	AC3 =	1.46		
		Tc =	10.0 min	Tc =	10.0 min	Tc =	10.0 min		
		Time Increment =	5 min	Time Increment =	5 min	Time Increment =	5.0 min		
		Release Rate (R1) =	28.2 L/s	Release Rate (R2) =	23.4 L/s	Controlled Release Rate (R3) =	112.7 L/s		
						Max. Required Storage Volume =	214.0 m <sup>3</sup>		
						Max. Storage Available =	496.56 m <sup>3</sup>		
<b>5-Year Design Storm</b>						<b>Uncontrolled Release Rate =</b>		<b>51.6</b>	<b>L/s</b>
						<b>Controlled Release Rate =</b>		<b>112.7</b>	<b>L/s</b>
						<b>Total Release Rate =</b>		<b>164.3</b>	<b>L/s</b>
						<b>Target Release Rate (5 Yr Pre) =</b>		<b>196.4</b>	<b>L/s</b>
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)
Time (min)	Rainfall Intensity (mm/hr)	Storm Runoff (m <sup>3</sup> /s)	Runoff Volume (m <sup>3</sup> )	Storm Runoff (m <sup>3</sup> /s)	Runoff Volume (m <sup>3</sup> )	Storm Runoff (m <sup>3</sup> /s)	Runoff Volume (m <sup>3</sup> )	Allowable Released Volume (m <sup>3</sup> )	Storage Volume (m <sup>3</sup> )
	$I = A(T+B)^C$	$(3) = [(2)*AC1] / 360$	$(4) = (3)*(1)*60$	$(5) = [(2)*AC2] / 360$	$(6) = (5)*(1)*60$	$(7) = [(2)*AC3] / 360$	$(8) = (7)*(1)*60$	$(9) = [(R3) / 1000]*(1)*60$	$(10) = (8)-(9)$
10.0	107.0	0.028	16.9	0.023	14.0	0.435	261.1	67.6	193.5
15.0	85.3	0.022	20.2	0.019	16.8	0.347	312.3	101.4	210.8
20.0	71.5	0.019	22.6	0.016	18.8	0.291	349.2	135.2	214.0
25.0	62.0	0.016	24.5	0.014	20.3	0.252	378.1	169.0	209.1
30.0	54.9	0.014	26.0	0.012	21.6	0.223	401.8	202.8	199.0
35.0	49.4	0.013	27.3	0.011	22.7	0.201	422.0	236.6	185.3
40.0	45.0	0.012	28.5	0.010	23.6	0.183	439.5	270.4	169.1
45.0	41.4	0.011	29.5	0.009	24.5	0.169	455.0	304.2	150.8
50.0	38.4	0.010	30.4	0.008	25.2	0.156	469.0	338.0	131.0
55.0	35.9	0.009	31.2	0.008	25.9	0.146	481.7	371.8	109.9
60.0	33.7	0.009	32.0	0.007	26.5	0.137	493.4	405.6	87.8
65.0	31.8	0.008	32.7	0.007	27.1	0.129	504.2	439.4	64.8
70.0	30.1	0.008	33.3	0.007	27.6	0.122	514.3	473.2	41.0
75.0	28.6	0.008	33.9	0.006	28.1	0.116	523.7	507.0	16.6
80.0	27.3	0.007	34.5	0.006	28.6	0.111	532.5	540.8	0.0
85.0	26.1	0.007	35.0	0.006	29.1	0.106	540.9	574.6	0.0
90.0	25.0	0.007	35.6	0.005	29.5	0.102	548.8	608.4	0.0
95.0	24.0	0.006	36.0	0.005	29.9	0.098	556.4	642.3	0.0
100.0	23.1	0.006	36.5	0.005	30.3	0.094	563.6	676.1	0.0
105.0	22.3	0.006	37.0	0.005	30.7	0.091	570.4	709.9	0.0
110.0	21.5	0.006	37.4	0.005	31.0	0.087	577.0	743.7	0.0
115.0	20.8	0.005	37.8	0.005	31.4	0.085	583.4	777.5	0.0
120.0	20.1	0.005	38.2	0.004	31.7	0.082	589.5	811.3	0.0
125.0	19.5	0.005	38.6	0.004	32.0	0.079	595.3	845.1	0.0
130.0	18.9	0.005	38.9	0.004	32.3	0.077	601.0	878.9	0.0
135.0	18.4	0.005	39.3	0.004	32.6	0.075	606.5	912.7	0.0
140.0	17.9	0.005	39.6	0.004	32.9	0.073	611.8	946.5	0.0
145.0	17.4	0.005	40.0	0.004	33.2	0.071	616.9	980.3	0.0
150.0	17.0	0.004	40.3	0.004	33.4	0.069	621.9	1014.1	0.0
155.0	16.6	0.004	40.6	0.004	33.7	0.067	626.8	1047.9	0.0
160.0	16.2	0.004	40.9	0.004	33.9	0.066	631.5	1081.7	0.0
165.0	15.8	0.004	41.2	0.003	34.2	0.064	636.1	1115.5	0.0

Roy Johnson, P. Eng.

**Modified Rational Method - Hundred Year Storm  
Site Flow and Storage Summary**  
South Brock Street Development  
File No. 2018-0302  
44417

Uncontrolled- Natural Swale	Uncontrolled- To Brock Street	Controlled- To Discharge into Creek
Drainage Areas A1 Post Area = <b>0.38</b> ha "C" = <b>0.25</b> AC1 = <b>0.09</b> Tc = <b>10.0</b> min Time Increment = <b>5</b> min Release Rate (R1) = <b>52.9</b> L/s	Drainage Areas A2 Post Area = <b>0.13</b> ha "C" = <b>0.61</b> AC2 = <b>0.08</b> Tc = <b>10.0</b> min Time Increment = <b>5</b> min Release Rate (R2) = <b>43.9</b> L/s	Drainage Areas A3 Post Area = <b>2.10</b> ha "C" = <b>0.70</b> AC3 = <b>1.46</b> Tc = <b>10.0</b> min Time Increment = <b>5.0</b> min Controlled Release Rate (R3) = <b>140.1</b> L/s  Max. Required Storage Volume = <b>488.1</b> m <sup>3</sup> Max. Storage Available = <b>496.56</b> m <sup>3</sup>
<b>100-Year Design Storm</b> A= 1799.0 B= 5.0 C= 0.810 I = A/(T+B)^C		Uncontrolled Release Rate = <b>96.7</b> L/s Controlled Release Rate = <b>140.1</b> L/s Total Release Rate = <b>236.8</b> L/s Target Release Rate (100 Yr Pre) = <b>366.6</b> L/s

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)
Time (min)	Rainfall Intensity (mm/hr)	Storm Runoff (m <sup>3</sup> /s)	Runoff Volume (m <sup>3</sup> )	Storm Runoff (m <sup>3</sup> /s)	Runoff Volume (m <sup>3</sup> )	Storm Runoff (m <sup>3</sup> /s)	Runoff Volume (m <sup>3</sup> )	Allowable Released Volume (m <sup>3</sup> )	Storage Volume (m <sup>3</sup> )
	I = A(T+B)^C	(3) = [(2)*AC1] / 360	(4) = (3)*(1)*60	(5) = [(2)*AC2] / 360	(6) = (5)*(1)*60	(7) = [(2)*AC3] / 360	(8) = (7)*(1)*60	(9) = [(R3) / 1000]*(1)*60	(10) = (8)-(9)
10.0	200.6	0.053	31.7	0.044	26.3	0.816	489.6	84.0	405.6
15.0	158.9	0.042	37.7	0.035	31.3	0.646	581.8	126.1	455.7
20.0	132.6	0.035	41.9	0.029	34.8	0.540	647.4	168.1	479.3
25.0	114.4	0.030	45.2	0.025	37.5	0.465	698.2	210.1	488.1
30.0	101.0	0.027	47.9	0.022	39.7	0.411	739.5	252.1	487.3
35.0	90.6	0.024	50.2	0.020	41.6	0.369	774.3	294.2	480.1
40.0	82.4	0.022	52.1	0.018	43.2	0.335	804.4	336.2	468.2
45.0	75.7	0.020	53.8	0.017	44.7	0.308	830.9	378.2	452.7
50.0	70.0	0.018	55.4	0.015	45.9	0.285	854.6	420.2	434.4
55.0	65.3	0.017	56.8	0.014	47.1	0.265	876.1	462.2	413.9
60.0	61.2	0.016	58.0	0.013	48.1	0.249	895.7	504.3	391.5
65.0	57.6	0.015	59.2	0.013	49.1	0.234	913.9	546.3	367.6
70.0	54.5	0.014	60.3	0.012	50.0	0.222	930.7	588.3	342.4
75.0	51.7	0.014	61.3	0.011	50.9	0.210	946.4	630.3	316.0
80.0	49.2	0.013	62.3	0.011	51.7	0.200	961.1	672.4	288.7
85.0	47.0	0.012	63.2	0.010	52.4	0.191	974.9	714.4	260.6
90.0	45.0	0.012	64.0	0.010	53.1	0.183	988.1	756.4	231.7
95.0	43.2	0.011	64.8	0.009	53.8	0.176	1000.5	798.4	202.1
100.0	41.5	0.011	65.6	0.009	54.4	0.169	1012.4	840.4	171.9
105.0	39.9	0.011	66.3	0.009	55.0	0.162	1023.7	882.5	141.2
110.0	38.5	0.010	67.0	0.008	55.6	0.157	1034.5	924.5	110.0
115.0	37.2	0.010	67.7	0.008	56.2	0.151	1044.9	966.5	78.3
120.0	36.0	0.009	68.3	0.008	56.7	0.147	1054.8	1008.5	46.3
125.0	34.9	0.009	69.0	0.008	57.2	0.142	1064.4	1050.6	13.9
130.0	33.8	0.009	69.6	0.007	57.7	0.138	1073.7	1092.6	0.0
135.0	32.9	0.009	70.1	0.007	58.2	0.134	1082.6	1134.6	0.0
140.0	31.9	0.008	70.7	0.007	58.7	0.130	1091.2	1176.6	0.0
145.0	31.1	0.008	71.2	0.007	59.1	0.126	1099.6	1218.6	0.0
150.0	30.3	0.008	71.8	0.007	59.5	0.123	1107.7	1260.7	0.0
155.0	29.5	0.008	72.3	0.006	60.0	0.120	1115.6	1302.7	0.0
160.0	28.8	0.008	72.8	0.006	60.4	0.117	1123.2	1344.7	0.0
165.0	28.1	0.007	73.3	0.006	60.8	0.114	1130.6	1386.7	0.0



**COLE**

Roy Johnson, P. Eng.

**Orifice Control**

South Brock Street Development  
File No. 2018-0302  
44417

**Orifice Equation**

$$Q = C \times A \times \sqrt{2 \times g \times h}$$

Storm Event	Drainage Area ID	Orifice Location	Orifice Coefficient	Diameter of Orifice	Orifice Invert	Headwater Elevation	Total Head	Area of Orifice	Release Rate
				(mm)	(m)	(m)	(m)	(m <sup>2</sup> )	(L/s)
2-Year	A3 Post	Outlet to Creek	0.61	225	269.52	270.42	0.90	0.040	101.9
5-Year	A3 Post	Outlet to Creek	0.61	225	269.52	270.62	1.10	0.040	112.7
100-Year	A3 Post	Outlet to Creek	0.61	225	269.52	271.22	1.70	0.040	140.1



**COLE**

Prepared By: S.Rayner, EIT

### Water Quality Calculations

South Brock Street Development

File No. 2018-0302

Date: July 2018

Catchment	Surface	Treatment	Effective TSS	Area (ha)	% Area of Site	Overall TSS Removal
A1 Post	Landscape	Inherent	80%	0.38	15%	12%
A2 Post	Landscape	Inherent	80%	0.07	3%	2%
	Rooftop	Inherent	80%	0.06	2%	2%
A3 Post	Asphalt/Impervious Area	Jellyfish Unit	80%	0.80	31%	24%
	Landscape	Inherent	80%	0.76	29%	23%
	Rooftop	Inherent	80%	0.54	21%	17%
<b>Total</b>	-	-	-	<b>2.61</b>	<b>100.0%</b>	<b>80%</b>

APPENDIX B.4  
QUALITY CONTROL CALCULATIONS



Prepared By Tim Ng

### Water Quality Calculations

South Brock Street Development  
 File No. 2018-0302  
 Date: July 2018

Catchment	Surface	Treatment	Effective TSS	Area (ha)	% Area of Site	Overall TSS Removal
A1 Post	Landscape	Inherent	80%	0.40	15%	12%
A2 Post	Landscape	Inherent	80%	0.07	3%	2%
	Rooftop	Inherent	80%	0.04	2%	1%
A3 Post	Asphalt/Impervious Area	Jellyfish Unit	80%	0.72	27%	22%
	Landscape	Inherent	80%	0.79	30%	24%
	Rooftop	Inherent	80%	0.60	23%	18%
<b>Total</b>	-	-	-	<b>2.61</b>	<b>100.0%</b>	<b>80%</b>

- 4.1.4 Inlet and Outlet Pipes Inlet and outlet pipes should be securely set into the device using approved pipe seals (flexible boot connections, where applicable) so that the structure is watertight, and such that any pipe intrusion into the device does not impact the device functionality.
- 4.1.5 Frame and Cover Installation Adjustment units (e.g. grade rings) should be installed to set the frame and cover at the required elevation. The adjustment units should be laid in a full bed of mortar with successive units being joined using sealant recommended by the manufacturer. Frames for the cover should be set in a full bed of mortar at the elevation specified.

#### 4.2 MAINTENANCE ACCESS WALL

In some instances the Maintenance Access Wall, if provided, shall require an extension attachment and sealing to the precast wall and cartridge deck at the job site, rather than at the precast facility. In this instance, installation of these components shall be performed according to instructions provided by the manufacturer.

4.3 FILTER CARTRIDGE INSTALLATION Filter cartridges shall be installed in the cartridge deck only after the construction site is fully stabilized and in accordance with the manufacturer's guidelines and recommendations. Contractor to contact the manufacturer to schedule cartridge delivery and review procedures/requirements to be completed to the device prior to installation of the cartridges and activation of the system.

### PART 5 – QUALITY ASSURANCE

5.1 FILTER CARTRIDGE INSTALLATION Manufacturer shall coordinate delivery of filter cartridges and other internal components with contractor. Filter cartridges shall be delivered and installed complete after site is stabilized and unit is ready to accept cartridges. Unit is ready to accept cartridges after it has been cleaned out and any standing water, debris, and other materials have been removed. Contractor shall take appropriate action to protect the filter cartridge receptacles and filter cartridges from damage during construction, and in accordance with the manufacturer's recommendations and guidance. For systems with cartridges installed prior to full site stabilization and prior to system activation, the contractor can plug inlet and outlet pipes to prevent stormwater and other influent from entering the device. Plugs must be removed during the activation process.

#### 5.2 INSPECTION AND MAINTENANCE

5.2.1 The manufacturer shall provide an Owner's Manual upon request.

5.2.2 After construction and installation, and during operation, the device shall be inspected and cleaned as necessary based on the manufacturer's recommended inspection and maintenance guidelines and the local regulatory agency/body.

5.3 REPLACEMENT FILTER CARTRIDGES When replacement membrane filter elements and/or other parts are required, only membrane filter elements and parts approved by the manufacturer for use with the stormwater quality filter device shall be installed.

### END OF SECTION





# STANDARD OFFLINE Jellyfish Filter Sizing Report

## Project Information

Date	Tuesday, January 29, 2019
Project Name	Brock St. S
Project Number	2018-0302
Location	Uxbridge

## Jellyfish Filter Design Overview

This report provides information for the sizing and specification of the Jellyfish Filter. When designed properly in accordance to the guidelines detailed in the Jellyfish Filter Technical Manual, the Jellyfish Filter will exceed the performance and longevity of conventional horizontal bed and granular media filters.

Please see [www.ImbriumSystems.com](http://www.ImbriumSystems.com) for more information.

## Jellyfish Filter System Recommendation

The Jellyfish Filter model JF8-8-2 is recommended to meet the water quality objective by treating a flow of 45.4 L/s, which meets or exceeds 90% of the average annual rainfall runoff volume based on 18 years of TORONTO CENTRAL rainfall data for this site. This model has a sediment capacity of 512 kg, which meets or exceeds the estimated average annual sediment load.

Jellyfish Model	Number of High-Flo Cartridges	Number of Draindown Cartridges	Manhole Diameter (m)	Treatment Flow Rate (L/s)	Sediment Capacity (kg)
JF8-8-2	8	2	2.4	45.4	512

## The Jellyfish Filter System

The patented Jellyfish Filter is an engineered stormwater quality treatment technology featuring unique membrane filtration in a compact stand-alone treatment system that removes a high level and wide variety of stormwater pollutants. Exceptional pollutant removal is achieved at high treatment flow rates with minimal head loss and low maintenance costs. Each lightweight Jellyfish Filter cartridge contains an extraordinarily large amount of membrane surface area, resulting in superior flow capacity and pollutant removal capacity.

## Maintenance

Regular scheduled inspections and maintenance is necessary to assure proper functioning of the Jellyfish Filter. The maintenance interval is designed to be a minimum of 12 months, but this will vary depending on site loading conditions and upstream pretreatment measures. Quarterly inspections and inspections after all storms beyond the 5-year event are recommended until enough historical performance data has been logged to comfortably initiate an alternative inspection interval.

Please see [www.ImbriumSystems.com](http://www.ImbriumSystems.com) for more information.

Thank you for the opportunity to present this information to you and your client.

## Performance

Jellyfish efficiently captures a high level of Stormwater pollutants, including:


- ☑ 89% of the total suspended solids (TSS) load, including particles less than 5 microns
- ☑ 59% TP removal & 51% TN removal
- ☑ 90% Total Copper, 81% Total Lead, 70% Total Zinc
- ☑ Particulate-bound pollutants such as nutrients, toxic metals, hydrocarbons and bacteria
- ☑ Free oil, Floatable trash and debris

## Field Proven Performance

The Jellyfish filter has been field-tested on an urban site with 25 TARP qualifying rain events and field monitored according to the TARP field test protocol, demonstrating:

- A median TSS removal efficiency of 89%, and a median SSC removal of 99%;
- The ability to capture fine particles as indicated by an effluent d50 median of 3 microns for all monitored storm events, and a median effluent turbidity of 5 NTUs;
- A median Total Phosphorus removal of 59%, and a median Total Nitrogen removal of 51%.

## Jellyfish Filter Treatment Functions



*Pre-treatment and Membrane Filtration*

## Project Information

Date:	Tuesday, January 29, 2019
Project Name:	Brock St. S
Project Number:	2018-0302
Location:	Uxbridge

## Designer Information

Company:	Cole Engineering Group Ltd.
Contact:	Tim Ng
Phone #:	

## Notes

--

## Design System Requirements

<b>Flow Loading</b>	90% of the Average Annual Runoff based on 18 years of TORONTO CENTRAL rainfall data:	<b>35.8 L/s</b>
<b>Sediment Loading</b>	Treating 90% of the average annual runoff volume, 8107 m <sup>3</sup> , with a suspended sediment concentration of 60 mg/L.	<b>486 kg*</b>

\* Indicates that sediment loading is the limiting parameter in the sizing of this Jellyfish system

## Recommendation

The Jellyfish Filter model JF8-8-2 is recommended to meet the water quality objective by treating a flow of 45.4 L/s, which meets or exceeds 90% of the average annual rainfall runoff volume based on 18 years of TORONTO CENTRAL rainfall data for this site. This model has a sediment capacity of 512 kg, which meets or exceeds the estimated average annual sediment load.

Jellyfish Model	Number of High-Flo Cartridges	Number of Draindown Cartridges	Manhole Diameter (m)	Wet Vol Below Deck (L)	Sump Storage (m <sup>3</sup> )	Oil Capacity (L)	Treatment Flow Rate (L/s)	Sediment Capacity (kg)
JF4-1-1	1	1	1.2	2313	0.34	379	7.6	85
JF4-2-1	2	1	1.2	2313	0.34	379	12.6	142
JF6-3-1	3	1	1.8	5205	0.79	848	17.7	199
JF6-4-1	4	1	1.8	5205	0.79	848	22.7	256
JF6-5-1	5	1	1.8	5205	0.79	848	27.8	313
JF6-6-1	6	1	1.8	5205	0.79	848	28.6	370
JF8-6-2	6	2	2.4	9252	1.42	1469	35.3	398
JF8-7-2	7	2	2.4	9252	1.42	1469	40.4	455
<b>JF8-8-2</b>	<b>8</b>	<b>2</b>	<b>2.4</b>	<b>9252</b>	<b>1.42</b>	<b>1469</b>	<b>45.4</b>	<b>512</b>
JF8-9-2	9	2	2.4	9252	1.42	1469	50.5	569
JF8-10-2	10	2	2.4	9252	1.42	1469	50.5	626
JF10-11-3	11	3	3.0	14456	2.21	2302	63.1	711
JF10-12-3	12	3	3.0	14456	2.21	2302	68.2	768
JF10-12-4	12	4	3.0	14456	2.21	2302	70.7	796
JF10-13-4	13	4	3.0	14456	2.21	2302	75.7	853
JF10-14-4	14	4	3.0	14456	2.21	2302	78.9	910
JF10-15-4	15	4	3.0	14456	2.21	2302	78.9	967
JF10-16-4	16	4	3.0	14456	2.21	2302	78.9	1024
JF10-17-4	17	4	3.0	14456	2.21	2302	78.9	1081
JF10-18-4	18	4	3.0	14456	2.21	2302	78.9	1138
JF10-19-4	19	4	3.0	14456	2.21	2302	78.9	1195
JF12-20-5	20	5	3.6	20820	3.2	2771	113.6	1280
JF12-21-5	21	5	3.6	20820	3.2	2771	113.7	1337
JF12-22-5	22	5	3.6	20820	3.2	2771	113.7	1394
JF12-23-5	23	5	3.6	20820	3.2	2771	113.7	1451
JF12-24-5	24	5	3.6	20820	3.2	2771	113.7	1508
JF12-25-5	25	5	3.6	20820	3.2	2771	113.7	1565
JF12-26-5	26	5	3.6	20820	3.2	2771	113.7	1622
JF12-27-5	27	5	3.6	20820	3.2	2771	113.7	1679

## Rainfall

Name:	TORONTO CENTRAL
State:	ON
ID:	100
Record:	1982 to 1999
Co-ords:	45°30'N, 90°30'W

## Drainage Area


Total Area:	2.1 ha
Imperviousness:	64.7%

## Upstream Detention

Peak Release Rate:	n/a
Pretreatment Credit:	n/a

## Jellyfish Filter Design Notes

- Typically the Jellyfish Filter is designed in an offline configuration, as all stormwater filter systems will perform for a longer duration between required maintenance services when designed and applied in off-line configurations. Depending on the design parameters, an optional internal bypass may be incorporated into the Jellyfish Filter, however note the inspection and maintenance frequency should be expected to increase above that of an off-line system. Speak to your local representative for more information.



*Jellyfish Filter Typical Layout*

- Typically, 18 inches (457 mm) of driving head is designed into the system, calculated as the difference in elevation between the top of the diversion structure weir and the invert of the Jellyfish Filter outlet pipe. Alternative driving head values can be designed as 12 to 24 inches (305 to 610mm) depending on specific site requirements, requiring additional sizing and design assistance.
- Typically, the Jellyfish Filter is designed with the inlet pipe configured 6 inches (150 mm) above the outlet invert elevation. However, depending on site parameters this can vary to an optional configuration of the inlet pipe entering the unit below the outlet invert elevation.
- The Jellyfish Filter can accommodate multiple inlet pipes within certain restrictions.
- While the optional inlet below deck configuration offers 0 to 360 degree flexibility between the inlet and outlet pipe, typical systems conform to the following:

Model Diameter (m)	Minimum Angle Inlet / Outlet Pipes	Minimum Inlet Pipe Diameter (mm)	Minimum Outlet Pipe Diameter (mm)
1.2	62°	150	200
1.8	59°	200	250
<b>2.4</b>	<b>52°</b>	<b>250</b>	<b>300</b>
3.0	48°	300	450
3.6	40°	300	450

- The Jellyfish Filter can be built at all depths of cover generally associated with conventional stormwater conveyance systems. For sites that require minimal depth of cover for the stormwater infrastructure, the Jellyfish Filter can be applied in a shallow application using a hatch cover. The general minimum depth of cover is 36 inches (915 mm) from top of the underslab to outlet invert.
- If driving head calculations account for water elevation during submerged conditions the Jellyfish Filter will function effectively under submerged conditions.
- Jellyfish Filter systems may incorporate grated inlets depending on system configuration.
- For sites with water quality treatment flow rates or mass loadings that exceed the design flow rate of the largest standard Jellyfish Filter manhole models, systems can be designed that hydraulically connect multiple Jellyfish Filters in series or alternatively Jellyfish Vault units can be designed.

# STANDARD SPECIFICATION STORMWATER QUALITY – MEMBRANE FILTRATION TREATMENT DEVICE

## PART 1 – GENERAL

### 1.1 WORK INCLUDED

Specifies requirements for construction and performance of an underground stormwater quality membrane filtration treatment device that removes pollutants from stormwater runoff through the unit operations of sedimentation, floatation, and membrane filtration.

### 1.2 REFERENCE STANDARDS

ASTM C 891: Specification for Installation of Underground Precast Concrete Utility Structures  
ASTM C 478: Specification for Precast Reinforced Concrete Manhole Sections  
ASTM C 443: Specification for Joints for Concrete Pipe and Manholes, Using Rubber Gaskets  
ASTM D 4101: Specification for Copolymer steps construction

#### CAN/CSA-A257.4-M92

Joints for Circular Concrete Sewer and Culvert Pipe, Manhole Sections and Fittings Using Rubber Gaskets

#### CAN/CSA-A257.4-M92

Precast Reinforced Circular Concrete Manhole Sections, Catch Basins and Fittings

Canadian Highway Bridge Design Code

### 1.3 SHOP DRAWINGS

Shop drawings for the structure and performance are to be submitted with each order to the contractor. Contractor shall forward shop drawing submittal to the consulting engineer for approval. Shop drawings are to detail the structure's precast concrete and call out or note the fiberglass (FRP) internals/components.

### 1.4 PRODUCT SUBSTITUTIONS

No product substitutions shall be accepted unless submitted 10 days prior to project bid date, or as directed by the engineer of record. Submissions for substitutions require review and approval by the Engineer of Record, for hydraulic performance, impact to project designs, equivalent treatment performance, and any required project plan and report (hydrology/hydraulic, water quality, stormwater pollution) modifications that would be required by the approving jurisdictions/agencies. Contractor to coordinate with the Engineer of Record any applicable modifications to the project estimates of cost, bonding amount determinations, plan check fees for changes to approved documents, and/or any other regulatory requirements resulting from the product substitution.

### 1.5 HANDLING AND STORAGE

Prevent damage to materials during storage and handling.

## PART 2 – PRODUCTS

Imbrium Systems  
[www.imbriumsystems.com](http://www.imbriumsystems.com)

Ph 888-279-8826  
Ph 416-960-9900

## 2.1 GENERAL

- 2.1.1 The device shall be a cylindrical or rectangular, all concrete structure (including risers), constructed from precast concrete riser and slab components or monolithic precast structure(s), installed to conform to ASTM C 891 and to any required state highway, municipal or local specifications; whichever is more stringent. The device shall be watertight.
- 2.1.2 Cartridge Deck The cylindrical concrete device shall include a fiberglass deck. The rectangular concrete device shall include a coated aluminum deck. In either instance, the insert shall be bolted and sealed watertight inside the precast concrete chamber. The deck shall serve as: (a) a horizontal divider between the lower treatment zone and the upper treated effluent zone; (b) a deck for attachment of filter cartridges such that the membrane filter elements of each cartridge extend into the lower treatment zone; (c) a platform for maintenance workers to service the filter cartridges (maximum manned weight = 450 pounds (204 kg)); (d) a conduit for conveyance of treated water to the effluent pipe.
- 2.1.3 Membrane Filter Cartridges Filter cartridges shall be comprised of reusable cylindrical membrane filter elements connected to a perforated head plate. The number of membrane filter elements per cartridge shall be a minimum of eleven 2.75-inch (70-mm) diameter elements. The length of each filter element shall be a minimum 15 inches (381 mm). Each cartridge shall be fitted into the cartridge deck by insertion into a cartridge receptacle that is permanently mounted into the cartridge deck. Each cartridge shall be secured by a cartridge lid that is threaded onto the receptacle, or similar mechanism to secure the cartridge into the deck. The maximum treatment flow rate of a filter cartridge shall be controlled by an orifice in the cartridge lid, or on the individual cartridge itself, and based on a design flux rate (surface loading rate) determined by the maximum treatment flow rate per unit of filtration membrane surface area. The maximum design flux rate shall be 0.21 gpm/ft<sup>2</sup> (0.142 lps/m<sup>2</sup>).

Each membrane filter cartridge shall allow for manual installation and removal. Each filter cartridge shall have filtration membrane surface area and dry installation weight as follows (if length of filter cartridge is between those listed below, the surface area and weight shall be proportionate to the next length shorter and next length longer as shown below):

Filter Cartridge Length (in / mm)	Minimum Filtration Membrane Surface Area (ft <sup>2</sup> / m <sup>2</sup> )	Maximum Filter Cartridge Dry Weight (lbs / kg)
15	106 / 9.8	10.5 / 4.8
27	190 / 17.7	15.0 / 6.8
40	282 / 26.2	20.5 / 9.3
54	381 / 35.4	25.5 / 11.6

- 2.1.4 Backwashing Cartridges The filter device shall have a weir extending above the cartridge deck, or other mechanism, that encloses the high flow rate filter cartridges when placed in their respective cartridge receptacles within the cartridge deck. The weir, or other mechanism, shall collect a pool of filtered water during inflow events that backwashes the high flow rate cartridges when the inflow

event subsides. All filter cartridges and membranes shall be reusable and allow for the use of filtration membrane rinsing procedures to restore flow capacity and sediment capacity; extending cartridge service life.

- 2.1.5 Maintenance Access to Captured Pollutants The filter device shall contain an opening(s) that provides maintenance access for removal of accumulated floatable pollutants and sediment, removal of and replacement of filter cartridges, cleaning of the sump, and rinsing of the deck. Access shall have a minimum clear vertical clear space over all of the filter cartridges. Filter cartridges shall be able to be lifted straight vertically out of the receptacles and deck for the entire length of the cartridge.
- 2.1.6 Bend Structure The device shall be able to be used as a bend structure with minimum angles between inlet and outlet pipes of 90-degrees or less in the stormwater conveyance system.
- 2.1.7 Double-Wall Containment of Hydrocarbons The cylindrical precast concrete device shall provide double-wall containment for hydrocarbon spill capture by a combined means of an inner wall of fiberglass, to a minimum depth of 12 inches (305 mm) below the cartridge deck, and the precast vessel wall.
- 2.1.8 Baffle The filter device shall provide a baffle that extends from the underside of the cartridge deck to a minimum length equal to the length of the membrane filter elements. The baffle shall serve to protect the membrane filter elements from contamination by floatables and coarse sediment. The baffle shall be flexible and continuous in cylindrical configurations, and shall be a straight concrete or aluminum wall in rectangular configurations.
- 2.1.9 Sump The device shall include a minimum 24 inches (610 mm) of sump below the bottom of the cartridges for sediment accumulation, unless otherwise specified by the design engineer. Depths less than 24 inches may have an impact on the total performance and/or longevity between cartridge maintenance/replacement of the device.

## 2.2 PRECAST CONCRETE SECTIONS

All precast concrete components shall be manufactured to a minimum live load of HS-20 truck loading or greater based on local regulatory specifications, unless otherwise modified or specified by the design engineer, and shall be watertight.

2.3 JOINTS All precast concrete manhole configuration joints shall use nitrile rubber gaskets and shall meet the requirements of ASTM C443, Specification C1619, Class D or engineer approved equal to ensure oil resistance. Mastic sealants or butyl tape are not an acceptable alternative.

2.4 GASKETS Only profile neoprene or nitrile rubber gaskets in accordance to CSA A257.3-M92 will be accepted. Mastic sealants, butyl tape or Con Seal CS-101 are not acceptable gasket materials.

2.5 FRAME AND COVER Frame and covers must be manufactured from cast-iron or other composite material tested to withstand H-20 or greater design loads, and as approved by the

local regulatory body. Frames and covers must be embossed with the name of the device manufacturer or the device brand name.

- 2.6 DOORS AND HATCHES If provided shall meet designated loading requirements or at a minimum for incidental vehicular traffic.
- 2.7 CONCRETE All concrete components shall be manufactured according to local specifications and shall meet the requirements of ASTM C 478.
- 2.8 FIBERGLASS The fiberglass portion of the filter device shall be constructed in accordance with the following standard: ASTM D-4097: Contact Molded Glass Fiber Reinforced Chemical Resistant Tanks.
- 2.9 STEPS Steps shall be constructed according to ASTM D4101 of copolymer polypropylene, and be driven into preformed or pre-drilled holes after the concrete has cured, installed to conform to applicable sections of state, provincial and municipal building codes, highway, municipal or local specifications for the construction of such devices.
- 2.10 INSPECTION All precast concrete sections shall be inspected to ensure that dimensions, appearance and quality of the product meet local municipal specifications and ASTM C 478.

### PART 3 – PERFORMANCE

#### 3.1 GENERAL

- 3.1.1 Verification – The stormwater quality filter must be verified in accordance with ISO 14034:2016 Environmental management – Environmental technology verification (ETV).
- 3.1.2 Function - The stormwater quality filter treatment device shall function to remove pollutants by the following unit treatment processes; sedimentation, floatation, and membrane filtration.
- 3.1.3 Pollutants - The stormwater quality filter treatment device shall remove oil, debris, trash, coarse and fine particulates, particulate-bound pollutants, metals and nutrients from stormwater during runoff events.
- 3.1.4 Bypass - The stormwater quality filter treatment device shall typically utilize an external bypass to divert excessive flows. Internal bypass systems shall be equipped with a floatables baffle, and must avoid passage through the sump and/or cartridge filtration zone.
- 3.1.5 Treatment Flux Rate (Surface Loading Rate) – The stormwater quality filter treatment device shall treat 100% of the required water quality treatment flow based on a maximum design treatment flux rate (surface loading rate) across the membrane filter cartridges of 0.21 gpm/ft<sup>2</sup> (0.142 lps/m<sup>2</sup>).



### 3.2 FIELD TEST PERFORMANCE

At a minimum, the stormwater quality filter device shall have been field tested and verified with a minimum 25 TARP qualifying storm events and field monitoring shall have been conducted according to the TARP 2009 NJDEP TARP field test protocol, and have received NJCAT verification.

- 3.2.1 Suspended Solids Removal - The stormwater quality filter treatment device shall have demonstrated a minimum median TSS removal efficiency of 85% and a minimum median SSC removal efficiency of 95%.
- 3.2.2 Runoff Volume – The stormwater quality filter treatment device shall be engineered, designed, and sized to treat a minimum of 90 percent of the annual runoff volume determined from use of a minimum 15-year rainfall data set.
- 3.2.3 Fine Particle Removal - The stormwater quality filter treatment device shall have demonstrated the ability to capture fine particles as indicated by a minimum median removal efficiency of 75% for the particle fraction less than 25 microns, an effluent  $d_{50}$  of 15 microns or lower for all monitored storm events.
- 3.2.4 Turbidity Reduction - The stormwater quality filter treatment device shall have demonstrated the ability to reduce the turbidity from influent from a range of 5 to 171 NTU to an effluent turbidity of 15 NTU or lower.
- 3.2.5 Nutrient (Total Phosphorus & Total Nitrogen) Removal - The stormwater quality filter treatment device shall have demonstrated a minimum median Total Phosphorus removal of 55%, and a minimum median Total Nitrogen removal of 50%.
- 3.2.6 Metals (Total Zinc & Total Copper) Removal - The stormwater quality filter treatment device shall have demonstrated a minimum median Total Zinc removal of 55%, and a minimum median Total Copper removal of 85%.

### 3.3 INSPECTION and MAINTENANCE

The stormwater quality filter device shall have the following features:

- 3.3.1 Durability of membranes are subject to good handling practices during inspection and maintenance (removal, rinsing, and reinsertion) events, and site specific conditions that may have heavier or lighter loading onto the cartridges, and pollutant variability that may impact the membrane structural integrity. Membrane maintenance and replacement shall be in accordance with manufacturer's recommendations.
- 3.3.2 Inspection which includes trash and floatables collection, sediment depth determination, and visible determination of backwash pool depth shall be easily conducted from grade (outside the structure).
- 3.3.3 Manual rinsing of the reusable filter cartridges shall promote restoration of the flow capacity and sediment capacity of the filter cartridges, extending cartridge service life.

**APPENDIX B.5**  
**WATER BALANCE/INFILTRATION TRENCH**  
**CALCULATIONS**



<b>5 mm Volume Control Retention Calculation</b>
Block 6 2017-0569 Date: February 2021

Land Use	Area (ha)	m <sup>3</sup>
Paved	1.36	
Landscape	1.26	
5 mm retention per impervious area =		<b>68</b>
	<b>Area (m<sup>2</sup>)</b>	<b>Ponding/storage Depth (mm)</b>
Infiltration Trenches	600	300
Total		<b>72</b>



**Infiltration Trench Calculations**

South Brock Street Development  
File No. 2018-0302  
Date: February 2021

Refer to Water Balance Calculations based on Hydrogeological Assessment and Water Balance Study performed by WSP March 2021 for Actual Infiltration into the Trench. Trenches have conservatively been sized with the total volume provided above the infiltration values from the WSP Report.

Proposed Infiltration							
Total Roof Area directed to infiltration trenches (m2)	Total landscaped areas directed to infiltration trenches	Total Area	Total Max Volume Provided for Infiltration (m <sup>3</sup> )/year	Max Provided Depth to be infiltrated (mm/year)	Average rainfall (mm/year)	% of Annual rainfall	Depth retained (mm)
2288	1739	4027	2200	546	886	62%	6

Infiltration Trench ID	Contributing Drainage Area	Rainfall Depth to be infiltrated	Stone Porosity	Runoff Volume for Infiltration <sup>1</sup>	Infiltration rate <sup>3</sup>	Required Drawdown Time	Maximum Allowable Trench Depth <sup>4</sup>	Proposed Trench Depth <sup>5</sup>	Minimum Footprint Area for Infiltration <sup>6</sup>	Proposed Trench Width	Proposed Trench Length	Actual Footprint Area for Infiltration
	(m <sup>2</sup> )	(mm)		(m <sup>3</sup> )	(mm/hr)	(hr)	(m)		(m <sup>2</sup> )	(m)	(m)	(m <sup>2</sup> )
Trench Central	4027	6	0.40	24	34.5	48	4.14	0.30	201	7.50	80	600
	4027			24								

CVC & TRCA Low Impact Development Stormwater Planning & Design Manual  
Used to calculate maximum LID depth for infiltration (Pg 4-57)

$$d_{max} = \frac{i \times T}{V_r}$$

- d = Maximum stone depth of soakaway pit/infiltration trench (mm)
- i = Infiltration Rate (mm/hr)
- T = Drawdown time (48 hrs max.) (hr)
- V<sub>r</sub> = Void Space Ratio (typically 0.40 for 50mm clear stone)

CVC & TRCA Low Impact Development Stormwater Planning & Design Manual  
Used to calculate the minimum footprint area for infiltration (Pg 4-58)

where:

- A = Bottom area of soakaway pit/infiltration trench (m<sup>2</sup>)
- WQV = runoff volume to be infiltrated (m<sup>3</sup>)
- d = Maximum stone depth of soakaway pit/infiltration trench (m)
- V<sub>r</sub> = Void Space Ratio (typically 0.40 for 50mm clear stone)

$$A = \frac{WQV}{d \times V_r}$$

- Notes:
- 1 - Volume of runoff based on 2mm of rain across the drainage area. See Water Balance Calculation for details.
  - 2 - Safety factor from TRCA Stormwater Management Criteria Appendix C: Water Balance and Recharge (Table C 3)
  - 3 - Infiltration rate based on WSP Report. See report in Appendix A.
  - 4 - Max depth for a 48 hour draw down time see equation above
  - 5 - Proposed depth for soakaway pit/infiltration trench
  - 6 - Minimum trench bottom area, see equation 4.3 above

**Infiltration Trench Details**

Highest Observed Existing Grade Near Swale	Water Table	Max. Elevation of Infiltration System	Lowest Grade at Infiltration System	Available Depth	Proposed Depth of stone
(m)	(m)	(m)	(m)	(m)	(m)
270.74	270.74	271.74	272.18	0.44	0.30

APPENDIX B.6  
PHOSPHORUS CALCULATIONS

**Phosphorus Removal Calculations**

South Brock Street Development  
2018-0302  
January 20201

				Existing Phosphorus Loading Calculation			
Land Use	Area (ha)	P Coef (kg/ha/yr)	P Load (kg/yr)	BMP	Efficiency (%)	BMP P (kg/yr)	Notes
Hay Pasture	1.96	0.06	0.12	None	0	0.12	
Low Intensity Development	0.25	0.13	0.03	None	0	0.03	
<b>Total</b>	<b>2.21</b>					<b>0.15</b>	<b>Existing TP Load</b>
				Proposed Phosphorus Loading Calculation with BMP			
Land Use	Area (ha)	P Coef (kg/ha/yr)	P Load (kg/yr)	BMP	Efficiency (%)	BMP P (kg/yr)	Notes
High Intensity Residential	1.81	1.32	2.39	Storage, Jellyfish Filter	62%	0.91	
High Intensity Residential	0.11	1.32	0.15	None	0%	0.15	
High Intensity Residential	0.29	1.32	0.38	Storage, Jellyfish Filter, Infiltration Trench	65%	0.13	
<b>Total</b>	<b>2.21</b>					<b>1.19</b>	<b>Total Remaining TP Load</b>
				Proposed Phosphorus Loading Calculation without BMP			
Land Use	Area (ha)	P Coef (kg/ha/yr)	P Load (kg/yr)	BMP	Efficiency (%)	BMP P (kg/yr)	Notes
High Intensity Residential	1.81	1.32	2.39	None	0%	2.39	
High Intensity Residential	0.11	1.32	0.15	None	0%	0.15	
High Intensity Residential	0.29	1.32	0.38	None	0%	0.38	
<b>Total</b>	<b>2.21</b>					<b>2.92</b>	<b>Total Phosphorus Load without BMP</b>
						<b>1.72</b>	<b>Total Phosphorus Removed with BMP</b>
						<b>59%</b>	<b>Phosphorus removal</b>

$R = A + B - [(A \times B) / 100]$  (Equation 4-1)

Where:

- R = Total TSS Removal Rate
- A = TSS Removal Rate of the First or Upstream BMP
- B = TSS Removal Rate of the Second or Downstream BMP

Underground Storage	=	25	% Phosphorus Removal
Jellyfish Treatment (as per ETV results)	=	49	% Phosphorus Removal
Infiltration Trench	=	60	% Phosphorus Removal
Jellyfish in Combination with Underground Storage R=59+25-[(59x25)/100]	=	62	% Phosphorus Removal
Jellyfish in Combination with Underground Storage and Infiltration Trench R=69+60-[(69x60)/100]	=	85	% Phosphorus Removal

**Phosphorus Loading Summary**

Existing Conditions	0.15	kg/year
Proposed Conditions with no BMP	2.92	kg/year
Proposed Conditions with BMP	1.19	kg/year
Post Development % Phosphorus Removal	59%	

# Recharge Compensation Form

Application Details	
<b>Site Name (Developer):</b>	Westlane Development
<b>Site Location:</b>	Brock Street and Nelkydd Lane, Township of Uxbridge
<b>File/APID #</b>	APID 223153 and 223097
<b>Anticipated Construction Start:</b>	
<b>Subwatershed:</b>	
Phosphorous Balance	
<b>Kg/year</b>	1.19
Compensation Costs	
<b>Offsetting Value</b>	<b>2.5</b>
<b>Compensation Cost (P load *2.5*\$35,700)</b>	\$106,207.50
<b>Administration Fee (15%)</b>	\$15,931.13
<b>Total</b>	<b>\$122,138.63</b>

# PHOSPHORUS EXPORT COEFFICIENTS

Updated: September 2011

## Land-Use Specific Phosphorus Export Coefficients for Lake Simcoe Watersheds


Subwatershed		Annual Phosphorus Load (kg/ha/year)											
		Agricultural			Urban			Natural Heritage		Other			
		HayPasture	Cropland	Sod Farm / Golf Course	Low Intensity Development	High Intensity Comm/Ind	High Intensity Residential	Forest	Wetland	Quarry	Unpaved Road	Transition	Open Water
Monitored	Beaver River	0.04	0.22	0.01	0.19	1.82	1.32	0.02	0.02	0.16	0.83	0.04	0.26
	Black River	0.08	0.23	0.02	0.17	1.82	1.32	0.05	0.04	0.15	0.83	0.06	0.26
	East Holland	0.12	0.36	0.24	0.13	1.82	1.32	0.10	0.10	0.18	0.83	0.16	0.26
	Hawkestone Creek	0.10	0.19	0.06	0.09	1.82	1.32	0.03	0.03	0.10	0.83	0.04	0.26
	Lovers Creek	0.07	0.16	0.17	0.07	1.82	1.32	0.06	0.05	0.06	0.83	0.06	0.26
	Pefferlaw-Uxbridge Brook	0.06	0.11	0.02	0.13	1.82	1.32	0.03	0.04	0.04	0.83	0.04	0.26
	Whites Creek	0.10	0.23	0.42	0.15	1.82	1.32	0.10	0.09	0.08	0.83	0.11	0.26
Unmonitored	Barrie Creeks	0.07	0.19	0.12	0.13	1.82	1.32	0.05	0.05	0.08	0.83	0.06	0.26
	Georgina Creeks	0.12	0.36	0.24	0.13	1.82	1.32	0.10	0.10	0.08	0.83	0.16	0.26
	Hewitts Creek	0.07	0.19	0.12	0.13	1.82	1.32	0.05	0.05	0.08	0.83	0.06	0.26
	Innisfil Creeks	0.07	0.19	0.12	0.13	1.82	1.32	0.05	0.05	0.08	0.83	0.06	0.26
	Maskinonge River	0.07	0.19	0.12	0.13	1.82	1.32	0.05	0.05	0.08	0.83	0.06	0.26
	Oro Creeks North	0.12	0.36	0.24	0.13	1.82	1.32	0.10	0.10	0.08	0.83	0.16	0.26
	Oro Creeks South	0.07	0.19	0.12	0.13	1.82	1.32	0.05	0.05	0.08	0.83	0.06	0.26
	Ramara Creeks	0.07	0.19	0.12	0.13	1.82	1.32	0.05	0.05	0.08	0.83	0.06	0.26
	Talbot/Upper Talbot River	0.07	0.19	0.12	0.13	1.82	1.32	0.05	0.10	0.08	0.83	0.06	0.26
	West Holland	0.12	0.36	0.24	0.13	1.82	1.32	0.10	0.05	0.08	0.83	0.16	0.26

### Summary for 17 sub-watersheds

Min	0.04	0.11	0.01	0.07	1.82	1.32	0.02	0.02	0.04	0.83	0.04	0.26
Max	0.12	0.36	0.42	0.19	1.82	1.32	0.10	0.10	0.18	0.83	0.16	0.26
Average	0.084	0.230	0.147	0.131	1.820	1.320	0.061	0.060	0.092	0.830	0.083	0.260
Standard deviation	0.025	0.079	0.104	0.026	0.000	0.000	0.028	0.027	0.036	0.000	0.047	0.000




APPENDIX B.7  
OVERLAND FLOW ANALYSIS



**IBI GROUP**  
 Unit 300 – 8133 Warden Avenue  
 Markham ON L6G 1B3 Canada  
 tel 905 763 2322 fax 905 763 9983  
 ibigroup.com

**LEGEND**

- PROPERTY LINE
- PROPOSED STORM DRAINAGE AREA BOUNDARY
- PROPOSED OVERLAND FLOW DIRECTION



**EMERGENCY OVERLAND FLOW AREAS**  
 WESTLANE DEVELOPMENTS LTD.  
 SOUTH BROCK STREET DEVELOPMENT  
 TOWN OF UXBRIDGE  
 REGIONAL MUNICIPALITY OF DURHAM

DATE: JANUARY 2021	PROJECT No.: 2018-0302
SCALE: 1:1500	FIGURE No.: DAP-3



Overland Flow Analysis Section A-A

South Brock Street Development

File No. 2018-0302

Date: February 2021

Surface Type Coefficients

Coefficient:	0.9	Paved
Coefficient:	0.25	Grass

Storm Event	Catchment Area (ha)	Paved Area (ha)	Landscape Area (ha)	Composite C Scaled for 100 Year Event	Percent Impervious	Tc (min)	Rainfall Intensity	Flow (L/s)
100	0.79	0.60	0.19	0.93	76%	10	200.6	409



Overland Flow Analysis Section B-B

South Brock Street Development

File No. 2018-0302

Date: February 2021

Surface Type Coefficients

Coefficient:	0.9	Paved
Coefficient:	0.25	Grass

Storm Event	Catchment Area (ha)	Paved Area (ha)	Landscape Area (ha)	Composite C Scaled for 100 Year Event	Percent Impervious	Tc (min)	Rainfall Intensity	Flow (L/s)
100	0.32	0.23	0.09	0.90	72%	10	200.6	158



Prepared By: Tim Ng

**Overland Flow Analysis Section C-C**

South Brock Street Development

File No. 2018-0302

Date: February 2021

Surface Type Coefficients		
Coefficient:	0.9	Paved
Coefficient:	0.25	Grass



Storm Event	Catchment Area (ha)	Paved Area (ha)	Landscape Area (ha)	Composite C Scaled for 100 Year Event	Percent Impervious	Tc (min)	Rainfall Intensity	Flow (L/s)
100	1.66	1.15	0.51	0.87	69%	10	200.6	808

**Rectangle Weir (above the roadway )**

Height	0.20	Building Entrance elevation minus the high point on the road (271.65-271.44)
Length	7.1	
C	1.65	
Q Capacity (L/s)	<b>1048</b>	

**Rectangle Weir (boulevard)**


Height	0.20	Building Entrance elevation minus the high point on the road (271.65-271.44)
Length	6.03	Half boulevard length because these weirs are triangular
C	1.65	
Q Capacity (L/s)	<b>890</b>	



**IBI GROUP**  
 Unit 300 – 8133 Warden Avenue  
 Markham ON L6G 1B3 Canada  
 tel 905 763 2322 fax 905 763 9983  
 ibigroup.com

**LEGEND**

- PROPERTY LINE
- PROPOSED STORM DRAINAGE AREA BOUNDARY
- PROPOSED OVERLAND FLOW DIRECTION



**100 YEAR CAPTURE AREA PLAN**  
 WESTLANE DEVELOPMENTS LTD.  
 SOUTH BROCK STREET DEVELOPMENT  
 TOWN OF UXBRIDGE  
 REGIONAL MUNICIPALITY OF DURHAM

DATE: JANUARY 2021	PROJECT No.: 2018-0302
SCALE: 1:1500	FIGURE No.: DAP-4



100-Year Capture Analysis


Brock Street South  
2018-0302  
Mar-21

Drainage Area ID	# of CB Type	Single CB (in Sag), Double CB (in Sag), Gutter CB or Area Drain	High Capacity Grates	Total Area (ha)	Runoff Coefficient 'C'	100 Year Rainfall Intensity (mm/hr)	Gutter Slope (%)	Ponding Depth (m)	Open Flow Area m <sup>2</sup> (72% opening for high capacity grate)	Area Drain Open Area (m <sup>2</sup> )	Cross Slope (%)	T Value	Gutter Flow Capacity Per CB	Direct Flow In (L/s)	Overflow In (L/s)	Total Flow In (L/s)	Flow Capture Capacity (L/s)	Blockage Factor	Flow Capture Capacity Assuming Blockage (L/s)	Overflow (L/s)	Overflow Location
C1	2	Single CB	Yes	0.26	0.86	200.60	-	0.02	0.52	-	-	-	-	125	0	125	195	50%	97	28	C2
C2	2	Gutter CB	No	0.24	0.86	200.60	0.75	-	-	-	2.00	2.50	45.00	115	28	143	90	50%	45	98	C3
C3	2	Gutter CB	No	0.21	0.86	200.60	0.75	-	-	-	2.00	2.50	45.00	101	98	199	90	50%	45	154	C11
C4	1	Single CB	No	0.12	0.86	200.60	-	0.30	-	-	-	-	-	58	0	58	204	50%	102	0	C3
C5	1	Single CB	No	0.12	0.86	200.60	-	0.30	-	-	-	-	-	58	0	58	204	50%	102	0	C8
C6	2	Gutter CB	No	0.14	0.86	200.60	1.00	-	-	-	2.00	2.50	48.00	67	0	67	96	50%	48	19	C7
C7	2	Gutter CB	No	0.14	0.86	200.60	0.50	-	-	-	2.00	2.50	40.00	67	19	87	80	50%	40	47	C8
C8	1	Single CB	Yes	0.06	0.86	200.60	-	0.01	0.26	-	-	-	-	29	47	75	69	50%	34	41	C10
C9	2	Single CB	No	0.04	0.86	200.60	-	0.09	-	-	-	-	-	19	0	19	44	50%	22	0	C10
C10	2	Single CB	Yes	0.25	0.86	200.60	-	0.09	0.52	-	-	-	-	120	41	161	413	50%	207	0	C11
C11	2	Double CB	Yes	0.10	0.86	200.60	-	0.10	1.04	-	-	-	-	48	154	202	871	50%	436	0	N/A
C12	1	Single CB	No	0.02	0.86	200.60	-	0.15	0.26	-	-	-	-	10	0	10	120	50%	60	0	N/A
C13	1	Single CB	No	0.06	0.86	200.60	-	0.15	0.26	-	-	-	-	29	0	29	120	50%	60	0	N/A
C14	1	Single CB	No	0.08	0.86	200.60	-	0.15	0.26	-	-	-	-	38	0	38	120	50%	60	0	N/A
C15	1	Single CB	No	0.07	0.86	200.60	-	0.15	0.26	-	-	-	-	34	0	34	120	50%	60	0	N/A
C16	1	Single CB	Yes	0.13	0.86	200.60	-	0.15	0.26	-	-	-	-	62	0	62	267	50%	133	0	N/A
C17	1	Single CB	No	0.08	0.86	200.60	-	0.15	0.26	-	-	-	-	38	0	38	120	50%	60	0	N/A

## APPENDIX B.8


# CHANNEL CONVEYANCE CALCULATIONS





**LEGEND**  
 ▨ AREA TO CUT  
 ▨ AREA TO FILL

**CROSS SECTIONS**  
 H=1:100  
 V=1:10



**KEY MAP**  
N.T.S.

**GENERAL NOTES**

1. CONTRACT DOCUMENTS, SPECIFICATIONS AND APPLICABLE BYLAWS MUST BE KEPT ON SITE DURING CONSTRUCTION FOR REFERENCE.
2. THE CONTRACTOR MUST NOTIFY THE CONTRACT ADMINISTRATOR AND CONSTRUCTION AUTHORITY OF THE INTENT TO COMMENCE WORK AT LEAST 48 HOURS IN ADVANCE.
3. THE CONTRACTOR IS RESPONSIBLE FOR ALL UTILITY LOCATIONS.
4. LAYOUT PLOTS BE FORWARDED AND APPROVED BY THE CONTRACT ADMINISTRATOR.
5. THE USER OF REPRESENTATIVE SHALL BE PRESENT DURING CONSTRUCTION TO PROVIDE GUIDANCE ON INSTALLATION OF THE FINISHES.

**TIMING OF WORKS**

1. WORKS SHALL BE COMPLETED BETWEEN JULY 1ST TO MARCH 31ST.
2. THESE CONSTRUCTION SHALL BE COMPLETED OUTSIDE THE WINTER SEASON TO COMPLY WITH THE FEDERAL REGULATORY BEST MANAGEMENT PRACTICES (BMP) FOR CONSTRUCTION ACTIVITIES TO PREVENT EROSION AND SEDIMENTATION FROM BEING A SOURCE OF POLLUTION TO ADJACENT WATER BODIES.
3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MONITORING THE PROGRESS OF THE WORKS AND REPORTING TO THE CONTRACT ADMINISTRATOR AND CONSTRUCTION AUTHORITY.
4. COMPLETE THE WORKS WITH MINIMAL UNDESIRABLE INTERRUPTIONS ONCE THEY COMMENCE.

**SITE AND MATERIAL MANAGEMENT**

1. ALL CONSTRUCTION EQUIPMENT AND MATERIALS (IMPORTED OR EXCAVATED) NOT TO BE STORED AT LEAST 75 m FROM ANY WATERWAY OR SENSITIVE AREA AND THE ACTIVE STORAGE OR ON A DESIGNATED STORAGE AREA. STORAGE OF MATERIALS SHALL BE DONE IN A MANNER THAT DOES NOT CAUSE POLLUTION TO ADJACENT WATER BODIES.
2. STORAGE OF MATERIALS SHALL BE DONE IN A MANNER THAT DOES NOT CAUSE POLLUTION TO ADJACENT WATER BODIES.
3. STORAGE OF MATERIALS SHALL BE DONE IN A MANNER THAT DOES NOT CAUSE POLLUTION TO ADJACENT WATER BODIES.
4. STORAGE OF MATERIALS SHALL BE DONE IN A MANNER THAT DOES NOT CAUSE POLLUTION TO ADJACENT WATER BODIES.
5. STORAGE OF MATERIALS SHALL BE DONE IN A MANNER THAT DOES NOT CAUSE POLLUTION TO ADJACENT WATER BODIES.
6. STORAGE OF MATERIALS SHALL BE DONE IN A MANNER THAT DOES NOT CAUSE POLLUTION TO ADJACENT WATER BODIES.
7. STORAGE OF MATERIALS SHALL BE DONE IN A MANNER THAT DOES NOT CAUSE POLLUTION TO ADJACENT WATER BODIES.
8. STORAGE OF MATERIALS SHALL BE DONE IN A MANNER THAT DOES NOT CAUSE POLLUTION TO ADJACENT WATER BODIES.
9. STORAGE OF MATERIALS SHALL BE DONE IN A MANNER THAT DOES NOT CAUSE POLLUTION TO ADJACENT WATER BODIES.
10. STORAGE OF MATERIALS SHALL BE DONE IN A MANNER THAT DOES NOT CAUSE POLLUTION TO ADJACENT WATER BODIES.

**EROSION AND SEDIMENT CONTROL**

1. EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSTALLED PRIOR TO START OF WORKS.
2. EROSION AND SEDIMENT CONTROL MEASURES MUST BE MAINTAINED THROUGHOUT CONSTRUCTION AND MUST BE REMOVED UPON COMPLETION OF WORKS.
3. EROSION AND SEDIMENT CONTROL MEASURES MUST BE MAINTAINED THROUGHOUT CONSTRUCTION AND MUST BE REMOVED UPON COMPLETION OF WORKS.
4. EROSION AND SEDIMENT CONTROL MEASURES MUST BE MAINTAINED THROUGHOUT CONSTRUCTION AND MUST BE REMOVED UPON COMPLETION OF WORKS.
5. EROSION AND SEDIMENT CONTROL MEASURES MUST BE MAINTAINED THROUGHOUT CONSTRUCTION AND MUST BE REMOVED UPON COMPLETION OF WORKS.
6. EROSION AND SEDIMENT CONTROL MEASURES MUST BE MAINTAINED THROUGHOUT CONSTRUCTION AND MUST BE REMOVED UPON COMPLETION OF WORKS.
7. EROSION AND SEDIMENT CONTROL MEASURES MUST BE MAINTAINED THROUGHOUT CONSTRUCTION AND MUST BE REMOVED UPON COMPLETION OF WORKS.
8. EROSION AND SEDIMENT CONTROL MEASURES MUST BE MAINTAINED THROUGHOUT CONSTRUCTION AND MUST BE REMOVED UPON COMPLETION OF WORKS.
9. EROSION AND SEDIMENT CONTROL MEASURES MUST BE MAINTAINED THROUGHOUT CONSTRUCTION AND MUST BE REMOVED UPON COMPLETION OF WORKS.
10. EROSION AND SEDIMENT CONTROL MEASURES MUST BE MAINTAINED THROUGHOUT CONSTRUCTION AND MUST BE REMOVED UPON COMPLETION OF WORKS.

**DELETERIOUS SUBSTANCE CONTROL/SPILL MANAGEMENT**

1. PREVENT THE RELEASE OF DELETERIOUS SUBSTANCES INTO WATER, SOIL, CONCRETE, ASPHALT OR ANY OTHER SENSITIVE AREA THROUGHOUT CONSTRUCTION AND THROUGHOUT CONSTRUCTION.
2. PREVENT THE RELEASE OF DELETERIOUS SUBSTANCES INTO WATER, SOIL, CONCRETE, ASPHALT OR ANY OTHER SENSITIVE AREA THROUGHOUT CONSTRUCTION AND THROUGHOUT CONSTRUCTION.
3. PREVENT THE RELEASE OF DELETERIOUS SUBSTANCES INTO WATER, SOIL, CONCRETE, ASPHALT OR ANY OTHER SENSITIVE AREA THROUGHOUT CONSTRUCTION AND THROUGHOUT CONSTRUCTION.
4. PREVENT THE RELEASE OF DELETERIOUS SUBSTANCES INTO WATER, SOIL, CONCRETE, ASPHALT OR ANY OTHER SENSITIVE AREA THROUGHOUT CONSTRUCTION AND THROUGHOUT CONSTRUCTION.
5. PREVENT THE RELEASE OF DELETERIOUS SUBSTANCES INTO WATER, SOIL, CONCRETE, ASPHALT OR ANY OTHER SENSITIVE AREA THROUGHOUT CONSTRUCTION AND THROUGHOUT CONSTRUCTION.
6. PREVENT THE RELEASE OF DELETERIOUS SUBSTANCES INTO WATER, SOIL, CONCRETE, ASPHALT OR ANY OTHER SENSITIVE AREA THROUGHOUT CONSTRUCTION AND THROUGHOUT CONSTRUCTION.
7. PREVENT THE RELEASE OF DELETERIOUS SUBSTANCES INTO WATER, SOIL, CONCRETE, ASPHALT OR ANY OTHER SENSITIVE AREA THROUGHOUT CONSTRUCTION AND THROUGHOUT CONSTRUCTION.
8. PREVENT THE RELEASE OF DELETERIOUS SUBSTANCES INTO WATER, SOIL, CONCRETE, ASPHALT OR ANY OTHER SENSITIVE AREA THROUGHOUT CONSTRUCTION AND THROUGHOUT CONSTRUCTION.
9. PREVENT THE RELEASE OF DELETERIOUS SUBSTANCES INTO WATER, SOIL, CONCRETE, ASPHALT OR ANY OTHER SENSITIVE AREA THROUGHOUT CONSTRUCTION AND THROUGHOUT CONSTRUCTION.
10. PREVENT THE RELEASE OF DELETERIOUS SUBSTANCES INTO WATER, SOIL, CONCRETE, ASPHALT OR ANY OTHER SENSITIVE AREA THROUGHOUT CONSTRUCTION AND THROUGHOUT CONSTRUCTION.

**WORK AREA ISOLATION**

1. ALL WORK ISOLATION WORKS MUST BE COMPLETED IN THE DAY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.
2. ALL WORK ISOLATION WORKS MUST BE COMPLETED IN THE DAY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.
3. ALL WORK ISOLATION WORKS MUST BE COMPLETED IN THE DAY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.
4. ALL WORK ISOLATION WORKS MUST BE COMPLETED IN THE DAY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.
5. ALL WORK ISOLATION WORKS MUST BE COMPLETED IN THE DAY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.
6. ALL WORK ISOLATION WORKS MUST BE COMPLETED IN THE DAY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.
7. ALL WORK ISOLATION WORKS MUST BE COMPLETED IN THE DAY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.
8. ALL WORK ISOLATION WORKS MUST BE COMPLETED IN THE DAY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.
9. ALL WORK ISOLATION WORKS MUST BE COMPLETED IN THE DAY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.
10. ALL WORK ISOLATION WORKS MUST BE COMPLETED IN THE DAY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.

NO.	DATE	BY	REVISIONS
3.	20/10/27	LD	FIRST DETAILED DESIGN SUBMISSION TO LSRC
2.	MARCH 2019	LD	SECOND SUBMISSION LSRC
1.	AUGUST 2018	LD	FIRST SUBMISSION LSRC

DESIGNED BY: PV      CHECKED BY: PV  
 DRAWN BY: LD/BM      DATE: OCTOBER 27, 2020

**PAUL V. VILLARD**  
FRACTURING MEMBER  
0957

**GEO MORPHIX**  
36 Main Street North, PO Box 205  
Campbellville, Ontario L0P 1B0  
T: 416.920.0926  
www.geomorphix.com

**226 BROCK STREET EAST  
 WESTLANE DEVELOPMENT GROUP LTD.**

**BIOSWALE DESIGN  
 CROSS SECTIONS**

PROJECT No.: 20094      DRAWING No.: XS-1  
 SCALE: AS NOTED      SHEET 3 OF 6

**NOT FOR CONSTRUCTION**

## Worksheet for Section D-D

Project Description	
Friction Method	Manning Formula
Solve For	Discharge
Input Data	
Channel Slope	0.540 %
Normal Depth	1,700.0 mm

### Section Definitions

	Station (m)	Elevation (m)
	0+08	271.60
	0+12	270.20
	0+13	270.20
	0+14	269.90
	0+15	269.90
	0+16	270.20
	0+17	270.20
	0+25	271.80

### Roughness Segment Definitions

Start Station	Ending Station	Roughness Coefficient
(0+08, 271.60)	(0+25, 271.80)	0.035

#### Options

Current Roughness Weighted Method	Pavlovskii's Method
Open Channel Weighting Method	Pavlovskii's Method
Closed Channel Weighting Method	Pavlovskii's Method


#### Results

Discharge	30.69 m <sup>3</sup> /s
Elevation Range	269.9 to 271.8 m
Flow Area	15.4 m <sup>2</sup>
Wetted Perimeter	16.6 m
Hydraulic Radius	928.1 mm
Top Width	16.09 m
Normal Depth	1,700.0 mm
Critical Depth	1,406.0 mm
Critical Slope	1.344 %
Velocity	2.00 m/s
Velocity Head	0.20 m
Specific Energy	1.90 m
Froude Number	0.653

# Channel conveyance capacity


## Worksheet for Section D-D

Results	
Flow Type	Subcritical
GVF Input Data	
Downstream Depth	0.0 mm
Length	0.0 m
Number Of Steps	0
GVF Output Data	
Upstream Depth	0.0 mm
Profile Description	N/A
Profile Headloss	0.00 m
Downstream Velocity	0.00 m/s
Upstream Velocity	0.00 m/s
Normal Depth	1,700.0 mm
Critical Depth	1,406.0 mm
Channel Slope	0.540 %
Critical Slope	1.344 %



APPENDIX B.9  
EROSION AND SEDIMENT CONTROL

Drainage Area	2
Volume Required per ha	125
Volume Required (m <sup>3</sup> )	250
Length Provided (m)	20
Width Provided (m)	10.0
Depth (m)	1.4
Volume Provided (m <sup>3</sup> )	252
Length <20 m	OK
Width < 0.5L	OK
Volume Provided > Required	OK



**Rip Rap Sizing Calculations**

Brook Street South  
File No. 20/18-0302  
March 1, 2021

Max Drainage Area to Swale	2
Coefficient	0.25
5 Year Flow	149

Worksheet: Triangular Channel -- 1

Solve For: Normal/Depth

Friction Method: Manning Formula

Flow Area:	0.11	m <sup>2</sup>
Wetted Perimeter:	1.23	m
Hydraulic Radius:	0.09	m
Top Width:	1.17	m
Critical Depth:	0.22	m
Critical Slope:	0.02884	m/m
Velocity:	1.31	m/s
Velocity Head:	0.09	m
Specific Energy:	0.28	m
Froude Number:	1.34	
Flow Type:	Supercritical	

Channel Slope: 0.035


Normal Depth: 0.19

Left Side Slope: 3:00

Right Side Slope: 3:00

Discharge: 148.00

Calculation Successful!



Velocity is approximately 1.3 m/s on the steepest swale which has a d50 close to 0 therefore no riprap is required.



### Rock Check Dam Spacing

Brock Street South  
 File No. 2018-0302  
 March 17 2021

\*Rock Check Dams Spaced Every 0.5 m along swales

Slope of Swale (%)	Rock Check Dam Spacing (m)
0.1	500
0.2	250
0.3	167
0.4	125
0.5	100
0.6	83
0.7	71
0.8	63
0.9	56
<b>1.0</b>	50
1.1	45
1.2	42
1.3	38
1.4	36
1.5	33
1.6	31
1.7	29
1.8	28
1.9	26
<b>2.0</b>	25
2.1	24
2.2	23
2.3	22
2.4	21
2.5	20
2.6	19
2.7	19
2.8	18
2.9	17
<b>3.0</b>	17
3.1	16
3.2	16
3.3	15
3.4	15
3.5	14
3.6	14
3.7	14
3.8	13
3.9	13
<b>4.0</b>	13
4.1	12
4.2	12
4.3	12
4.4	11
4.5	11
4.6	11
4.7	11
4.8	10
4.9	10
<b>5.0</b>	10



# Weekly Erosion, Sediment, Pre Topsoil Stripping, Earthworks Report

PROJECT NAME:	_____	REPORT NO:	_____
PROJECT NO.:	_____	DATE AND TIME:	_____
TOWN PROJECT NO.:	_____	CIVIL CONSULTANTS:	_____
TOWN INSPECTOR(S):	_____	CONTRACTOR:	_____
		INSPECTOR(S):	_____

**FENCING (SILT, SNOW, TREE PRESERVATION):**

- Fences are located and installed as per Town of Markham Standards and the Sediment and Erosion Control Drawing Yes  No
- Fences require remedial action in the following areas: \_\_\_\_\_

**TEMPORARY SEDIMENT CONTROL PONDS/SWALES:**

- Required temporary sediment control ponds/swales are located as per the Sediment and Erosion Control Drawing Yes  No
- Required temporary sediment control ponds/swales are functioning as per the Sediment and Erosion Control Drawing Yes  No
- Temporary sediment control ponds/swales require remedial action in the following areas: \_\_\_\_\_

**CHECK DAMS:**

- Required Check Dams are located and constructed as per Town of Markham Standards and the Sediment and Erosion Control Drawing Yes  No
- Required Check Dams are functioning properly and are free of sediment build-up Yes  No
- Check Dams require remedial actions in the following areas: \_\_\_\_\_

**MUD MAT/ACCESS:**

- The Mud Mat/Access is located and constructed as per Town of Markham Standards, the Sediment and Erosion Control Drawing and the roadway is clean Yes  No
- The Mud Mat/Access is functioning properly and is free of excessive sediment build-up Yes  No
- The required traffic control signage is present around the Construction Access Yes  No
- The Mud Mat/Access requires the following remedial action: \_\_\_\_\_

**TREE PRESERVATION:**

- Tree Preservation Fences are located and installed as per Town of Markham Standards and the Sediment and Erosion Control Drawing Yes  No
- Tree Preservation Fences require remedial action: \_\_\_\_\_

**DUST CONTROL/ROAD CLEANING:**

- Dust Control Plan and Strategy is communicated with the Town of Markham and the Contractor Yes  No
- Road Cleaning Plan and Strategy is communicated with the Town of Markham and the Contractor Yes  No

**COMMENTS:**

\_\_\_\_\_

\_\_\_\_\_



\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_



# APPENDIX C ENGINEERING PLANS



**LEGEND**


PROPERTY LINE	---
PROPOSED GRADE	x 149.50
EXISTING GRADE	x 149.30EX
PROPOSED GRADE (TOP OF CURB)	x 149.65TC
PROPOSED GRADE (BOTTOM OF CURB)	x 149.50BC
PROPOSED GRADE (BOTTOM OF SWALE)	x 147.58SW
PROPOSED GRADE (TOP OF WALL)	x 147.58TW
PROPOSED SWALE	---
PROPOSED SLOPE (3:1 MAX.)	---
PROPOSED SANITARY MANHOLE	○
PROPOSED STORM MANHOLE	○
PROPOSED CATCH BASIN MANHOLE	○
PROPOSED CATCH BASIN	□
PROPOSED OGS	○
EXISTING MANHOLE	○
EXISTING CATCH BASIN	□
PROPOSED VALVE AND BOX	M V&B
PROPOSED FIRE HYDRANT	FH
PROPOSED SIAMESE CONNECTION	---
EMERGENCY OVERLAND FLOW ROUTE	---
EXISTING OVERLAND FLOW ROUTE	---
LOT NUMBER	---
HYDRO TRANSFORMER	---
SUMP PUMP	---
MINIMUM GOOSE NECK ELEVATION	---

**LIST OF DRAWINGS**

SG-01 - SITE GRADING PLAN
XS-01 - CROSS SECTIONS
XS-02 - CROSS SECTIONS
EC-01 - EROSION CONTROL PLAN - PHASE 1
EC-02 - EROSION CONTROL PLAN - PHASE 2
EC-03 - EROSION CONTROL PLAN - PHASE 3
EC-04 - EROSION CONTROL DETAILS
DD-01 - DETAILS
DD-02 - DETAILS

<b>SITE PLAN INFORMATION</b>	<b>SURVEYOR INFORMATION</b>
ICR ASSOCIATES INCORPORATED 12 SANDBOURNE CRESCENT TORONTO, ONTARIO M4W 4B5 PHONE: (416) 499-4422 E-MAIL: icr.dwg@gmail.com	H.F. GRANDER Co. LTD. 1575 HIGHWAY 7A WEST, UNIT 2A PORT FERRY, ONTARIO L1L 1A6 PHONE: (905) 965-3600 FAX: (905) 965-2347

NO.	REVISION	DATE	BY
4	ISSUED FOR SITE PLAN APPROVAL	SEP 03, 2021	LMV
4	ISSUED FOR SITE PLAN APPROVAL	MAR 19, 2021	PS
3	ISSUED FOR ZONING APPROVAL	MAR 15, 2019	LMV
2	ISSUED FOR COORDINATION	SEPT 5, 2018	TVL
1	ISSUED FOR ZONING APPROVAL	AUG 10, 2018	LMV















TOWN OF UXBRIDGE  
REGION OF DURHAM  
WESTLANE DEVELOPMENT GROUP LTD.  
SOUTH BROCK STREET DEVELOPMENT  
UXBRIDGE, ONTARIO

**SITE GRADING PLAN**

DESIGNED BY: LMV	DATE: JUNE 2018	CHECKED BY: JL
DRAWN BY: LMV	PROJECT No. 2018-0302	DRAWING No. SG-01
SCALE: 1:400		





LOCATION PLAN N.T.S.

LEGEND

LEGEND

LIST OF DRAWINGS

- SG-01 - SITE GRADING PLAN
- SS-01 - SITE SERVICING PLAN
- XS-01 - CROSS SECTIONS
- XS-02 - CROSS SECTIONS
- EC-01 - EROSION CONTROL PLAN - PHASE 1
- EC-02 - EROSION CONTROL PLAN - PHASE 2
- EC-03 - EROSION CONTROL PLAN - PHASE 3
- EC-04 - EROSION CONTROL DETAILS
- DD-01 - DETAILS
- DD-02 - DETAILS

SITE PLAN INFORMATION

SURVEYOR INFORMATION

ICR ASSOCIATES INCORPORATED  
12 SANDBOURNE CRESCENT  
TORONTO, ONTARIO M4K 4B5  
PHONE: (416) 499-9427  
E-MAIL: icr.dwg@gmail.com

H.F. GRANDER CO. LTD.  
1575 HIGHWAY 7A WEST, UNIT 2A  
PORT FERRY, ONTARIO L1L 1A6  
PHONE: (905) 965-3600  
FAX: (905) 965-2347

NO.	REVISION	DATE	BY
4	ISSUED FOR SITE PLAN APPROVAL	SEP 03, 2021	LMV
4	ISSUED FOR SITE PLAN APPROVAL	MAR 19, 2021	PS
3	RE-ISSUED FOR ZONING APPROVAL	MAR 15, 2019	LMV
2	ISSUED FOR COORDINATION	SEPT 5, 2018	TVL
1	ISSUED FOR ZONING APPROVAL	AUG 10, 2018	LMV











TOWN OF UXBRIDGE  
REGION OF DURHAM

WESTLANE DEVELOPMENT GROUP LTD.  
SOUTH BROCK STREET DEVELOPMENT  
UXBRIDGE, ONTARIO

CROSS SECTIONS

IBI GROUP  
Unit 300 - 8133 Warden Avenue  
Markham ON L3G 1B3 Canada  
tel 905 763 2322 fax 905 763 9983  
ibigroup.com

DESIGNED BY: LMV DATE: JUNE 2018 CHECKED BY: JL  
DRAWN BY: LMV PROJECT No. 2018-0302 DRAWING No. XS-01  
SCALE: 1:100



**LEGEND**

**LIST OF DRAWINGS**

SG-01 - SITE GRADING PLAN
SS-01 - SITE SERVICING PLAN
XS-01 - CROSS SECTIONS
XS-02 - CROSS SECTIONS
EC-01 - EROSION CONTROL PLAN - PHASE 1
EC-02 - EROSION CONTROL PLAN - PHASE 2
EC-03 - EROSION CONTROL PLAN - PHASE 3
EC-04 - EROSION CONTROL DETAILS
DD-01 - DETAILS
DD-02 - DETAILS

SITE PLAN INFORMATION		SURVEYOR INFORMATION	
ICR ASSOCIATES INCORPORATED 12 SANDBOURNE CRESCENT TORONTO, ONTARIO L4K 4B5 PHONE: (416) 499-9427 E-MAIL: icr.dwg@gmail.com		H.F. GRANDER Co. LTD. 1575 HIGHWAY 7A WEST, UNIT 2A PORT FERRIER, ONTARIO L1L 1A6 PHONE: (905) 965-8600 FAX: (905) 965-2347	

NO.	REVISION	DATE	BY
4	ISSUED FOR SITE PLAN APPROVAL	SEP 03, 2021	LMV
4	ISSUED FOR SITE PLAN APPROVAL	MAR 19, 2021	PS
3	RE ISSUED FOR ZONING APPROVAL	MAR 15, 2019	LMV
2	ISSUED FOR COORDINATION	SEPT 5, 2018	TVL
1	ISSUED FOR ZONING APPROVAL	AUG 10, 2018	LMV





TOWN OF UXBRIDGE  
REGION OF DURHAM

WESTLANE DEVELOPMENT GROUP LTD.  
SOUTH BROCK STREET DEVELOPMENT  
UXBRIDGE, ONTARIO

**CROSS SECTIONS**

IBI GROUP  
Unit 300 - 8133 Warden Avenue  
Markham ON L3G 1B3 Canada  
tel 905 763 2322 fax 905 763 9883  
ibigroup.com

DESIGNED BY: LMV	DATE: JUNE 2018	CHECKED BY: JL
DRAWN BY: LMV	PROJECT No. 2018-0302	DRAWING No. XS-02
SCALE: 1:100		



LOCATION PLAN  
N.T.S.

**LEGEND**

PROPERTY LINE	---
TEMPORARY SILT FENCE	- - - - - SF
PROPOSED SEDIMENT TRAP	[Hatched Box]
TEMPORARY ROCK CHECK DAM	[Rock Pattern]
TEMPORARY GRAVEL MUD MAT	[Gravel Pattern]


**LIST OF DRAWINGS**

SG-01 - SITE GRADING PLAN
SS-01 - SITE SERVICING PLAN
XS-01 - CROSS SECTIONS
XS-02 - CROSS SECTIONS
EC-01 - EROSION CONTROL PLAN - PHASE 1
EC-02 - EROSION CONTROL PLAN - PHASE 2
EC-03 - EROSION CONTROL PLAN - PHASE 3
EC-04 - EROSION CONTROL DETAILS
DD-01 - DETAILS
DD-02 - DETAILS

<b>SITE PLAN INFORMATION</b>	<b>SURVEYOR INFORMATION</b>
ICR ASSOCIATES INCORPORATED 12 SANDBOURNE CRESCENT TORONTO, ONTARIO L4K 4B5 PHONE: (416) 499-9427 E-MAIL: icr.dcs@gmail.com	H.F. GRANDER Co. LTD. 1575 HIGHWAY 7A WEST, UNIT 2A PORT FERRY, ONTARIO L1L 1A6 PHONE: (905) 965-3600 FAX: (905) 965-2347

4	ISSUED FOR SITE PLAN APPROVAL	SEP 03, 2021	LMV
4	ISSUED FOR SITE PLAN APPROVAL	MAR 19, 2021	PS
3	RE ISSUED FOR ZONING APPROVAL	MAR 15, 2019	LMV
2	ISSUED FOR COORDINATION	SEPT 5, 2018	TVL
1	ISSUED FOR ZONING APPROVAL	AUG 10, 2018	LMV



NO.	REVISION	DATE	BY



TOWN OF UXBRIDGE  
REGION OF DURHAM  
WESTLANE DEVELOPMENT GROUP LTD.  
SOUTH BROCK STREET DEVELOPMENT  
UXBRIDGE, ONTARIO

**EROSION CONTROL PLAN-STAGE 1**

DESIGNED BY: LMV	DATE: JUNE 2018	CHECKED BY: JL
DRAWN BY: LMV	PROJECT No. 2018-0302	DRAWING No. EC-01
SCALE: 1:400		



LOCATION PLAN  
N.T.S.

**LEGEND**

PROPERTY LINE	---
TEMPORARY SILT FENCE	---
PROPOSED SEDIMENT TRAP	[Symbol]
TEMPORARY ROCK CHECK DAM	[Symbol]
TEMPORARY GRAVEL MUD MAT	[Symbol]

**LIST OF DRAWINGS**

SG-01 - SITE GRADING PLAN
SS-01 - SITE SERVICING PLAN
XS-01 - CROSS SECTIONS
XS-02 - CROSS SECTIONS
EC-01 - EROSION CONTROL PLAN - PHASE 1
EC-02 - EROSION CONTROL PLAN - PHASE 2
EC-03 - EROSION CONTROL PLAN - PHASE 3
EC-04 - EROSION CONTROL DETAILS
DD-01 - DETAILS
DD-02 - DETAILS

SITE PLAN INFORMATION	SURVEYOR INFORMATION
ICR ASSOCIATES INCORPORATED 12 SANDBOURNE CRESCENT TORONTO, ONTARIO L4K 4B5 PHONE: (416) 499-9427 E-MAIL: icr.dwg@gmail.com	H.F. GRANDER Co. LTD. 1575 HIGHWAY 7A WEST, UNIT 2A PORT FERRY, ONTARIO L1L 1A6 PHONE: (905) 965-3600 FAX: (905) 965-2347



NO.	REVISION	DATE	BY
4	ISSUED FOR SITE PLAN APPROVAL	SEP 03, 2021	LMV
4	ISSUED FOR SITE PLAN APPROVAL	MAR 19, 2021	PS
3	RE ISSUED FOR ZONING APPROVAL	MAR 15, 2019	LMV
2	ISSUED FOR COORDINATION	SEPT 5, 2018	TVL
1	ISSUED FOR ZONING APPROVAL	AUG 10, 2018	LMV



TOWN OF UXBRIDGE  
REGION OF DURHAM  
WESTLANE DEVELOPMENT GROUP LTD.  
SOUTH BROCK STREET DEVELOPMENT  
UXBRIDGE, ONTARIO

**IBI GROUP**  
Unit 300 - 8133 Warden Avenue  
Markham ON L6G 1B3 Canada  
tel 905 763 2322 fax 905 763 9883  
ibigroup.com

DESIGNED BY: LMV	DATE: JUNE 2018	CHECKED BY: JL
DRAWN BY: LMV	PROJECT No. 2018-0302	DRAWING No. EC-02
SCALE: 1:400		



LOCATION PLAN  
N.T.S.

**LEGEND**

PROPERTY LINE	---
TEMPORARY SILT FENCE	--- SF
PROPOSED SEDIMENT TRAP	[Symbol]
TEMPORARY ROCK CHECK DAM	[Symbol]
TEMPORARY GRAVEL MUD MAT	[Symbol]

**LIST OF DRAWINGS**

SG-01 - SITE GRADING PLAN
SS-01 - SITE SERVICING PLAN
XS-01 - CROSS SECTIONS
XS-02 - CROSS SECTIONS
EC-01 - EROSION CONTROL PLAN - PHASE 1
EC-02 - EROSION CONTROL PLAN - PHASE 2
EC-03 - EROSION CONTROL PLAN - PHASE 3
EC-04 - EROSION CONTROL DETAILS
DD-01 - DETAILS
DD-02 - DETAILS

<b>SITE PLAN INFORMATION</b>	<b>SURVEYOR INFORMATION</b>
ICR ASSOCIATES INCORPORATED 12 SANDBOURNE CRESCENT TORONTO, ONTARIO L4K 4B5 PHONE: (416) 499-9422 E-MAIL: icr.dcx@gmail.com	H.F. GRANDER Co. LTD. 1575 HIGHWAY 7A WEST, UNIT 2A PORT FERRY, ONTARIO L1L 1A6 PHONE: (905) 965-3600 FAX: (905) 965-2347

NO.	REVISION	DATE	BY
4	ISSUED FOR SITE PLAN APPROVAL	SEP 03, 2021	LMV
4	ISSUED FOR SITE PLAN APPROVAL	MAR 19, 2021	PS
3	RE ISSUED FOR ZONING APPROVAL	MAR 15, 2019	LMV
2	ISSUED FOR COORDINATION	SEPT 5, 2018	TVL
1	ISSUED FOR ZONING APPROVAL	AUG 10, 2018	LMV













TOWN OF UXBRIDGE  
REGION OF DURHAM  
WESTLANE DEVELOPMENT GROUP LTD.  
SOUTH BROCK STREET DEVELOPMENT  
UXBRIDGE, ONTARIO

**EROSION CONTROL PLAN-STAGE 3**

DESIGNED BY: LMV	DATE: JUNE 2018	CHECKED BY: JL
DRAWN BY: LMV	PROJECT No. 2018-0302	DRAWING No. EC-03
SCALE: 1:400		

IBI GROUP  
Unit 300 - 8133 Warden Avenue  
Markham ON L6G 1B3 Canada  
tel 905 763 2322 fax 905 763 9883  
ibigroup.com





**LIST OF DRAWINGS**

SG-01 - SITE GRADING PLAN	
XS-01 - CROSS SECTIONS	
XS-02 - CROSS SECTIONS	
EC-01 - EROSION CONTROL PLAN - PHASE 1	
EC-02 - EROSION CONTROL PLAN - PHASE 2	
EC-03 - EROSION CONTROL PLAN - PHASE 3	
EC-04 - EROSION CONTROL DETAILS	
DD-01 - DETAILS	
DD-02 - DETAILS	

**SITE PLAN INFORMATION**

ICR ASSOCIATES INCORPORATED  
12 SANDBOURNE CRESCENT  
TORONTO, ONTARIO L4K 4B5  
PHONE: (416) 499-9427  
E-MAIL: icr.dwg@gmail.com

**SURVEYOR INFORMATION**

H.F. GRANDER Co. LTD.  
1575 HIGHWAY 7A WEST, UNIT 2A  
PORT PERRY, ONTARIO L6L 1A6  
PHONE: (905) 965-3600  
FAX: (905) 965-2347

4	ISSUED FOR SITE PLAN APPROVAL	SEP 03, 2021	LMV
4	ISSUED FOR SITE PLAN APPROVAL	MAR 19, 2021	PS
3	ISSUED FOR ZONING APPROVAL	MAR 15, 2019	LMV
2	ISSUED FOR COORDINATION	SEPT 5, 2018	TVL
1	ISSUED FOR ZONING APPROVAL	AUG 10, 2018	LMV










**TOWN OF UXBRIDGE**  
REGION OF DURHAM

WESTLANE DEVELOPMENT GROUP LTD.  
SOUTH BROCK STREET DEVELOPMENT  
UXBRIDGE, ONTARIO

**EROSION CONTROL DETAILS**

**IBI GROUP**  
Unit 300 - 8133 Warden Avenue  
Markham ON L6G 1B3 Canada  
tel 905 763 2322 fax 905 763 9983  
ibigroup.com

DESIGNED BY: LMV DATE: JUNE 2018 CHECKED BY: JL  
DRAWN BY: LMV PROJECT No. DRAWING No.  
SCALE: NTS 2018-0302 EC-04



**LIST OF DRAWINGS**






SG-01 - SITE GRADING PLAN
SS-01 - SITE SERVICING PLAN
XS-01 - CROSS SECTIONS
XS-02 - CROSS SECTIONS
EC-01 - EROSION CONTROL PLAN - PHASE 1
EC-02 - EROSION CONTROL PLAN - PHASE 2
EC-03 - EROSION CONTROL PLAN - PHASE 3
EC-04 - EROSION CONTROL DETAILS
DD-01 - DETAILS
DD-02 - DETAILS

**SITE PLAN INFORMATION**

ICR ASSOCIATES INCORPORATED  
12 SANDBOURNE CRESCENT  
TORONTO, ONTARIO L4K 4B5  
PHONE: (416) 499-9427  
E-MAIL: icr.dwg@gmail.com

**SURVEYOR INFORMATION**

H.F. GRANDER CO. LTD.  
1575 HIGHWAY 7A WEST, UNIT 2A  
PORT HURON, ONTARIO L1K 1A6  
PHONE: (800) 965-3600  
FAX: (800) 965-2347



4	ISSUED FOR SITE PLAN APPROVAL	SEP 03, 2021	LMV
4	ISSUED FOR SITE PLAN APPROVAL	MAR 19, 2021	PS
3	ISSUED FOR ZONING APPROVAL	MAR 15, 2019	LMV
2	ISSUED FOR COORDINATION	SEPT 5, 2018	TVL
1	ISSUED FOR ZONING APPROVAL	AUG 10, 2018	LMV

**PROFESSIONAL ENGINEER**  
M. ZDRAVEVSKI  
100130902  
2021-09-03  
PROVINCE OF ONTARIO

DESIGNED BY: LMV DATE: JUNE 2018 CHECKED BY: JL  
DRAWN BY: LMV PROJECT No. 2018-0302 DRAWING No. DD-01  
SCALE: NTS

